

UNIVERSITY OF TORONTO



3 1761 01751795 4













THE THEORY AND PRACTICE OF  
ENAMELLING ON IRON  
AND STEEL.

**NET BOOK.**—This book is supplied to the  
Trade on terms which will not allow of Discount  
to the Public.

CHARLES GRIFFIN & CO. LTD.

NET BOOK - This book is supplied to the

Trade on terms which will allow of Discount

to the Public

CHARLES GRIFFIN & CO. LTD.



THE THEORY AND PRACTICE OF  
ENAMELLING ON IRON  
AND STEEL.



## GRIFFIN'S TECHNICAL PUBLICATIONS.

- Elements of Chemical Engineering.** By J. GROSSMANN, M.A., Ph.D. With Preface by Sir WM. RAMSAY. 3s. 6d. net.
- Chemistry for Manufacturers.** By BERTRAM BLOUNT, F.I.C., and A. G. BLOXAM, F.I.C. SECOND EDITION. 16s.
- Oils, Fats, Butters, Waxes.** By C. R. ALDER WRIGHT, D.Sc. Revised by C. A. MITCHELL, B.A., F.I.C. SECOND EDITION. With 800 pages. 25s. net.
- The Clayworkers' Handbook.** In Cloth. With 30 Illustrations. 6s. net.
- Peat: Its Use and Manufacture.** By P. R. BJÖRLING and F. T. GISSING. Illustrated. 6s. net.
- Calcareous Cements.** By G. R. REDGRAVE and CHARLES SPACKMAN, F.C.S. SECOND EDITION. 15s. net.
- Handbook for Cement Works' Chemists.** By FRANK B. GATEHOUSE, F.C.S. In Handsome Cloth. 5s. net.
- Gas Manufacture.** By W. J. A. BUTTERFIELD. Vol. I., 7s. 6d.; Vol. II., *Shortly*.
- Acetylene.** By F. H. LEEDS and W. J. A. BUTTERFIELD. SECOND EDITION, Thoroughly Revised.
- Painting and Decorating.** A Complete Practical Manual. By W. J. PEARCE. THIRD EDITION, Revised and Enlarged. 12s. 6d.
- Painters' Colours, Oils, and Varnishes.** By G. H. HURST, F.C.S. FOURTH EDITION, Revised and Enlarged. 12s. 6d.
- Painters' Laboratory Guide.** By G. H. HURST, F.C.S. In Cloth. With Illustrations. 5s.
- Treatise on Colour Manufacture.** By GEORGE ZERR and Dr RÜBENCAMP. English Edition by Dr C. MAYER, of Burgdorf. Profusely Illustrated. 30s. net.
- The Manufacture of Rubber Goods.** By ADOLF HEIL and Dr W. ESCH. Translated by E. W. LEWIS, A.C.G.I. Illustrated. 10s. 6d. net.
- Leather Trades' Chemistry.** By S. R. TROTMAN, M.A., F.I.C. In Handsome Cloth. Fully Illustrated. 15s. net.
- Paper Technology.** By R. W. SINDALL, F.C.S. In Medium 8vo. Handsome Cloth. Illustrated. SECOND EDITION, Revised. 12s. 6d. net.
- Ink Manufacture.** By C. A. MITCHELL, B.A., F.I.C., and T. C. HEPWORTH. In Cloth. With Plates and Illustrations. 7s. 6d. net.
- Synthetic Dyestuffs, and the Intermediate Products from which they are Derived.** By J. C. CAIN, D.Sc., and J. F. THORPE, Ph.D. In Large 8vo. Cloth. Pp. i-xv+405. 16s. net.
- Smoke Abatement.** By WM. NICHOLSON, Chief Smoke Inspector, Sheffield. With Illustrations. 6s. net.
- Petroleum.** A Treatise on. By Sir BOVERTON REDWOOD, D.Sc., etc. SECOND EDITION, Revised and Greatly Enlarged. With Valuable Bibliography. 45s. net.
- A Handbook on Petroleum.** For Inspectors under the Petroleum Acts. By Capt. J. H. THOMPSON and Sir BOVERTON REDWOOD. SECOND EDITION. 8s. 6d. net.
- Oil Fuel: Its Supply, Composition, and Application.** By S. H. NORTH. Fully Illustrated. 5s. net.
- Trades' Waste: Its Treatment and Utilisation.** By W. NAYLOR, F.C.S., etc. Illustrated. 21s. net.
- Fire and Explosion Risks.** By Dr VON SCHWARTZ. In Cloth. 16s. net.

LONDON: C. GRIFFIN & CO., LTD., EXETER ST., STRAND, W.C.

TC  
Gru.

THE THEORY AND PRACTICE  
OF  
ENAMELLING ON  
IRON AND STEEL  
WITH HISTORICAL NOTES ON THE  
USE OF ENAMEL.

BY

JULIUS GRÜNWALD,

TECHNICAL CHEMIST AND WORKS MANAGER, LAFESCHÖTTE.

TRANSLATED BY

HERBERT H. HODGSON,

M.A. (Camb.), B.Sc. (Lond.), Ph.D. (Heidelberg),

LECTURER AND RESEARCH CHEMIST AT THE MUNICIPAL TECHNICAL  
COLLEGE, BRADFORD.




LONDON:  
CHARLES GRIFFIN & COMPANY, LIMITED  
EXETER STREET, STRAND.

1909

[All Rights Reserved.]

107389  
17/1/11





Digitized by the Internet Archive  
in 2007 with funding from  
Microsoft Corporation



## PREFACE.

THE manufacture of enamelled ware is carried on to greater extent in Germany and France than elsewhere. This treatise is from the pen of a German technologist of wide experience in enamel works, and who is now the chief chemist and director of large works in the French centre of the industry. The book deals more especially with the process of enamelling hollow-ware. It gives a description of the raw material used in enamelling; it explains the action and the effect of each substance, and states the chemical combinations which take place. A number of mixtures are given for obtaining given effects or colourings. The process of enamelling is followed up in detail from the mixing, melting, and grinding of the enamel components; the annealing and pickling of the sheets and castings; the application of the enamel; the burning, decorating, etc. It also compares utensils made of enamelled ware with similar ones made of nickel and aluminium.

The book abounds in instructive matter which throws much light on the intricacies of a branch of industry in which very few people are posted, and it is hoped that this English edition will be found of great service.

*October 1909.*



# CONTENTS.

CHAP.	PAGE
I. INTRODUCTION . . . . .	I
II. THE RAW MATERIALS . . . . .	5
III. PREPARATION OF THE ENAMEL . . . . .	50
IV. PREPARATION OF THE CRUDE WARE . . . . .	70
V. THE PROCESS OF ENAMELLING . . . . .	79
VI. FIRING THE ENAMELLED WARES . . . . .	88
VII. THE DECORATION OF ENAMELLED OBJECTS—	
PAINTING . . . . .	99
VIII. DECORATION OF ENAMELLED OBJECTS—PHOTO-	
CERAMICS. . . . .	103
IX. STATISTICS AND GENERAL INFORMATION . . . . .	110
APPENDIX — SHORT HISTORY OF THE ART OF	
ENAMELLING . . . . .	121
INDEX . . . . .	129





# THE THEORY AND PRACTICE OF ENAMELLING ON IRON AND STEEL.

---

## CHAPTER I.

### INTRODUCTION.

ENAMELLING, which was for too long regarded as an insignificant though interesting industry, has, commensurate with its extraordinary growth during the last ten to fifteen years, become of considerably increased interest and importance. An industry of which the total output in Germany alone is estimated at about £3,000,000 annually, and which directly employs 20,000 workers in that country and from 12,000 to 14,000 in Austria-Hungary, has established its title to economic existence.

Its growth dates from the time when the empirical worker in the factory was displaced by the scientifically trained technologist, who, investigating methods hitherto jealously guarded, developed them ; and our industry has this in common with most others of importance, that while earlier generations of workers

sought from an empirical standpoint to remove such defects as made themselves manifest, it is their successors, the trained men, who have succeeded in divining the cause of the faults and so removing them, and who, in addition, are able by a study of the chemical and physical properties of enamels to select the most suitable raw materials and use them to the best advantage.

In this manner the industry has not only been able to keep pace with the constantly advancing price of raw materials, such as felspar, tin, tin oxide, cobalt oxide, coal, sheet metal, and also wages, but by simplification of production and improved methods has won its way into popular favour and increased general use.

For the progress attained, however, it is not only the up-to-date worker that has to be thanked, but the fortunate circumstance that manufacturers have everywhere been found ready to encourage every advance, even by costly and often fruitless outlay. These men, with their untiring activity, have been a source of inspiration to their juniors ; and the latter, with sound theoretical knowledge and high ideals and aspirations, applied themselves to this new calling which had lain so long outside the beaten track of technical activity.

Trying work, many cares, and frequent reverses awaited their efforts ; but so much the greater was the sense of satisfaction when a new advance was chronicled, renewing the vitality of the industry, and indicating fresh channels for its development.



Owing to the exceptional nature of the enamel industry, its literary treatment has been but meagre in character, the existing literature being hitherto of very inferior quality, since it is either entirely obsolete, or at the most only up to the standard of the uninitiated. It is true that a few actual treatises for the worker are in existence,\* but in general one thinks of literature dealing with enamels as consisting more or less of disguised enamel formulæ. This degraded materialism on the part of the majority of experts may keep many a searcher after manufacturing recipes from the existing publications. It must be stated, moreover, that the publication of formulæ not only frequently entails a breach of confidence, but may also be absurd and misleading.

It is hardly necessary to state that one and the same formula is not suitable for all work, and that the chemical composition of the materials employed, of the sheet metal, the kind of fuel, the muffle and smelting furnaces, and the methods adopted in the enamel works themselves, have a definite influence on the composition of an enamel formula. The true expert will easily be able, after a short time, to prepare on demand the most suitable enamel possible for a given work. The difference between the formulæ often lies in quite small but nevertheless important deviations, since in essentials the nature of the formulæ is the same everywhere ; for the

\* I gladly make an exception in the case of the interesting economical study of Dr H. Wuppermann, on *The Industry of Enamelled Hardware in Germany*.

enamels are chemical compounds, which are only capable of variation between certain narrow limits. Again, value and knowledge are not to be gained from the formula-book, but from experience and intelligence.

Finally, the technologist's experience of the process is not his exclusive property, for though he may in the main thank his own intelligence, yet almost always his knowledge has been acquired at the owner's expense.

## CHAPTER II.

### THE RAW MATERIALS.

**Felspar.**—This important material is obtained almost exclusively at the present time from Norway. The felspar may often safely be replaced by an indigenous mineral such as one finds in Bohemia, where it occurs in sufficient quantity and purity. A good felspar should be colourless, or at the most appear faintly yellow (*Mosserfelspar*) or maroon, and should possess the following composition as nearly as possible :—

Siliceous earth.	.	.	65·0 per cent.
Alumina	.	.	18·0 „
Alkalies	.	.	16·5 „

The purer the felspar and the less it is contaminated by iron oxide, etc., the whiter will be the enamel.

The table on page 6 shows the composition of the felspars according to the locality where found.

As regards its use, the felspar should be obtained in lump only, as opposed to the increasing employment of powdered spar, for in this way only has one the certainty of always buying the same product, free from admixture with cheap quartz, etc. An

analysis made at the time of purchase is well worth doing, but the expert knows the nature and value of the felspar by merely looking at a specimen.

Two felspars, moreover, possessing the same chemical composition, may have a different influ-

	Felspar from					
	Norway.	Bohemia.	Halle.	Fichtelgebirge.	Bavaria.	France, Chanteloup.
Siliceous earth . . .	64.44	63.11	62.76	70.10	61.37	64.00
Alumina . . .	18.75	19.76	19.20	17.16	20.23	20.56
Lime and magnesia . . .	9.27	2.27	0.64	1.43	0.55	0.38
Potassium oxide . . .	13.82	14.57	14.90	1.52	15.75	14.99
Sodium oxide . . .	2.40	...	...	8.65	...	...
Iron oxide . . .	0.65	0.45	...	0.91	0.45	...
Water + waste . . .	...	...	1.70	...	1.31	...

ence upon the enamels prepared from them, according to the mines from which they are obtained. The cause of this phenomenon may depend on molecular conditions, but as yet has not been investigated.

The expensive and now obsolete process of making the felspar red-hot and then disintegrating it before grinding is superfluous. Great care must, however, be taken that the felspar is not contaminated by earthy matters, coal, etc., such as may be gathered from the ship and truck. In such cases the fragments of felspar may be sieved and washed.

The smaller pieces are ground apart for use in the preparation of ground or of blue enamels.



**Quartz.** — An important and usually unadulterated product which may safely be purchased in a powdered condition.

In many places the quartz has been replaced with advantage by beautiful white river-sand, bodies which chemically are silica, or, in other words, pure quartz. The best substitution, however, is made where enamels are prepared from river-sand, not from quartz.

Concerning the origin of the use of felspars, quartz, and especially clay little is known.

**Fluorspar.**—Only the best and purest qualities of fluorspar or calcium fluoride may be employed, especially for white enamels. The difference in price between the various qualities is not material, in view of the relatively small amounts of fluorspar consumed. Great care must be exercised in taking the correct quantities, since excess of lime is always detrimental ; while for ground-enamels fluorspar is avoided as far as possible.

**Borax.**—This compound has the advantage of being less complex, more agreeable, and more certain in its action than a mixture of boric acid and soda. Borax crystallising in the monoclinic system with ten molecules water of crystallisation ( $\text{Na}_2\text{B}_4\text{O}_7 + 10\text{H}_2\text{O}$ ) must be distinguished from that crystallising in the regular system and containing only five molecules of water.

We are only concerned with the former substance, which melts at a red heat with a loss of 47 per cent. of its water of crystallisation, and dissolves

easily in hot water (200 parts of borax in 100 parts water). Specific gravity = 1.69.

Borax must not be stored in a position exposed to the air, as it attracts moisture, alters in weight, and so causes an error in admixture. For the same reason the moisture content of a borax consignment is determined at the time of its arrival, in order eventually to obtain compensation from the consignor. Up to as much as 6 per cent. of moisture may be fixed during transit, and the effect of this in a large enamel works needs no further discussion.

Borax is imported in the form of very fine powder. In those works which manufacture their own borax, it is carefully dried by being left a sufficient time in the centrifugal machine, and then ground as fine as grain. The finer the powdered borax is, the more intimate will be the mixture with the remaining enamel constituents, and in consequence the more uniform and beautiful the enamel. Generally speaking, the preparation of one's own borax is inadvisable, since various disturbing factors may arise; but, in addition, the manufacture of too many separate products for home consumption is not economical. Here the law governing division of labour consequent on specialisation holds good, and those chemical firms which are engaged more or less exclusively in the manufacture of borax, the production of metallic oxides, colours, etc., will always be more capable of taking up work or of entering into competition.

**Boric Acid.**—In places where boric acid is used, the chemically prepared pure substance, which never changes in character, is preferred to the discoloured Tuscan variety.

**Soda and Potash.**—These bodies give the enamel a bright lustre, but excess must be carefully guarded against. Soda is to be preferred to the more expensive potash (potassium carbonate), since the action is identical. The term soda is used for the body corresponding to the chemical formula  $\text{Na}_2\text{CO}_3 + 10\text{H}_2\text{O}$ , but in practice only calcined soda is employed, being anhydrous sodium carbonate in powdered form.


This calcined soda, containing 41 per cent. carbonic acid and 59 per cent. sodium oxide, is stored in a dry place, since it is highly deliquescent and liable to form lumps. As in the case of borax, so with soda: only a very finely powdered condition is employed.

**Saltpetre.**—Sodium-saltpetre ( $\text{NaNO}_3$ ) is cheaper than the potassium salt ( $\text{KNO}_3$ ) and acts in identically the same manner. It is added in quite small quantities to the enamel mixture, and its primary function is to decolourise. To blue enamel very little saltpetre is added, or, even better, none at all. After common salt, the most hygroscopic body is saltpetre, and this is stored in boxes lined with tin-plate and capable of being made air-tight.

**Cryolite.**—Both natural and artificial cryolite are procured and employed for this industry. Recently many sodium silico-fluorides have been



used, these being obtained for the most part as by-products in the manufacture of artificial manures, etc. In the above, the removable hydro-fluor-silicic acid is taken up by water, and the sodium silico-fluoride precipitated from this solution by the addition of soda. Many works use common salt for the same purpose. Before using such a sodium silico-fluoride, a warning must be given that sodium chloride is always present, and a sodium silico-fluoride prepared through the agency of common salt is recognised by its poor colour and disagreeable odour. A simple analysis such as the following quickly shows the presence of chlorine. A sample of the body in question is boiled with distilled water, filtered, the filtrate acidified with a little chemically pure nitric acid, and a few drops of lunar caustic or silver nitrate solution added, whereby a chloride will separate out as a white, curdy precipitate. A faint white turbidity indicates nothing. A convenient quantitative method for estimating sodium silico-fluoride is as follows :—A weighed amount is taken, dissolved in hot water, and the solution titrated with 2N (twice normal) caustic soda, using phenolphthalein as indicator. The calculation of the amount of pure sodium silico-fluoride present is given by the following equation :—



Commercial sodium silico-fluoride contains 90–95 per cent., and has been employed with much success, partly displacing the natural cryolite, although for

more expensive wares, and in the case of blue enamel, the natural cryolite is preferable.

The so-called artificial cryolite which is used possesses a variable composition, depending on the vendor and on the price. The more inexpensive it is, the more quartz or silica it will contain, so that here good quality and cheapness do not go together.

One sample of an artificial cryolite had the following composition :—

- (1) 95 per cent. sodium-aluminium fluoride  
( $6\text{NaF} + \text{Al}_2\text{F}_6$ ).  
5 „ silica.

For manufacturing purposes this quality is most suitable, and almost entirely corresponds to natural cryolite. The ratio of  $\text{Al}_2\text{F}_6 : \text{NaF} = 40 : 60$ , *i.e.* normal.

Another sample was made up as follows :—

- (2) 80 per cent. sodium-aluminium fluoride.  
20 „ valueless quartz.

Naturally this was less expensive.

Finally, a still further interesting composition was exhibited by another variety :—

- (3) 18 per cent.  $\text{Al}_2\text{F}_6$  (aluminium fluoride).  
50 „  $\text{NaF}$  (sodium fluoride).  
32 „  $\text{SiO}_2$  (silica or quartz).

A fourth contains :—

- (4) 26 per cent.  $\text{Al}_2\text{F}_6$ .  
40 „  $\text{NaF}$ .  
32 „  $\text{SiO}_2$ .

From the above examples we learn possible variations and causes of failure in enamel preparation. It would not be correct, however, to deny every advantage to artificial cryolite, for when the composition is similar to No. 1 above, then the natural cryolite may be safely replaced, if the difference in price allows. When making a purchase there must be a guarantee as to the composition of the product, and frequently an analysis is desirable.

It is obvious what an injurious effect a cryolite substitute containing 32 per cent. quartz must have in the preparation of enamels by an unsuspecting manufacturer who, unwittingly increasing the silica content of his enamels, obtains an insufficiently opaque product.

Natural cryolite occurs as a beautiful mineral in masses having a milky-white appearance ; it is greasy to the touch, its specific gravity varies from 8.5 to 8.9, and its degree of hardness is 3. Cryolite may readily be scratched by the finger, crystallises in the monoclinic system, and is easily fusible.

The warning uttered in the case of felspar is still more necessary for natural cryolite, for it is always purchased in lumps and never as powder. Before use, the cryolite is carefully ground under personal supervision and mixed in a very finely powdered condition. Cryolite and its artificial substitutes act as fluxes, yet at the same time produce a more opaque enamel. In the preparation of white enamel the amount used must not exceed 15 per cent.



**Ammonium Carbonate.**—Many firms, when mixing their white enamels, add 3 to 4 per cent. of ammonium carbonate. Opinion as to the value of this varies enormously. On the one hand, the fact is put forward that ammonium carbonate volatilises on heating, and therefore its addition is pure waste, especially as the product is somewhat expensive. This is perfectly correct, with, however, certain reservations. On the other hand, it has been firmly established that the addition of ammonium carbonate to the enamel mixture has a favourable influence, since the action of the ammonium carbonate may be observed. The enamel is more uniform, and the so-called cracking (*Reifzen*) on firing is avoided. It is true that this actual result of experience still requires an explanation, for more than fifty years ago Moritz Vogelsang confirmed the observation in his interesting little work on *The Art of enamelling Iron* (*Die Eisenemaillierkunst*), and put forward the following explanation of the data obtained. He writes: "In all probability the effect of the ammonium carbonate may only be explained by cohesion, which force operates until the particular moment is attained at which the cracking (*Reifzen*) of the enamel ceases."

I gladly utilise the opportunity, as I now write about M. Vogelsang, to express half a century later my highest appreciation of his work—an appreciation which is rightly due to the man who nearly sixty years ago put forward, in his now antique little book, ideas and opinions which appear to me to be

as full of valuable information as all the later and more recent publications. Vogelsang was the first writer who, from a scientific standpoint, gave us in a neat and concise form knowledge of the enamels and their raw materials.

**Stannic Oxide.**—This is an absolute necessity. Continual experiments, made with the object of replacing it by less expensive products, have without exception always resulted in a return to the original. At the present time it is almost exclusively added at the mill.

The ordinary method of preparation is by the gradual surface oxidation of perfectly pure tin in the blast furnace. 100 kilos. of tin yield 124–126 kilos. tin oxide.

Often small black specks are found in the enamel after covering and baking, which spoil the general appearance of the wares. These may be traced to dust, magnesia, etc., but in general they are caused by small specks of non-oxidised metallic tin, which may easily be present in imperfectly prepared stannic oxide. As soon as these imperfections are noticed the following investigation should be conducted :—

One kilo. stannic oxide is washed with water, or, more fully described, it is made into a paste and water allowed to run into it, accompanied by a vigorous stirring, periodically varied by being allowed to settle for about 10 seconds. The stannic oxide is carried away by the water, and the process of washing is continued, always more cautiously, until the decanted water appears clear. At the

bottom of the vessel a grey, granular residue of metallic tin is left, which, being specifically heavier than the oxide, settles more quickly during the washing. This residue is collected, dried, and weighed, and the vendor who supplied it made answerable for the discrepancy. In many samples of stannic oxide the presence of up to 20 grammes of metallic tin per kilo. may be proved, *i.e.* 2 per cent.

During the manufacture of stannic oxide it may happen that particles of tin are only oxidised superficially, and inside may still be a nucleus of tin. In consequence of this the stannic oxide, where manufactured, is continually sieved and heated to redness in a special oven.

Different products, appearing on the market under diverse names, have been proposed as partial substitutes for the expensive stannic oxide, but a genuine success in this direction has yet to be recorded. The degree of opacity given by bone-ash or calcium phosphate is inadequate, while such a large amount of these substitutes must be added that the enamel is rendered absolutely useless. These facts caused me to try the antimony oxide derivatives, such as white antimony oxide, leukonin (potassium metantimoniate), etc., etc. The possibility of producing opacity by the above products is beyond question, yet we are met by the fact that their availability for use as an addition to the grinding is very restricted. If more than 4-5 per cent. be added to the mixture, the enamel will have its covering power diminished, and also be uneven



and slimy. Still, however, antimony is the best partial substitute for replacing tin oxide.

As one is aware, the use of antimony and lead compounds in the preparation of enamels is forbidden in many countries, and this is the case in Germany and Austria-Hungary (the particular countries in which enamelled culinary utensils are manufactured). In the first place we have to bow before the authority of the law and avoid such compounds, while in the second place we are not able to take an independent position on the question of the use of antimony preparations as complete or partial substitutes for stannic oxide. And on this latter point we are involuntarily driven to the following train of thought :—The price of tin, as also of stannic oxide, is rising in alarming fashion, apart from the momentary unestablished speculative tendency, and stannic oxide has an important rôle in the expenditure of an enamel works. The price of raw material is increasing, wages are rising, and the selling price of enamelled goods is falling, or at the best of times remaining stationary.

Why is the use of products forbidden which give a somewhat better chance to the manufacturer of making headway against adverse market conditions, when civilised countries of the first rank, such as England, France, Belgium, America, etc.—models with regard to hygiene and other similar subjects—allow the use of antimony compounds ?

A really correct explanation would be difficult to give. It is said that antimony compounds are

poisonous ; yet, granted that this may be the case, it is only true for soluble antimony compounds, and even then very large quantities are necessary in order to constitute a real danger to health. For example, an enamel contains 10 per cent. oxide of antimony, and a medium-sized cooking-pot of 5 litres content is enamelled inside with this enamel. For enamelling the interior of such a vessel about 100 grammes, say 120 grammes, of white enamel are necessary, and this would therefore contain 12 grammes antimony oxide. Now, antimony oxide is insoluble in water and very sparingly soluble in acids. Analyses have proved that on boiling for half an hour with 4 per cent. acetic acid no antimony has been dissolved, and even in particular cases where solution has taken place the amount dissolved was infinitesimal. Moreover, the antimony oxide in the enamel forms an insoluble compound with the silicates present.

Again, no mention has been made of any injurious action. In France, Belgium, etc., no single instance can be found, even of a case of very slight poisoning.

The danger due to antimony oxide in enamels is a fable as far as practice is concerned, like the famous, or infamous, romance of a French apothecary, who ascribed appendicitis (inflammation of the appendix) to the action of enamel splinters.

It matters not to us, who may enjoy, with a calm conscience, food which has been prepared in cooking-utensils coated with enamel containing antimony.

The fact that tin is becoming more and more scarce, and therefore more expensive, shows the need for a modification of the legislation by which antimony preparations are prohibited. Whether, indeed, much would be gained in the event of tin oxide being completely replaced by antimony compounds, remains to be seen. At present the enamel industry is one of the principal consumers of tin, and so soon as the demand for tin quite ceases the price must fall ; while on the other hand that of antimony will materially rise, so that in such a case prudence and caution will be necessary.

**Lead Oxide—Compounds.**—Notwithstanding its valuable property as a flux, this is absolutely valueless in the form of calx (a mixture of tin and lead calcined) for producing opacity, on account of being detrimental to health. Our potters, by their wanton use of lead-glaze, have for generations caused mischief enough.

The gradual but successful supplanting of lead-glazed earthenware by the absolutely uninjurious, inexpensive, and more durable enamelled wares must, from the standpoint of hygienic economy, be regarded as an important advance. Here the objection could be raised against any restriction being made to the use of the beautiful, inexpensive lead-glaze for certain enamelled wares which are not concerned with the kitchen, such as sanitary articles, baths, door-plates, etc.

Theoretically, nothing could be said against it ; but in practice, where in the same enamel works



kitchen utensils and door-plates are made, the line of distinction between the different enamel preparations (those free from lead or those containing it) is not sharply drawn. An enamel containing lead, which at the outset may appear as beautiful as the rest, is unstable when exposed to weather, and at the present time it may safely be asserted that in no enamel works are lead preparations employed.

A simple experiment may be performed for the identification of traces of lead in an enamel.

A place on the enamelled object is spotted with a few drops of chemically pure nitric acid, and heated over a flame until the nitric acid is driven off, then moistened with distilled water and a few drops of a 10 per cent. solution of potassium iodide added. Traces of lead present cause an intense yellow discoloration, owing to the formation of lead iodide, which must be insoluble in ammonia.

While reviewing the bodies which produce opacity, our attention is involuntarily drawn to the well-known property which titanium oxide possesses of causing intense opacity in enamels. The initial product is rutile, a brown-coloured mineral, consisting of about 94 per cent. titanous acid and 6 per cent. iron oxide. The use of rutile for causing opaqueness only meets with strictly limited success, in the form of a maximum addition of 1 per cent. to the mixture, for the iron oxide present excludes all further use. For years a method has been sought of preparing

chemically pure titanitic acid from rutile, but the first products which appeared on the market years ago always possessed a faint yellowish-green colour and were expensive in addition, 1 kilo. of pure titanitic acid costing as much as 15 marks (15s.). Many years back the firm of Wuppermann took out a patent for decolourising the enamels containing titanitic acid; but the question remained a purely academic one, since it was not found possible to prepare inexpensively pure white titanitic acid. Dr C. Dreper\* a few years ago took out a patent in Freiberg. He prepared titanitic acid by treating rutile with dilute sulphuric acid and sodium bisulphate, and then submitting the filtered solution to electrolysis. He placed the kathode in the filtered solution, and the anode in acidulated water, the liquids being separated by a porous cell, while the electrodes were of lead. A period of inactivity now took place until recently, when a method was patented by the chemical firm of Güstrow in Mecklenburg,† entitled "A process for the preparation of white opaque enamel and white opaque glass by the use of titanitic acid as opacity-producing agent." The titanitic acid prepared by this firm is pure white, and is moreover inexpensive, so that one can look forward to experimenting and gaining experience with it. The above firm has also introduced the barium salt of titanitic acid to the trade, and this appears to be full of promise. This titanitic acid may be added

\* D. R.-P. Nr. 152,257, Kl. 12i.

† D. R.-P. C. 15,243, Kl. 48c.

with advantage, up to 10 per cent., to an enamel during the grinding, and the enamel should be prepared as far as possible without saltpetre, but with the addition of 10 grms. of cobalt oxide to the mixture. Cases will arise in an enamel works requiring the closest attention for this material in order to discover the most suitable mode of employment. Titanium oxide appears to impart to the enamel favourable physical properties. An investigation should be made with the above to find out if the question of producing a lighter, more opaque ground-enamel is capable of a better solution, since the disturbing properties of tin oxide make these characteristics impossible.

**Cobalt Oxide.**—This is one of the most ancient and precious of the ceramic colouring oxides. The intensity of the blue tint depends on the quantity present, and on the chemical composition of the respective cobalt oxides.

In the preparation of blue enamels more than 1 per cent. is seldom employed. On the market the following types are discriminated according to price and chemical composition :—

FHKO. The purest cobaltic oxide =  $\text{Co}_2\text{O}_3$  containing 71 per cent. Co.

FKO. Pure cobaltic oxide =  $\text{Co}_2\text{O}_3$  containing 60–65 per cent. Co.

RKO. Black cobalto-cobaltic oxide =  $\text{Co}_3\text{O}_4$  containing 73 per cent. Co.

GKO. Dark grey cobaltous oxide =  $\text{CoO}$ .



KOH. Basic hydrated cobaltic sesqui-carbonate  
 $= \text{Co}_2\text{O}_3(\text{CO}_3)_2 + 4\text{H}_2\text{O}$  containing 45  
 per cent. Co.

PKO. Red cobaltic phosphate  $= \text{Co}_3(\text{PO}_4)_2 +$   
 $8\text{H}_2\text{O}$  containing 34 per cent. Co.

PO. Cobaltous oxide (protoxide)  $= \text{CoO}$  con-  
 taining 59 per cent. Co.

AKO. Cobaltic arsenate  $= \text{Co}(\text{AsO}_4)_2 + 8\text{H}_2\text{O}$   
 containing 30 per cent. Co.

The value of the cobalt oxide depends upon the percentage content of metallic cobalt.

In order to make the best use of cobalt oxide for the manufacture of deep-blue enamels, a most intimate and continual mixing of the raw materials is necessary, so that the cobalt oxide is actually distributed as finely as possible throughout the enamel.

The most important of the pioneering countries engaged in the production of this valuable oxide are England and Germany.

Cobalt oxide possesses valuable physical characteristics which especially make it suitable for the preparation of ground-enamels, for these derive the property that their coefficients of expansion are as near as possible the same as sheet iron. The modern enamel firms, seeking to replace expensive materials by cheaper ones having the same influence, have replaced cobalt oxide with success in the ground-enamels by the much less expensive nickel oxide. The price-ratio of the two oxides is about as 10 : 1·2.

At this point a short theoretical diversion may be allowed to establish thoroughly by what quantities the cobalt oxide must be replaced by nickel oxide in a ground-enamel, so that the physical properties of the same may remain unaltered.

According to the law of P. Joubin, the product of the specific heat multiplied by the specific gravity of a body is proportional to the product of the modulus of elasticity and the coefficient of linear expansion of the specific heat = the quantity of heat, expressed in calories, which is necessary to raise a mass of 1 kilo. through  $1^{\circ}$  C.

Further, the product atomic heat multiplied by specific heat of unit volume  $\times \left( \frac{\text{atomic volume}}{3} \right) =$

$$\left[ \text{Melting point} \times \frac{(\text{specific heat of unit volume})}{1.28} \right].$$

The specific heat =  $0.1737$  for iron.

For cobalt at  $900^{\circ}$  C. the specific heat is :

$$S_m = 0.1444.$$

For nickel at  $900^{\circ}$  C :

$$S_m = 0.13707.$$

Therefore, in order to raise 1 grm. of cobalt through  $1^{\circ}$  C.,  $0.1444$  calories are required ; while to raise 1 grm. of nickel through the same range of temperature  $0.13707$  calories are needed.

Weber states that the requisite amount of heat necessary to raise a body from zero to its melting

point (reckoned for the atomic weight) is inversely proportional to its coefficient of cubical expansion, and therefore the coefficient of cubical expansion

for cobalt =  $\frac{1}{0.1444} = 6.92$ , while for nickel it is

$$\frac{1}{0.13707} = 7.29.$$

From the ratio of the coefficient of cubical expansion of nickel to that of cobalt we have :

$$0.1444 : 0.13707 = 1.052 \text{ grms.}$$

$$7.29 : 6.92 = x : 1$$

$$\therefore x = \frac{7.29}{6.92} = 1.053 \text{ grms.}$$

Concerning expansion, then, 1.053 grms. nickel will correspond for all practical purposes to 1 gram. of cobalt, or 100 grms. cobalt oxide may be replaced by 106 grms. nickel oxide in the preparation of a ground-enamel.

**Limonite.**—This in the pure state is manganese peroxide ( $\text{MnO}_2$ ), but as a mineral it is known as pyrolusite. It is employed for decolourising white enamels which are discoloured. By the addition of larger quantities beautiful dark violet enamels are obtained, while iron oxide together with limonite produces lovely brown to black results. The limonite reacts by giving off oxygen, *i.e.* it is an ordinary oxidising agent.

Only the purest and best market samples are used, since the difference in price is trifling compared with the greatly enhanced results.



When fused in small quantities with the ground-enamel it works very favourably, and in like manner it is added to molten blue enamels in order to save cobalt oxide, for, as the cobalt content diminishes and the manganese addition is increased, the blue enamel takes a bluish-violet to reddish-blue glistening colour.

**Ferric Oxide.**—This is prepared by heating to redness protosulphate of iron or ferrous sulphate. According to the temperature employed, shades ranging from bright red to reddish violet are obtained.

The less the ferric oxide has been heated, the lighter will be the shade produced, so that great care must be exercised during the operation. More or less sulphuric acid is always present in the iron oxide, caused by incomplete decomposition, and therefore due to insufficient heating. On digesting with hot water, the bulk of the above may be removed, but this is the manufacturer's business. Insufficient heating of the iron oxide causes red enamel to be dull, and this, when stored as a finished product, acquires a permanent white efflorescence containing alkali sulphate. This white growth possesses a saline taste.

A qualitative test for free sulphuric acid, and also for the undecomposed sulphate in the ferric oxide, is easily made, viz. :—A few grammes of the ferric oxide compound to be tested are boiled with distilled water in a test-tube, and after filtration a few drops of chemically pure hydrochloric acid are added to the

filtrate. On the addition of a few cubic centimetres of a 10 per cent. barium chloride solution, the sulphuric acid is precipitated as barium sulphate, which is white. Should only a slight turbidity arise, then the iron oxide may safely be used.

Beautiful pure red iron oxide is formed when, to a boiling solution containing 17 parts soda to 68 water, 10 parts of crystallised ferrous sulphate are added gradually, the mixture being well stirred, then filtered, washed, allowed to oxidise in the air, spread in thin layers, and finally heated to redness.

The finest ferric oxide is prepared by the so-called method of Vogel, in which a saturated oxalic acid solution is added to boiling ferrous sulphate. The precipitate is washed and heated in a shallow dish at 200° C.


**Other Colouring Matters.**—Chromic oxide and also copper oxide are used for preparing green-coloured enamels. As regards chromic oxide the same remarks apply as in the case of ferric oxide. Cheap chromic oxide often gives dull enamels, accompanied by a separation of potassium dichromate. It is best prepared by heating potassium dichromate to redness ; but if the chromic oxide obtained in this way has not been sufficiently heated and washed, a part of the potassium dichromate remains undecomposed, and separates out after the firing of the enamelled utensils.

The test made when purchasing chromic oxide is extremely simple, since only a few grammes of the oxide are treated with hot water, and the presence of

undecomposed potassium dichromate demonstrated by a yellow-coloured filtrate. The amount of oxide added to the enamel mixture on grinding varies from 5 to 9 per cent. according to its quality and to the tint desired.

For lamp-shades, etc., a fused green enamel may be successfully prepared by melting enamel waste with 5 to 8 per cent. borax and 8 per cent. chromic oxide. The enamel waste has preferably been previously fused.

Chromic oxide may be prepared by another method, using 1 part potassium dichromate and 3 parts of burnt gypsum. This mixture is strongly heated to redness and then treated with very dilute hydrochloric acid. The following chemical reaction takes place :—



After boiling with dilute hydrochloric acid, whereby the lime goes into solution, the liquid is decanted off and the residue washed and dried. (A. Casali.)

Chromic oxide is also prepared by heating potassium dichromate to redness with flowers of sulphur. From 100 parts potassium dichromate and 50 of sulphur, 68 parts of chromic oxide are obtained.

The best chromic oxide is obtained by gradually heating ammonium bichromate, digesting with water, and then grinding. The lower the decomposition temperature, the more beautiful will be the



green colour. Chromic oxide obtained by a wet method (solution of chrome alum + soda) is never so beautiful as when a dry process is used.

**Cupric Oxide** produces fine dark-green to bluish-green enamels, depending on whether the enamel contains saltpetre or not. The oxide must be fused with the enamel, as it is not suitable for addition on grinding, in consequence of its exceptional behaviour.

The reducing gases in the muffle may in the case of enamels prepared from cupric oxide bring about a separation of copper in the form of faint red spots.

Coloured substances varying from green to bluish violet are obtained, according to Le Chatelier,\* from : 30 parts silica + 49 parts heavy spar ( $\text{BaCO}_3$ ) + 20 parts cupric oxide, heated for an hour at  $1050^\circ \text{C}$ . The shade obtained is bluish violet. Or : 375 parts silica + 265 parts heavy spar + 7 parts cuprous oxide + 42 parts sodium bicarbonate. This mixture, heated to  $1200^\circ \text{C}$ ., gives a pure blue.

**A Bluish-green Oxide** is prepared from copper and cobalt salts, or with chromium and cobalt salts. According as one or the other of the oxides prevails, bluish-green to greenish-blue shades are produced. Reviewing the price-list for the green and blue colouring oxides, a bluish-green or Turkish-blue oxide will be cheaper as the colour inclines towards the green, and more expensive when towards the blue. At the mill  $\frac{1}{2}$ —1 per cent. is added according to the desired

\* D. R.-P. Nr. 112,761, 11th October 1899.

shade. Since this blue-green oxide is one of the most expensive, and therefore most in demand, lighter shades of blue-green enamels are recommended for use, these being moreover much more delicate and elegant than the richly coloured and expensive blue-green enamels.

The yellow enamels are usually prepared by adding cadmium, chromium, or uranium salts when grinding. Cadmium sulphide gives very beautiful colours, also lead chromate, but its use is avoided as far as possible, on account of the lead content. Uranium salts and barium chromate are seldom employed.

**Brown Colouring Matters.**—Brongniart's brown is a very beautiful brown colouring matter, consisting of ferrous chromite. It is prepared by adding a solution of potassium chromate (1 in 3) gradually to one of pure ferrous sulphate (1 in 3). The precipitate is washed six times, dried, and heated to redness in a crucible, then finely powdered.

**Rose Colouring Matters.**—The rose-coloured enamels are prepared by colouring with gold salts; usually, however, by the addition on grinding of 6–10 per cent. of the so-called pink-rose.

It is difficult to obtain the same shade on all occasions, since after preparing and firing the pink-rose changes in shade and colour intensity. The enamels which have been coloured by the above are very unstable against fire. Also every place on the enamelled utensil which has been touched by the perspiring fingers of the workmen remains white, in consequence of the reduction which sets in.

What concerns the preparation of the pink-rose substances applies also to the mixture of chalk, quartz, tin oxide, borax, and potassium dichromate, which is heated to redness, the dye-stuff so obtained being digested with water, levigated, and washed. The preparation of pink-rose by this particular method is not recommended, on account of the inherent difficulties. Pink-rose (*Pinkrosa*) is counted among the most antique of the ceramic colours, the name being suggested by the English term "pink colours" (*Nelkenfarbe*). The exact chemical composition has not up to the present been fixed, but it appears to be a stannate or a chromium and calcium salt of stannic acid.

A very useful mixture for its preparation is afforded by : 50 kilos. stannic oxide, 25 kg. chalk, 18 kg. quartz, 4 kg. potassium dichromate, and 6 kg. borax.

The rose colour prepared by employing gold salts is only used for fine artistic enamels, and is distinguished from the other similar colours by its stability against fire.

**Purple (Purple of Cassius)**, a ceramic colour for making intense purple-coloured glazes, was well known to the ancients, being the most expensive and the loveliest red which is used in the ceramic and enamel industries. It is therefore only employed for decorating the better-class utensils.

Purple of Cassius\* is prepared by the addition of 1 part auric chloride to a solution containing 1 part

\* Cassius, inventor of gold-purple, 1683, in Leyden.



of stannous chloride and 2 parts stannic chloride, when a purple-red precipitate is formed, which is collected, washed, and dried.

If instead of 1 part gold chloride only half a part is taken, and the other half replaced by a silver salt, a beautiful carmine red is produced.

The true chemical constitution is not yet clear. It is regarded as a lake of metastannic acid coloured by finely divided gold (Debray).\*


Moissan,† the famous French chemist to whom we owe calcium carbide and other valuable discoveries, was occupied with this question shortly before his decease. He pointed out the remarkable fact that from the gold-purple obtained he could evaporate gold at the temperature of the electric furnace. Moissan tried the same experiment with an alloy of gold and tin, and found that, as the tin more quickly evaporated, a purple vapour formed, which was deposited in powdered form in the furnace. He obtained different varieties of purple, according as gold was used in the presence of aluminium, magnesium, zirconium, or silicon. This experiment confirms the view put forward by Debray for the constitution of gold-purple.

**Gold Glance.**—This is an indispensable requisite for decorating enamelled wares. It is best procured in large bottles, from which a definite amount is weighed out daily into a small work-vessel and given to the artists. On account of the

\* Debray, *Comptes rendus*, lxxv., p. 1025, 1872.

† *Bulletin de la Société Chimique*, 1906, p. 267.

unavoidable loss, the import in smaller bottles is inadvisable. Gold glance is prepared by dissolving auric chloride (gold dissolved in aqua regia, the mixture evaporated, and the residue dissolved in water) in a little water and adding 8–9 parts of a mixture of sulphur balsam in lavender oil (4 parts sulphur balsam and 4 parts lavender oil). The contents are vigorously stirred with a pestle, and allowed to stand twenty-four hours, in order that all the evolved hydrochloric acid due to mixing may escape. Usually half a part of finely powdered basic bismuth nitrate is then added, and the mixture allowed to stand again. By this means the gold will be made to adhere better. In all probability the following chemical reaction takes place :—



This is the process of Dutertre.

It is important to collect together all the waste materials from the gold glance process, such as the artists' overalls, brushes, glass plates and bottles, for the recovery of the gold. Gold glance contains about 10–12 per cent. gold. The above-mentioned articles are placed in a pot and burnt in the muffle. The empty bottles are likewise heated, splintered by water, and the glass powdered. The ash and glass fragments are then placed in a sufficiently large porcelain dish, aqua regia added, and the whole evaporated on the water-bath until the odour of nitric acid disappears. After cooling, aqua regia is

once more added, and again evaporated until the evolution of fumes ceases. Hot water is then added, the whole being well stirred and filtered. The gold goes into solution as auric chloride, to which a freshly prepared solution of the purest ferrous sulphate ( $\text{FeSO}_4 \cdot 7\text{H}_2\text{O}$ ) is added gradually, whereby the gold separates in the form of a yellowish-brown metallic powder, which is filtered, washed, and dried.

In many works the loss of gold glance is often considerable, and this alone is a sufficient recommendation in the majority of instances for the recovery of the gold from the waste materials. Many firms utilise the empty bottles which have held the gold glance for the preparation of rose-coloured enamels. The bottles are heated to redness, splintered, the glass powdered and added in the proper proportions to a mixture of white enamel in the smelting furnace.

Lustrous colours are seldom used, on account of their high price; but whether in the future the production of lustrous enamels will catch the popular eye remains to be seen. One or two metallic lustres are already prepared in large quantities, and there is no reason why, in the case of enamels, similar plays of colour should not be prepared chemically as in glass and porcelain manufacture. There is no lack of recipes and formulæ, but the times and demand are not yet ripe.

For the sake of curiosity, some of the above-mentioned recipes may be noticed, as they have



been used in part by the Arabs for preparing metallic reflections on artistic enamels.

A mixture of copper and silver carbonates ( $95\text{CuCO}_3 + 5\text{Ag}_2\text{CO}_3$ ), or 30 per cent. copper carbonate and 70 per cent. red ochre, or 20 per cent. copper sulphate, 25 per cent. stannous oxide, and 55 per cent. red ochre, were well powdered in the presence of a little gum arabic, finely triturated with water, and added to the transparent enamels; the wares being fired at  $900^\circ\text{C}$ ., allowed to cool, and again heated in the reducing fire at only  $650^\circ\text{C}$ . In this way very beautiful effects have been obtained.

L. Tranchet (*Comptes rendus*, 1905, pp. 1020 et 1237) gives several other formulæ:—

(1)	Enamel A	.	.	.	.	100.0
	Kaolin	.	.	.	.	10.0
	Silver carbonate	.	.	.	.	2.0
(2)	Enamel or substance A	.	.	.	.	100.0
	Kaolin	.	.	.	.	10.0
	Zinc oxide	.	.	.	.	1.0
	Tin oxide	.	.	.	.	1.0
	Silver carbonate	.	.	.	.	0.5
	Copper oxide	.	.	.	.	3.0
(3)	Substance A	.	.	.	.	100.0
	Kaolin	.	.	.	.	10.0
	Bismuth subnitrate	.	.	.	.	4.0
	Silver carbonate	.	.	.	.	2.0
	Copper carbonate	.	.	.	.	1.0

The substance A had the following composition :—

Quartz	. . . . .	12·0
Felspar	. . . . .	10·0
Kaolin	. . . . .	2·0
Sand	. . . . .	20·0
Minium (red lead)	. . . . .	30·0
Borax	. . . . .	19·0
Boric acid	. . . . .	2·0
Potash	. . . . .	2·0
Common salt	. . . . .	1·8

The substance A was fused, splintered by water, and ground at the mill, temperature 970° C.

	Arabian Formula.	Italian Formula.
Copper sulphide . .	26·87	24·74
Silver sulphide . .	1·45	1·03
Red ochre . . . .	71·98	49·45
Mercuric sulphide .	...	24·74

When firing the wares, the so-called green broom (German *Pfriemenkraut*, French *Genêt vert*, also Spanish *Klepper*) is placed in the interior of the muffle for combustion.

This slight deviation may be excused on the ground that one should not stand aloof with regard to hints and statements in the literature. If the question of the production of metallic reflection on enamels by using artificial lustrous colours is not at the present moment acute, yet a demand for the same may arise at any time. These formulæ are not easily obtainable, and are quickly forgotten.

**Clay and Kaolin.**—I have omitted to mention a material so important to the enamel industry as clay. At first sight there is apparently not much to say, yet in reality many volumes might be written on clay and its position in our industry.

And this is indeed an error which many enamel firms commit, viz. that they do not pay suitable attention to their clay; and many of the mistakes which have been explained away in the most impossible and fantastic ways have their origin here.

Chemically, we understand by clay and kaolin a compound of alumina and silicic acid, contaminated by more or less lime, magnesia, etc., according to its origin.

Clay has been originally formed by the decomposition of the felspars. Where the latter were to be found thousands of years ago, they have been gradually decomposed by the influence of the atmosphere, carbonic acid, water, etc. The water takes up the compounds of silicic acid with the alkalies, deposits them elsewhere, and leaves behind the insoluble compound of silicic acid with alumina, viz. clay.

If the clay still remains in its original situation, we term it kaolin; but should the clay after formation have been gradually transported by water and deposited elsewhere, then we speak of ordinary clay.

Kaolin, then, is residual clay, as distinguished from the ordinary variety which has suffered transportation. We must look, then, for kaolin among the



primitive rocks, since it is older than ordinary clay. An ideal clay would consist of :—

- 45 per cent. alumina or aluminium oxide.  
 40 „ silica or quartz.  
 15 „ water of composition.

In nature the composition varies, the so-called standard clays being presented in the following table :—

ANALYSES OF STANDARD CLAYS.

	Ia. Clay from Saarau. Pit Coal Clay.	Zettlitz Kaolin.	Belgian Clay from the Ardennes.	Fine Good Clay from Mülheim, near Coblenz.	Grünstadt, Ia. Clay similar to Kaolin from a Secondary Position.	Oberkaufungen, Moderate Lignite Clay.	Niederpleitz, Inferior Lignite Clay.
Alumina . . .	36'30	38'54	34'78	36'00	35'05	27'97	28'05
Silica as sand {	38'94	40'58	36'69	41'00	39'32	33'59	30'71
	4'90	5'15	9'95	6'74	8'01	24'40	27'61
Magnesia . . .	0'19	0'38	0'41	0'33	1'11	0'54	0'75
Lime . . .	0'10	0'08	0'68	0'40	0'16	0'97	0'72
Iron oxide . . .	0'46	0'90	1'80	2'57	2'30	2'01	1'89
Potash . . .	0'42	0'66	0'41	1'05	3'18	0'53	1'39
Loss when heated to redness . . .	17'78	13'00	12'00	11'81	10'51	9'43	8'66
Fireproof . . .	100	60-70	50	45	30	80	10
	poor	poor	very rich	rich	very rich	very rich	very rich

For enamelling purposes a good white clay containing about 36 per cent. alumina and 40 per cent. silica is preferable to kaolin ; for the latter, notwithstanding its purity, does not give in most cases that degree of expansion to the enamel which is essential. Localities for finding really good enamelling clay are becoming more scarce. The best varieties come from the Rhine neighbourhood, near Coblenz (Vallendar), and the Ahr valley, in the region of Bad Neuenahr. The clay from Sauerland possesses

valuable properties similar to that of Vallendar. Unfortunately, these pits are now exhausted, and the opening of new deposits must be continually taken in hand.

The treatment of clay in the enamel works before its use as an addition to the enamel requires careful and conscientious attention. The following may be stated, not in the sense of revealing secret operations, but in order to remind every expert anew of the value attached to the conscientious preliminary treatment of the clay.

The clay, before use, must be soaked as thoroughly as possible for two, or at least one day, in pure water at the temperature of the room. Since clay always contains enclosed organic matter of a vegetable or other origin, this must be removed; and therefore a weak fermentation is induced by soaking in water, which continues unaided if the mixture is allowed to remain at a moderate temperature. After a suitable time has elapsed, the clay is boiled with water for a short period, in order to terminate quickly the fermentation, and to drive away the last of the gaseous products so formed, such as carbonic acid.

The clay is then passed through a fine-meshed enamel sieve, using as much water as possible, allowed to settle, the water decanted off, and the clay thus prepared added in requisite amount to the enamel when grinding. Usually the quantity added varies between 5 and 10 per cent., sometimes reaching 12 per cent.

Should a clay contain an especially large amount of organic matter, and this be added to the enamel without undergoing the treatment described above, in particular without being boiled, small blisters frequently arise in the enamel. These blisters are caused by the carbonic acid contained in the fermenting clay.

How much annoyance may be spared by careful treatment of the clay ! and, on the other hand, how many mishaps are due to badly controlled enamel mills !

**A Short Note on Water.**—An important factor, on which success depends, is water. On principle, the purest water should be used for grinding enamel in the wet way. The most ideal kind is rain water or melted snow ; but these, unfortunately, are not always at disposal in sufficient quantity, so that well or river water must be used.

The use of very soft water which has stood for some time is especially recommended. Where soft water is not at hand, a little pure milk of lime is added to hard water, the mixture thoroughly stirred and allowed to settle over-night for use on the following day. This treatment of the water has a particularly good influence on ground-enamels. Condensed water may not be so pure as alleged ; water which has filtered through land, and pond water, must absolutely be avoided. A chemical analysis of the water regularly used at the mill should be made three or four times a year.



In general, for water of good quality the following data may be accepted: 1 litre of water may contain :—

Chlorine . . . . .	less than 0·015	gram.
Sulphuric acid . . . . .	0·002–0·005	„
Organic matter . . . . .	less than 0·001	„
Volatile „ . . . . .	„ 0·015	„
Total hardness . . . . .	2–8	
Hardness after boiling . . . . .	1–3	

It is often important to be able to test quickly and simply for the presence of chlorine and sulphuric acid in cases where one suspects the water used in the enamel mill to be contaminated by the waste water from the cleansing process. The procedure is as follows :—

**Test for Traces of Hydrochloric Acid in Water.—**

A small sample of the water is placed in a clean test-tube, 2 drops of pure dilute nitric acid and a few drops of dilute silver nitrate solution added (5 grm. silver nitrate dissolved in 100 grm. distilled water). If chlorine is present, a white turbidity, and often a heavier white precipitate, is obtained, due to the formation of silver chloride. The amount of turbidity will afford an estimate of the quantity of chlorine present. A faint translucent turbidity is often unimportant. The precipitate of silver chloride must dissolve in ammonia.

**Test for Traces of Sulphuric Acid in Water.—**A small quantity (10 c.cm.) of the water to be tested is placed in a test-tube, 2 drops of dilute nitric acid

and a few cubic centimetres of a dilute solution of barium chloride (10 grm. barium chloride dissolved in 100 grm. distilled water) added. The presence of sulphuric acid or its salts is detected by a more or less thick white turbidity, or if a large amount of sulphuric acid is present, a white precipitate of barium sulphate forms. The chemical reagents necessary are furnished by every apothecary or druggist.

**Coal.**—A few remarks may be made on this necessary combustible for the production of the temperature required for fusion in the enamel-smelting furnace and in the muffle. As the consumption of coal is extraordinarily great, many enamel works have been erected in the neighbourhood of coalfields. The amount of coal required for firing completely 100 kg. of enamelled wares may be taken as 120 to 250 kg., according to the construction of the furnace, mode of firing, quality of the coal, and, last but not least, according to the activity of the workers. This coal consumption is directly connected with the mode of heating the muffle. In Saxony and Bohemia, where the best quality of lignite (up to 6000 calories) may be obtained cheaply, it is used in the enamel works.

Austria possesses good pit-coal in the Ostrau-Karwiner district and in the Pilsen basin. Hungary's pit-coal and lignite are of less value, and leave up to 25 per cent. residue. Most of the coal used in the German, French, and Swiss enamel works is imported

from Westphalia. Some data of German standard coals may be inserted here.

	Name of the Pit.			
	Count Bismarck.	Hardenberg.	Schlägel u. Eisen (Iron).	North Star (Nord-stern).
Weight of 1 cubic metre .	696	741	700	744
Cohesion in percentage .	83	77	78	83
Unused residues .	4'24	5'94	3'46	9'90
Water evaporated from 0° reckoned in kg. from 100 kg. coal .	7'21	7'3	6'88	6'72

Lignite usually contains :—

Carbon . . .	44-57 per cent.
Hydrogen . . .	0·9-2·8 „
Water . . .	35-47 „
Ash . . .	5·0-7·5 „
Calories . . .	3500-6000

Pit-coal usually contains :—

Carbon . . .	70-80 per cent.
Hydrogen . . .	3-4 „
Water . . .	13-23 „
Ash . . .	3 „
Calories . . .	6600-8000

The large water-content causes the carriage of lignite to be unprofitable, especially where no inexpensive means of water-transport is to hand.

Lignite should never be stacked higher than 1·5 m., on account of spontaneous combustion. Pit-coal may be piled up a little higher.



AVERAGE COMPOSITION AND VALUE OF SOME BRITISH FUELS.

Description.	C	H	O	S	Ash, including Nitrogen.	Total Heat of Combustion.
Welsh . .	83·87	4·79	4·15	1·43	5·89	14858
Newcastle .	82·12	5·31	5·69	1·24	5·12	14820
Derbyshire .	79·68	4·94	10·28	1·01	4·06	13860
S. Yorkshire .	81·88	4·83	7·47	·54	2·95	14296
Lancashire .	77·90	5·32	9·53	1·44	6·18	13918
Scotch . .	78·53	5·61	9·69	1·11	5·03	14164
Irish Anthracite	80·03	2·30	...	6·76	11·03	13302
Coke (Durham)	85 to 92	...	...	·25 to 2·0	4 to 12	12832

Too large storage of coal must be avoided, since the coal, after being stacked a long time, falls to pieces, accompanied by a partial evolution of gas, causing deterioration thereby. In many cases it is advisable to sprinkle the surface of the pit-coal with water previous to burning, whereby a loss of unconsumed coal-dust will be avoided.

The necessity for a thorough and regular control of the coal entry and exit cannot be too strongly recommended, the latter being exactly recorded for each separate firing. The heating itself requires extremely great care, strenuous work, and undivided control. Something will be said concerning gas analysis in the chapter entitled "Firing of the Enamelled Utensils."

The last, but none the less important, materials in

our industry of enamelling on sheet and cast metals are the latter metals themselves.

**Sheet and Cast Iron.**—For the preparation of a faultless enamelled ware, one of the most important items is faultless sheet metal or a flawless casting, possessing a definite chemical and physical behaviour.

Almost exclusively at present a soft sheet steel is used, *i.e.* rolled-out steel which has been prepared according to the basic Martin process in the special Martin furnace. For utensils which have not been forged, but only made up from sheet, and where, therefore, nothing has been exacted from the physical properties of the steel, the somewhat less expensive and more simply treated sheet steel is used.

The quality of the steel is unfortunately often variable, and dependent on the care exercised during its manufacture at the iron-works. Good forged sheet steel should be box-heated, a term derived from the process of heating in iron boxes, as far as possible with the exclusion of air. Often impurities, such as particles of slag, etc., will be rolled in with the sheet metal, so that on forging, and even more on enamelling, flaws will develop in wares prepared from such material. Chemically, a well-forged sheet for enamelling purposes should possess the following composition :—

Carbon	.	.	.	0·050—0·080	per cent.
Manganese	.	.	.	0·230—0·350	„
Phosphorus	.	.	.	0·002—0·080	„

and, at the most, traces of silicon.

Regarded physically, it should possess the following coefficients :—

Coefficient of tenacity . . .	35-38 per cent.
„ contraction . . .	56-65 „
„ elasticity . . .	30-38 „
Specific gravity . . . . .	7·6-7·8

The immediate analysis of the purchased metal, so as to buy it on the basis of the previous figures, is most strongly recommended. The physical examination is carried out by the testing-machine, the purchase of which is advisable, on account of the quicker and more simple investigation of the sheet metal. This machine is based on the principle of the decimal balance, in which the sample strip to be broken is stretched in position on the beam between two levers, and on adding to the load by placing weights on the scale an increasing tension is obtained until finally the sample breaks.

England and Germany produce most of the forged metal, and the larger part of this of first-rate quality. In addition, Austria-Hungary and France manufacture good forged metals in several iron-works, but these are frequently expensive. Moreover, the adaptability of these works is often very limited.

Austria-Hungary grants to enamel firms the rebate of the tax on English or German sheet metals in the case of exportation of the enamelled wares prepared from them. In consequence of this it is possible to employ first-class English sheet-iron in the manufacture of wares for export.



Until the year 1896, almost all the forged metal used in the German enamel works was imported from England. The annual consumption of metal for enamelling purposes is estimated by Dr H. Wuppermann at 70,000 to 85,000 tons, having an approximate value of £1,000,000. The data giving the decrease in the import may be directly applied to the weight of the quantity of enamels used. Here may be mentioned the more complete statistical treatise of Dr Hermann Wuppermann, *The Sheet Metal Enamelling Industry in Germany*.

The tax levied in Germany for imported sheet metals, according to the customs tariff of 25th December 1902, for pieces more than 1 mm. thick, amounts to 30s. per ton, and for thicknesses of 1 mm. or under, 46s. per ton. For rolls the tax is raised 25 per cent.

In the case of foreign metals, rolls are recommended, the saving in freight being 50 per cent.

The most thorough management of the metallic stock is indispensable, and is greatly facilitated by having a specially designed storehouse, where the sheets may be stacked according to size and thickness. It is self-evident that such a store should be kept dry, to prevent the metals rusting. The utilisation of the metal to the best advantage by cutting out the shape to be folded for the crude ware, or the preparation of rolls, should be as economical as possible. The larger metallic fragments may be profitably used for the manufacture of hollow handles, knobs, children's toys, etc.

A frequent, and if possible daily, oversight of the metallic fragments is an indispensable duty of the official entrusted with the management, for many a badly forged article, often due to the workmen, will be exposed by an efficient control.

**Cast Iron suitable for Enamelling Purposes** (*Cast Iron for Utensils or Pots*).—If not exactly within the scope of the industry concerned with sheet metal enamelling, yet the importance of the manufacture of enamelled cast-iron wares for special purposes, such as the preparation of hygienic implements, water-closet appliances, water-pipes, baths, basins, etc., and often for cooking-vessels, chemical apparatus, etc., should not be underestimated.

Corresponding to the essential chemical and physical difference between sheet and cast iron is the treatment and preparation of the enamels, etc., which for the enamelling of cast-iron vessels differ from those in the process of enamelling on sheet metal. The iron suitable for pots and utensils is a thin wrought iron, which gives a sharp mould, and possesses a smooth surface, and for this purpose the inexpensive pig-iron containing phosphorus, with a little manganese and a moderate silicon content, is suitable (prepared from bog-iron ore, which earlier was regarded as valueless), since a certain amount of brittleness or a somewhat lower strength does not matter.

The English quality corresponding to the above is found near Middlesborough, and the German

variety, the so-called Lorraine or Luxembourg pig-iron, near Luxembourg.

English pig-iron contains :—

Carbon	.	.	.	3·5 per cent.
Silicon	.	.	.	2·0 „
Phosphorus	.	.	.	1·4 „
Manganese	.	.	.	0·7 „

Luxembourg pig-iron contains :—

Carbon	.	.	.	3·6 per cent.
Silicon	.	.	.	2·0 „
Phosphorus	.	.	.	1·8 „
Manganese	.	.	.	0·5 „

For thin objects, which, in consequence of rapid cooling, are more brittle than thicker ones, the property of phosphorus in producing this brittleness is inconvenient, and in the case of a high phosphorus content a little more silicon serves as a remedy. To the above pig-iron 40–50 per cent. of good bog-iron is added.

For thin hardware, which easily becomes brittle, the use of a more tenacious iron containing increased quantities of silicon and carbon is recommended, so as to acquire a more uniform, smooth, blue surface ; the better German and English varieties are therefore prepared with the addition of 1–2 per cent. of steel (fragments from the Bessemer process, which, however, must not be rusted over), or pieces of wrought iron, to the molten metal. This small addition of steel is often made with advantage at the foundry. Steel in contact with the glowing coke



of the cupola furnace takes up carbon and changes into grey pig-iron, providing the silicon content of the molten metallic mixture is sufficient.

Arsenic, antimony, copper, or chromium should not be present, even in small quantities, in the cast iron. If P is the weight of the mould, then the weight of the cast iron is approximately, for moulds of—

Pine or fir-wood	.	.	.	.	14'00 × P
Oak	.	.	.	.	9'00 × P
Beech	.	.	.	.	10'00 × P
Lime	.	.	.	.	13'50 × P
Birch	.	.	.	.	11'00 × P
Alder	.	.	.	.	13'00 × P
Brass	.	.	.	.	0'90 × P
Zinc	.	.	.	.	0'80 × P
Lead	.	.	.	.	0'70 × P
Cast iron	.	.	.	.	0'97 × P

Difficulties in the process of enamelling hardware are frequently caused by adhering mould-sand which has been burnt in. To avoid this, 10 per cent. of powdered coal is mixed with the sand, and the inside of the mould is sprinkled with charcoal dust. Before etching the hardware, it must be carefully cleaned by wire brushes, files, etc., so that finally, with the aid of the sand-blast, a metallic surface suitable for etching and enamelling will be obtained.

### CHAPTER III.

## THE PREPARATION OF THE ENAMEL.

THE mixing of the enamel, *i.e.* the intermingling of all the raw materials the object of which, after fusion, is the finished product, is carried out in a special chamber. Since the preparation of enamel is a trade secret, the mixing is performed in small firms by the owner himself or his representative, while in larger establishments, where the daily enamel production is on a scale too vast for the owner or manager to deal with exclusively, the following procedure takes place :—

The official entrusted with the preparation of the enamel mixes together the smaller constituents, such as soda, saltpetre, cobalt-nickel oxide, magnesia, braunstein, and in addition a small part of the borax, felspar, and cryolite required in the formulæ described earlier. The workman takes from this preliminary mixture the corresponding quantity, and completes the mixture by adding the materials in the amounts given him. A small example will serve to illustrate.

A formula for white enamel runs as follows :—

Borax	.	.	.	132 kg.
Quartz	.	.	.	152 „
Felspar	.	.	.	130 „
Soda	.	.	.	26 „
Saltpetre	.	.	.	6 „
Cryolite	.	.	.	78 „
Fluorspar	.	.	.	3 „
Magnesia	.	.	.	6 „
Total				533 kg.

This is subdivided as follows :—

	Mixture by	
	The Official in charge.	The Workman.
Borax . . .	12 kg.	120 kg.
Quartz . . .	12 „	140 „
Felspar . . .	30 „	100 „
Soda . . .	10 „	16 „
Saltpetre . . .	6 „	...
Cryolite . . .	28 „	50 kg.
Fluorspar . . .	3 „	...
Magnesia . . .	6 „	...
Total . . .	107 kg.	426 kg.

That only very trustworthy workmen should be entrusted with the mixing operation, will be self-evident.

As already mentioned, the raw materials to be mixed must be as dry and finely powdered as possible, for then the mixture will be more intimate,



and in consequence the fused enamel more uniform. In the larger works a practical balance with the mixing boxes placed upon it is fitted up. The mixing chamber should be well ventilated, and during the process any unnecessary production of dust, involving loss of material, must be avoided. The pot or metal chest in which the finished mixture is transported to the smelting furnace should always be thoroughly cleansed, while in the case of blue and ground enamels separate boxes are to be preferred. The more expensive metallic oxides should be separately weighed on small balances. Cobalt oxide requires an especially long time for mixing, so that the colour intensity may be properly developed.

With smaller quantities (up to 200 kg.) the mixing is performed by a workman who employs a crook for the purpose, but larger quantities are brought together by a mechanical mixing apparatus or mixing cylinder. Careful mixing by hand is, however, more reliable. The rule may be stated that the smaller the quantities taken the more intimate the mixture. Larger quantities, up to 800 kg., which are mixed in the "mélangeur," must remain a correspondingly long period in the apparatus—in fact, up to thirty minutes. Coloured enamels require an especially long time.

The crude enamel mixture must be put through a wire sieve (width of meshes 5 to 7 mm.).

The saltpetre usually gathers into small balls, which must be carefully crushed by hand.

In a well-conducted works, stress will be laid on

the exact manipulation of the blended raw materials which when fused together form the enamel, on the one hand to ascertain precisely the loss on melting and therefore the value of the enamel, and on the other to expose negligence.

Above all, the balance should play an important part in the enamel industry. All the materials which enter and leave, whether proceeding from the mixing chamber, or leaving the furnace, or entering the mill, the enamel from the latter, coal, the etched ware, etc., all are weighed, and a really efficient service at the balance renders most valuable help to the works management.

**The Melting Process.** — From the mixing chamber the enamel proceeds to the melting furnace, which is generally a blast furnace (*Wannenöfen*) and seldom a crucible furnace. According to the dimensions of the workings, the furnaces are provided direct with 50 per cent. gas or generative heating.

The crucible furnace gives very good results in the case of the best enamels, but its utility is limited and the cost of maintenance too great, so that at present the blast furnace is almost exclusively used. The dimensions of the latter must not be too great, but correspond to the proportions of the melt.

What was stated with regard to blending finds its parallel here. The smaller the portions, the more uniform the fusion and the finer the enamel.

In works of moderate size the charge should not exceed 150–200 kg. at any single operation.

Larger works are necessary, however, in con-

sequence of the large consumption, and these must be able to deal with over 200 kg. at a time. If the temperature of the furnace is insufficient, then the charge of enamel must remain there longer, doubtless to the detriment of the product, for not only discoloration but frequently a decomposition of the enamel may set in. Moreover, every expert knows the disagreeable consequences of working with an under-fused enamel.

Too high a temperature in the furnace is in a like manner objectionable, since combustion of the enamel may take place, or a premature decomposition of the separate materials may proceed before the mixture has time to unite chemically to form a silicate. The mean temperature lies between  $1100^{\circ}$  and  $1200^{\circ}$  C.

Special emphasis is laid on a very vigorous crooking, viz. stirring the molten enamel in the furnace by means of iron crooks.

Success depends largely on this latter operation. On melting the enamels there commences a distinct separation of the constituents, according to their specific gravity. The borax, soda, and cryolite melt, while the fusible quartz and felspar endeavour to settle to the bottom. Should frequent and conscientious stirring be neglected, there develops an uneven exclusion of the silicate, with consequent deterioration in the quality of the enamel. The duration of the fusion may be taken as two hours for white, and two and a half to three hours for ground and blue enamels. The latter should be



vigorously fused, but this must be abated for white enamel before complete devitrification takes place, otherwise it will become more transparent and less opaque. From time to time samples are taken from the furnace with an iron bar, and should the glass threads of enamel which form exhibit the partial development of knots, then the enamel must remain longer in the furnace.

In addition, before drawing off the enamel, a small specimen is placed in a vessel, allowed to cool, and the fractured surface observed. Well-fused enamel shows a bright, absolutely smooth surface, and fracture free from porosity.

Many of the smaller works fill the furnace with the mixture to be fused, and allow the molten enamel to run off continuously, while the mixed materials are persistently added to the furnace.

That this form of continuous working is not suitable follows from the reasons offered above. On fusion two factors operate in causing a loss of enamel: on the one hand the decomposition of certain constituents, which give off their water of crystallisation or carbon dioxide (borax 47 per cent., soda 41 per cent., since only calcined soda is used, saltpetre 61 per cent.), and by the partial loss of hydrofluoric acid from the cryolite and fluorspar; on the other hand there is the loss in manipulation, which ordinarily should not exceed 3 per cent. The average total loss on fusion may be taken at 15-23 per cent. An estimate should be made for each separate case, in order to show what amount of

enamel may be obtained by suitable manipulation of the raw materials.

The molten enamel is allowed to run into cold water, in order to splinter it, the water then being run off and the moist enamel either taken direct to the mill or to the storehouse. Many firms dry the fused enamel, but the majority use or retain it in the moist condition as it comes from the water chambers attached to the furnace. In the latter case the enamel contains about 4 per cent. of adhering moisture, which must be taken into account when estimating its weight. For storing the fused enamel, chambers are used which are protected against wind, rain, and dust, the floors being cemented and the side walls covered with sheet zinc.

Separate compartments are employed for the different varieties of enamel, which must be maintained in a condition of the utmost cleanliness.

As an example of the calculations whereby the loss during fusion is arrived at, the following composition of a ground-enamel will serve :—

Borax	72.0 kg.,	loss 47 per cent. =	33.80 kg.
Felspar	55.8 „	...	...
Quartz	31.2 „	...	...
Soda	8.4 „	loss 41 per cent. =	3.44 kg.
Fluorspar	7.2 „	...	...
Saltpetre	5.4 „	loss 61 per cent. =	3.29 kg.
Cobalt oxide	0.4 „	...	...
Limonite	1.2 „	loss 9 per cent. =	0.11 kg.
<hr/>			
Total	181.6 kg.	Loss =	40.64 kg.

181·6 kg. of mixed ground enamel give, according to the mode of fusion,  $181·6 - 40·64 = 140·96$  kg. of fused enamel. This gives a loss on fusion of 22 per cent., to which must be added a still further loss of about 2–3 per cent. due to manipulation.

**The Grinding Process.**—The fused enamel is taken to the mill, where it is ground in stone mills (with nether millstone and adjustable bearings) or drum mills. The latter are not suitable for the moist grinding of white enamel, but may be employed with advantage for large quantities of coloured enamels. The fact is that white enamel ground by stone mills is not only finer, but also more opaque, for the particles of tin oxide appear to be crushed and distributed better throughout the enamel by grinding in this way.

In the grinding room the most scrupulous cleanliness is observed, and the production of dust avoided. The amount of fused enamel to be ground varies from 20–40 kg., while the duration of the process will be, according to the quality of the enamel and the grade of fineness desired, between four and twelve hours. Water is added up to 30 per cent. for white, and 40 per cent. for ground-enamel, of the weight of the portion taken. Since during the grinding operation loss of water may frequently occur, care is always taken to replace this; otherwise, in consequence of friction between enamel and millstone, heat may be evolved and thereby the quality of the powder unfavourably influenced. In such cases the enamel is said to be burnt (*verbrannt*), *i.e.* it loses its lustre when burnt into the utensil.



The deterioration of the enamel so caused is traced to a loss of lustre consequent on overheated mill-stones.

Certain compounds are added to the moist grinding, not only to develop the white, red, or green colour, but also to make the enamel capable of use for the subsequent enamelling of the crude ware. Fused enamel, ground without these additions, would be useless, as it would quickly settle to the bottom.

As additions on grinding there are used : stannic oxide for developing an intensive white in the enamel ; such colour oxides as pinkrosa, ferric oxide, chromium oxide, cadmium sulphide, etc., which develop rose, red, green, and yellow colours respectively. In many cases a little zinc oxide (2 per cent.) is also added to make the white enamel more fiery.

Clay serves as a further important addition to the grinding process for every enamel, since it possesses to the highest degree, due to its finely divided condition, the capacity of holding the ground-enamel in a state of suspension, and thus preventing the so-called "settling." Moreover, the clay produces opacity and influences most favourably the elasticity of the enamel. The preliminary treatment of the clay has been already described. The addition of stannic oxide to white enamel varies from 5-18 per cent., that of clay from 5-13 per cent. Only 3-6 per cent. clay is added to ground and blue enamels.

It is also advisable to use in certain cases a so-called vehicle (*Stellmittel*) with the enamel, unless one prefers to do this immediately before charging the working-dishes with enamel.

The vehicles used are for the most part alkaline, seldom of an acid character, and serve to stiffen the enamel, so that, on taking a sample in a ladle, the enamel is only mobile for a few seconds and then quickly comes to rest. The enamel is then said to stand good.

The principal vehicles to be noticed are sal-ammoniac, ammonium carbonate, magnesium chloride, burnt magnesia (formed by heating magnesium carbonate to redness), common salt, and, for many enamels, borax and soda. Often Epsom salts and magnesium sulphate are used. Most worthy of recommendation for white enamels are ammonium carbonate and burnt magnesia. The former has the valuable property of volatilising in the muffle without leaving behind the often injurious chloride and sulphate. Burnt magnesia also commends itself as a pure base free from acids. For ground and blue enamels borax is readily used as a vehicle (about 50–60 grm. per 100 kg. enamel). With such powerful substances for vehicles a caution must be uttered. The enamel expert will always find for individual cases the correct minimum amount to add of these unavoidable vehicles, and from fundamental reasons this important post in an enamel works is never given to workmen. It has happened that workmen who appeared conversant with the use of such materials have often used highly objectionable salts as vehicles, and in consequence have been severely reprimanded.

Finely ground enamels have a brighter lustre than

those more coarse ; yet in spite of this the enamels are not powdered too finely, since they acquire a soapy, slimy feel and are hard to use, owing to the formation of lumps.

Ground and blue must be somewhat more coarse-grained than white. In cases where the utensil is only to be coated once with white enamel, it must be ground correspondingly coarser than a so-called second white, which is used for the second covering.

The specific gravity of the enamels, *i.e.* the weight of a cubic centimetre, amounts to :—

For white, calculated without included

water . . . . . 2·8

The same reckoned + 30 per cent.

water . . . . . 1·8

For ground-enamels, calculated without

included water . . . . . 2·04

The same reckoned + 30 per cent.

water . . . . . 1·55

According to the ordinary formula,  $v \times s = g$ , *i.e.* the product of volume and specific gravity of a body is equal to its weight. The weight of a volume of the enamel, or *vice versa*, may quickly be calculated by using the above specific gravities.

*E.g.* a vessel contains 45 litres of white enamel powder, including water, and therefore ready for use. This 45 l. weighs, therefore,  $45 \times 1·8 = 81$  kg.

The same vessel containing 45 l. ground-enamel will only weigh 70 kg., since  $45 \times 1·55 = 70$  kg.

The specific gravity of white enamel is higher than



that of the other enamels, owing to the addition of stannic oxide, and approaches, consistent with similarity in character, the specific gravity of glass, which varies from 2.4-3.

The cost of fusion for 100 kg. enamel, from the ratios of the amounts melted, will be determined by the sum of the following variables : crucibles for melting, fire-proof material, boxes for holding the enamel, coal for the furnace, shovels and similar implements, the wages of the smelters, bricklayers, locksmiths, and tanners.

The cost entailed in the grinding is in its turn similarly calculated from the amount of work done in a month, wages, repairs, and materials used. The calculation of the complete enamel, ground moist and ready for use, is reckoned, however, without water, and may be rapidly made on the basis of the following formula :—

Pr stands for the cost in shillings of 100 kg. of the mixed, untreated enamel.

Pz = value in shillings of the additions to the grinding.

L = cost of fusing 100 kg. enamel.

M = cost of grinding 100 kg. enamel.

Z = the percentage additions to the grinding.

Pm = the cost of 100 kg. enamel ready for use, and including all the additions, with the exception of water.

$$P_m = \frac{(1.17Pr + P_z + L)100}{100 + Z} + M.$$

If for white enamel the additions average 16 per cent., then the formula approximately reads :—

$$Pm = Pr + 0.85 \times Pz + L + M.$$

In many works the powdered white enamel is subjected to a further purifying process. The success attained for the latter requires notice, but the process is not recommended for ordinary use, on account of the relatively high expense. To blue enamel a little ferric oxide is advantageously added on grinding, whereby the blue will be rendered more brilliant and intense.

The enamel fragments produced during the operation should as far as possible be separated according to colour, collected together, and fused, for further addition in suitable quantity to the blue enamel before melting, *e.g.* :—

#### BLUE ENAMEL.

Borax . . . . .	60.0 kg.
Alumina . . . . .	3.6 „
Felspar . . . . .	101.0 „
Soda . . . . .	6.2 „
Natural cryolite . . . . .	24.0 „
Saltpetre . . . . .	3.0 „
Fused enamel, fragmentary . . . . .	40.0 „
Cobalt oxide . . . . .	3.0 „
Limonite . . . . .	0.3 „
Ferric oxide . . . . .	0.1 „
	<hr/>
	241.2 kg.

## Additions on grinding :

4½ per cent. purified levigated clay.

120 grm. ammonium carbonate per 100 kg. enamel.

The following further formulæ, etc., may be given for some special varieties :—

## BLACK FUSED ENAMEL.

Borax	.	.	.	.	.	62 kg.
Felspar	.	.	.	.	.	120 „
Soda	.	.	.	.	.	14 „
Ferric oxide	.	.	.	.	.	8 „
Cobalt oxide	.	.	.	.	.	2 „
Smalt	.	.	.	.	.	16 „
Limonite	.	.	.	.	.	16 „
Total						238 kg.

## ACID-RESISTING WHITE.

Borax	.	.	.	.	.	74 kg.
Felspar	.	.	.	.	.	100 „
Quartz	.	.	.	.	.	115 „
Cryolite	.	.	.	.	.	47 „
Stannic oxide	.	.	.	.	.	40 „
Fluorspar	.	.	.	.	.	6 „
Soda	.	.	.	.	.	20 „
Saltpetre	.	.	.	.	.	10 „
Magnesium carbonate	.	.	.	.	.	1 „
Pure powdered glass-meal	.	.	.	.	.	53 „
Clay	.	.	.	.	.	12 „
Calcspar	.	.	.	.	.	6 „
Total						484 kg.



Additions on grinding :

7 per cent. clay.

6 „ tin oxide.

$\frac{1}{3}$  „ burnt magnesia.

#### GLAZE.

Borax	.	.	.	.	21 kg.
Quartz	.	.	.	.	60 „
Felspar	.	.	.	.	40 „
Cryolite	.	.	.	.	12 „
Saltpetre	.	.	.	.	4 „
Soda	.	.	.	.	8 „
Fluorspar	.	.	.	.	6 „
Total					151 kg.

#### WHITE, FOR CORAL RED, ETC.

Borax	.	.	.	.	60 kg.
Felspar	.	.	.	.	58 „
Quartz	.	.	.	.	34 „
Soda	.	.	.	.	6 „
Cryolite	.	.	.	.	11 „
Clay	.	.	.	.	4 „
Total					173 kg.

Additions on grinding :

4 per cent. clay.

7-10 per cent. coral red substances.

Among the enamels suitable for hardware, the following may be mentioned:—For ground-enamels a matted ground is used, *i.e.* a substance which has

only been heated in the furnace to the melting point, and which on account of its composition is excluded from complete fusion. This matt is prepared by mixing together borax, quartz or flint, felspar, fluorspar, and clay. Naturally, a number of formulæ exist, from which the following are selected :—

	Additions on grinding.
(1) 30 kg. quartz.	$8\frac{2}{3}$ kg. clay.
17 „ borax.	$\frac{1}{2}$ „ magnesia.
(2) 30 kg. quartz.	$10\frac{3}{4}$ kg. clay.
30 „ felspar.	6 „ felspar.
25 „ borax.	$1\frac{3}{4}$ „ magnesia.
(3) 210 kg. flint, 70 kg. borax, 10 kg. soda are fused for three to four hours in the furnace. During grinding, 32 kg. of the melt, 11 kg. clay, 34 kg. quartz are added.	
	Additions on grinding.
(4) 28 kg. flint (silica).	18 kg. of the melt.
8 „ borax.	6 „ quartz.
1 „ fluorspar.	1.5 „ clay.

This mass is known as the matt (*Fritte*), and is prepared by mixing the substances named, and heating to redness in a shallow pan, covered externally by clay, in the muffle furnace. The heating lasts about one to one and a half hours.

The matt forms a porous, tuff-looking mass, which is broken up and ground moist in the mill with the addition of the other substances. A too abrupt fusion of the matt is avoided, otherwise a loss of adhering power is entailed.

All the good white enamels for sheet metal may be used for enamelling hardware. Many cast objects, such as imitation majolica, baths, etc., should not be covered by enamels ground moist, but with those powdered by hand or by means of a sieve or special machine. The process of covering a cast object which is red hot with dry enamel finely powdered will be understood a little later. The enamel used must be easily fusible, and the process is performed with repeated warming of the object, until the enamel layer has the desired thickness. Vessels so treated present a porcelain-like appearance, but are expensive. Frequently the ground white enamel may be sprinkled direct on the red glowing cast without the intermediate stage of a matted ground.

Many enamel powders are prepared with lead, antimony, or arsenic compounds, which give an extraordinary lustre to the enamels.

An enamel containing arsenic is easy to recognise, since in fused samples it exhibits a bluish, gleaming, translucent edge.

As an example of a white enamel powder free from poison may be taken :—

Borax	.	.	.	.	.	200 kg.
Felspar	.	.	.	.	.	120—130 „
Stannic oxide	.	.	.	.	.	68 „
Clay	.	.	.	.	.	20 „
Soda	.	.	.	.	.	8 „
Saltpetre	.	.	.	.	.	2 „
Natural cryolite	.	.	.	.	.	40 „



Ammonium carbonate	.	.	3 kg.
Fluorspar	.	.	2 „
Magnesium carbonate	.	.	2 „
Total			465 kg.

As a further example of a white enamel for covering cast iron when moist :—

Borax	.	.	.	.	62.0 kg.
Felspar	.	.	.	.	60.0 „
Soda	.	.	.	.	4.0 „
Cryolite	.	.	.	.	20.0 „
Saltpetre	.	.	.	.	3.0 „
Clay	.	.	.	.	2.5 „
Stannic oxide	.	.	.	.	2.0—5.0 „
Magnesia	.	.	.	.	0.2 „
Fluorspar	.	.	.	.	0.1 „
Total					153.8 kg.

Additions on grinding :

7 per cent. tin oxide,

7 „ clay, and

0.3 „ magnesia.

THE CHEMICAL COMPOSITION OF SEVERAL ENAMELS.

Number.	Species of Enamel.	Silica ( $\text{SiO}_2$ ).	Alumina ( $\text{Al}_2\text{O}_3$ ).	Lime ( $\text{CaO}$ ).	Magnesia ( $\text{MgO}$ ).	Sodium Borate ( $\text{Na}_2\text{B}_4\text{O}_7$ ).	Sodium Oxide ( $\text{Na}_2\text{O}$ ).	Potassium Oxide ( $\text{K}_2\text{O}$ ).	Stannic Oxide ( $\text{SnO}_2$ ).	Antimony Oxide ( $\text{Sb}_2\text{O}_3$ ).	Phosphoric Acid ( $\text{P}_2\text{O}_5$ ).	Cobalt Oxide ( $\text{Co}_2\text{O}_3$ ).	Ferric Oxide ( $\text{Fe}_2\text{O}_3$ ).	Boric Acid ( $\text{B}_2\text{O}_3$ ).	Limonite.
1	White, easily fusible	39.38	10.32	0.75	...	21.83	7.81	8.11	11.80	...	...	...	...	...	...
2	White, easily fusible	44.70	6.59	0.40	...	21.66	11.09	4.89	11.40	...	...	...	...	...	...
3	White, easily fusible	34.23	8.97	0.63	3.41	23.70	9.73	10.90	8.30	...	...	...	...	...	...
4	White, hardly fusible	47.28	2.29	5.73	4.87	18.76	2.68	8.90	9.50	...	...	...	...	...	...
5	White, easily fusible	36.72	11.0	2.69	5.72	20.51	0.65	11.23	12.20	...	...	...	...	...	...
6	White, stable to acid	60.90	5.51	5.58	0.26	...	12.65	2.64	2.60	...	0.36	...	...	9.83	...
7	White . . .	41.48	11.67	4.10	0.65	...	11.98	2.14	17.38	...	0.11	...	...	8.62	...
8	White . . .	35.0	15.0	3.50	0.22	...	16.30	3.30	...	9.80	...	...	...	17.32	...
9	White . . .	41.56	10.70	0.93	0.47	...	13.28	5.73	14.28	...	0.15	0.08	...	10.70	...
10	Blue . . .	53.16	15.89	0.55	0.22	...	13.92	5.83	0.34	...	0.17	1.26	2.23	5.60	0.25

EXAMPLES OF MIXTURES CORRESPONDING TO THE  
ABOVE ANALYSES.

No. 1 is the analysis of an easily fusible white body-enamel, the mixture being made up of :—

Felspar	.	.	.	.	60 kg.
Borax	.	.	.	.	42 „
Tin oxide	.	.	.	.	12 „
Soda	.	.	.	.	15 „
Saltpetre	.	.	.	.	2 „

No. 2 is the analysis of a white enamel consisting of :—

Felspar	.	.	.	.	27·0 kg.
Borax	.	.	.	.	35·0 „
Quartz	.	.	.	.	20·0 „
Tin oxide	.	.	.	.	17·0 „
Soda	.	.	.	.	16·0 „
Saltpetre	.	.	.	.	2·5 „

No. 8 is white enamel mixed from :—

Borax	.	.	.	.	47·0 kg.
Felspar	.	.	.	.	46·0 „
Antimony oxide	.	.	.	.	9·2 „
Soda	.	.	.	.	1·4 „
Clay	.	.	.	.	4·5 „
Cryolite	.	.	.	.	16·2 „



## CHAPTER IV.

### THE PREPARATION OF THE CRUDE WARE.

THE crude wares are heated to redness before pickling, with the object of removing the adhering greasy or soapy layer. Moreover, the elasticity of the sheet metal, which is lost during the forging, drawing, planing, or pressing processes, is restored by heating, this operation being conducted for the most part in the muffle, seldom in a special furnace. If the crude wares are dipped in weakly acidified water before heating, the process is rendered more thorough, since the oxide or scale layer easily comes off after glowing. With better-class wares this should always be done. Many of the flaws which show themselves in the enamelled utensil after firing have their origin in the incomplete and therefore insufficient heating of the crude wares.

Above all, too many wares should not be heated at the same time. Washing utensils, plates, etc., are placed in sets of not more than five to eight pieces. If,

for example, washing utensils in piles containing twenty or more pieces are heated, then incomplete combustion of the impurities takes place, together with a non-uniform oxidation in consequence of the scarcity of oxygen. The latter often causes afterwards a chipping off of the enamel at the edges of the utensil. Bad heating is generally an accompanying cause of scale formation (nail-chips, *coup d'ongle*), so that, on cooling, small enamel particles in the form of a miniature finger-nail break off from the fired enamelled ware. It should not be supposed that this, which is so feared by the workman, can only be traced to improper heating, since scale formation is often due to insufficient burning in of the ground-enamel, or to a faulty enamel. In order, however, to avoid a usual error during manufacture, which may be ascribed to different and often not permanent causes, the careful man will use all the means which experience has placed at his disposal.

It is folly to pack together for heating cylindrical or conical objects, such as pots, stewpans, etc., for the grease will only be incompletely burnt, and carbon deposited, which will be drawn into the pores of the metal. When enamelling such objects, a more or less thick blister formation takes place on the sides and edges, causing an increased percentage of damaged goods.

The temperature of the furnace must be suitable (about  $750^{\circ}$  C.) and kept uniform. An underheated furnace, in which the crude wares

must remain over long, is as injurious as one overheated.

As in the preliminary treatment of hardware, so in other cases, it is advisable to heat gently in the muffle before pickling, in order to burn up the adhering coal-dust.

The crude ware so prepared is now taken to the pickling chamber. The pickling has for its object the production of a pure metallic surface, since only upon such will the ground-enamel adhere, and on burning in unite with it.

At the same time, during the pickling, the metallic surface will become rough, causing the enamel to adhere better and more intimately. As pickling, liquid hydrochloric acid is generally used, seldom sulphuric. The latter is employed more especially for cleansing cast wares, although many firms pickle with hydrofluoric acid, which dissolves at the same time the adherent or more deeply embedded sand particles derived from the sand mould or blast.

How deep the sand particles may penetrate into sheet metal when exposed to the sand blast, follows from the remarkable fact that such metal, when as pure as it is possible to obtain it and in spite of an additional immersion in acid, is no longer capable of being tinned. The tin will only alloy itself at isolated spots on the metal.

Dilute hydrochloric acid is used, one-third acid of 21° Bé (specific gravity 1.171) to two-thirds water. The sulphuric acid for pickling is prepared from



90 parts water and 10 parts concentrated acid of  $64^{\circ}$  to  $65^{\circ}$  Bé (specific gravity 1.795–1.820). For cast iron, since hydrofluoric acid is not used, dilute sulphuric is taken, and heated by means of steam. Hydrochloric is preferable to sulphuric acid, being not only cheaper, but also causing less inconvenience in breathing. The acid must be free from arsenic, otherwise arseniuretted hydrogen will be evolved during the pickling, and this possesses a disagreeable garlic-like odour, and is, moreover, injurious to health.

It is advantageous to test the pickling agent daily for the amount of unused acid. A test quantity is titrated with semi-normal caustic soda solution to which a little sugar has been added to avoid oxidation of the dissolved ferrous salt. Phenolphthalein is used as indicator during the analysis. This test may be carried out in a few minutes by any intelligent workman.

If the frequent control of the acid liquor be neglected, it may happen that either too little or too much fresh acid will be added daily.

Sorel \* recommends the following for cast iron :—

96 parts sulphuric acid of  $10^{\circ}$  Bé.

4 „ tin salt ( $\text{SnCl}_2$ ), or zinc chloride ( $\text{ZnCl}_2$ ).

If the acid content be too small, the amount of ferrous salt in the acid baths will be too great, and

\* Dingler, *Polyt. Journal*, cvii. 446.

inadequate duty done ; besides, the cleansed crude ware will be tarnished by a yellow coating of ferric oxide.

If acid be added too frequently and in too great quantity, then the process will be too energetic. Iron will be dissolved unnecessarily at the expense of the excess of acid, and this quite apart from the material disadvantage due to acid waste.

A mud gradually settles on the floor of the acid vessel or vat, arising from the undissolved tin, separated ferric oxide, etc. The vat must therefore be cleaned out from time to time, and this is done by scooping out the mother liquor into a wooden vat (old casks) and allowing the mud to settle. The clear upper liquid is replaced in the pickling vat, and the required amount of fresh water and pure acid added.

A pickling solution prepared without the addition of old mordant liquor acts very slowly at first, a fact which may be traced to the catalytic influence of hydrogen gas dissolved in the acid. If at first the cleansing liquor has absorbed a relatively large amount of hydrogen, its activity will be brisk, and therefore the addition of the old mother liquor, which is rich in hydrogen, is necessary, as well as economical. The greater part of the pickling liquor is lost in adhering to the wares and to the particles torn from the acid bath.

To what degree loss of metal is caused by pickling is shown by the following example of a roll 20 cm. in diameter and of varying thickness :—

# THE PREPARATION OF THE CRUDE WARE. 75

## THE LOSS OF METAL DURING PICKLING.

Diameter of the Roll, in cm.	Thickness of the Metal, in mm.	Surface, in sq. cm.	Net Weight, in gr.		Loss due to Pickling (metallic loss).
			Before Heating and Cleansing.	After Cleansing.	
20	0'25	628	55	52'25	Per cent. 5'0
"	0'30	"	66	63'25	4'10
"	0'35	"	77	74'25	3'50
"	0'40	"	88	85'25	3'10
"	0'45	"	99	96'25	2'80
"	0'50	"	110	107'25	2'50
"	0'55	"	121	118'25	2'30
"	0'60	"	132	129'25	2'10
"	0'65	"	143	140'25	1'90
"	0'70	"	154	151'25	1'80
"	0'75	"	165	162'25	1'70
"	0'80	"	176	173'25	1'50
"	0'85	"	187	184'25	1'40
"	0'90	"	198	195'25	1'38
"	0'95	"	209	206'25	1'31
"	1'00	"	220	217'25	1'25

The crude wares suffer a loss in weight on pickling which averages 2-4 per cent. The problem as to which is the best material for making the most serviceable pickling vats is hard to solve. Tanks made of granite or earthenware are very durable, but too expensive and, moreover, limited in capacity. Also vessels prepared from slabs of glazed stone are unsatisfactory. The most suitable are those thoroughly coated inside with lead, which in its turn is covered by wood. Between the wood and lead Goudronteer or Frankfort asphalt is poured. A limpid pickling agent acts more quickly and saves any subsequent rubbing or scrubbing of the cleaned ware.



The metallic object to be pickled is placed in a latticed basket and set in the acid bath. The process lasts from 30-45 minutes, according to the concentration of the bath and the thickness of the metal. For the ware to remain too long in the acid is injurious, on account of partial decomposition of the material and the formation of so-called metallic blisters. The sheet metal is composed of many layers, and the pressure of the hydrogen evolved produces an inflation, *i.e.* a blister. A rusted crude article which has suffered much atmospheric exposure requires prolonged pickling, and becomes of inferior quality because of rust formation and the unequal action of the acid. The pickled ware is placed in a water tank in order that the greater part of the acid may be removed. The last traces of acid adhering are neutralised by dipping the objects in boiling soda, frequently merely milk of lime solution. The cleansed ware is then rapidly dried on a special drying hearth. This drying must follow as quickly as possible, to prevent fresh oxidation. Hollow handles, etc., require a specially careful and thorough drying.

Pickling hardware likewise requires much care. The ware remains in the hot 6-10 per cent. sulphuric acid about 1-1½ hours, is then placed in pure water, and finally in boiling soda solution. After it has been so treated, the cast is cleaned or scrubbed once more by wire brushes, using a large amount of water.

The harmless preparation and removal of the



acid liquor often involves expensive and difficult work. In several countries the legal regulations respecting this are very lax, but in Germany a conscientious observance of very stringent laws is strictly enforced.

Where sufficient running water is at hand, with which the waste acid liquors can mix in a minimum ratio of 1 : 10, the liquor-removal problem has a simple solution. In other localities the contrary is the case. By neutralising the acid liquor with milk of lime and soda, leading the same into oxidation reservoirs where the ferric oxide for the most part separates out and settles, filtering the neutral liquor through powerful filter presses in order to retain the last particles of mud, and then allowing this liquor to filter through land in percolating ponds, it is possible to remove in reality all danger of contaminating running water.

Some German enamel firms have set up complete plants for the thorough neutralisation and separation of mud from their acid liquors.

How far the purification of acid water may be accomplished in the manner described is shown by the following illustrations :—In a large German iron-works the impure acid waste liquor shows the follow-average composition :—

100 litres contain :

Sulphuric acid	.	.	.	70·08	gram.
Iron	.	.	.	43·96	„
Chlorine	.	.	.	0·62	„

After purification by neutralisation, filtration, etc., this waste liquor is made up as follows :—

100 litres water contain :

Solid constituents	.	.	.	6.920	gram.
(a) inorganic	.	.	.	5.080	„
(b) organic	.	.	.	1.840	„
Chlorine (Cl).	.	.	.	0.590	„
Sulphuric acid (SO <sub>3</sub> )	.	.	.	0.820	„
Lime (CaO)	.	.	.	1.600	„
Magnesia (MgO)	.	.	.	0.360	„
Iron (Fe)	.	.	.	0.003	„

The organic substance present in 100 litres, expressed in terms of potassium permanganate (KMnO<sub>4</sub>) = 1.94.

At all events the chemical purification of waste acid liquor has been carried out on a large scale with marked success.

## CHAPTER V.

### THE PROCESS OF ENAMELLING.

THE cleaned crude ware is further examined for accidental bruises, these being removed by beating out with a wooden hammer, a process now conducted in the principal workroom of the enamel works.

The coating of the cleaned utensil with enamel is done in accordance with definite rules and manipulations, and is known as the "laying" of the enamel. The workmen entrusted with the operation are called "enamellers."

The art of covering can only be acquired by long practice, and requires intelligent, educated workmen, since every kind of utensil, however different its shape, must be provided with the enamel coating by a suitable rolling movement.

There are distinguished the so-called "primary coating," the first white, the second white or protecting coat, and the coloured enamel coatings. An immediate covering or enamelling of the cleaned crude ware with white enamel is impossible, for the latter, by virtue of its composition, possesses an

expansion coefficient essentially different from that of iron. Moreover, the stannic oxide content of the white enamel brings about a blister development, since this oxide is reduced by the carbon present in the iron at the heat of the muffle. Before the white coating the crude ware must therefore be provided with an enamel cover possessing very definite chemical and physical properties. The enamel used is known as ground-enamel (*Grundemaille*), and is essentially an easily fusible substance, coloured by cobalt or nickel oxide with a little limonite. The requisite amounts of these oxides, in union with borax, give to the ground-enamel a coefficient of expansion approaching quite near to that of sheet iron. The same composition minus cobalt or nickel oxide would be useless.

The search for a ground-enamel free from cobalt and nickel oxide still remains a problem for the expert, and it may be safely asserted that the previous formulæ for such white primary enamels must be regarded as humbug.

In recent years partial success has been realised by replacing the expensive cobalt oxide in the ground-enamel with the much cheaper nickel oxide, but this requires careful attention, and the enamel so prepared is inferior to the cobalt oxide primary in stability and elasticity. For high-class wares a ground-enamel coloured by cobalt oxide is therefore employed.

The ground-enamel should be fairly dilute (40 per cent. water) and coarse-grained, and the primary



coating should be as thin as possible. A small plate of sheet metal coated with ground-enamel should, after the burning in of the enamel, be capable of being bent without the ground-enamel chipping off at the edge of the bend.

The average output of a man working with the ground-enamel lies between 200-300 pieces (150-300 kg.) for large, and from 300-1500 pieces (200-400 kg.) for small utensils, in the course of a ten-hour day. Naturally, such numbers are subject to great fluctuation, when the many varieties and sizes of utensils are taken into account.

The vessels covered with ground-enamel must be rapidly dried, and for this purpose specially constructed stands are used, which are heated by steam-pipes, or more generally by the hot gases from the muffle furnace. Should rapid drying be omitted, then rust easily develops, and the damp wares then exhibit rusty-brown stains. A moderate addition of borax frequently prevents this partial rust formation. In the case of ground-enamels used for cast iron or for matts the same treatment serves, yet in this case only borax which has been previously fused and dissolved in hot water is added.

Care must be taken that wares coated with primary enamel show no damaged metallic places after drying, since in the subsequent firing these places are changed to ferrous oxide and so give rise to faulty goods. An article carefully covered with primary enamel and then fired forms the basis for future treatment. A

covering ground-enamel prepared too concentrated is equally as bad as one too dilute. It is the business of the enamel master to be convinced repeatedly during the day of the consistence of the ground-enamel, for, should this be too fusible relative to the next coating, then a blister development in starry form will be found on the finished product.

The introduction of ground-enamels prepared from new formulæ should be cautiously made, since nothing can endanger the trade or inflict greater injury on the owner than a careless, hasty importation of a new ground-enamel.

The weight of ground-enamel necessary for 1 kg. crude ware, supposed to be of average metallic thickness, varies from 80–100 grm., *i.e.* 8–10 per cent. The firing of well-dried ground-enamelled sheet ware is conducted in the muffle furnace at a temperature of 950–1000° C., corresponding to the varying composition of the ground-enamels in the different works. The utensils, on being coated with ground-enamel, are submitted to a more severe burning in than that given for the next covering. The borax, which is present in ample proportions in the ground-enamel, requires a fairly large amount of heat to become a mobile liquid, and so unite intimately with the metal.

After the firing of the wares coated with ground-enamel, the next operation is the enamelling with white enamel. In the case of many inexpensive wares only one white coating is put on, but the

majority require a second. At this stage mention might be made of the circumstance that the great expectations entertained by the introduction of methods having for their object a single white coating have only been partly realised.

Every expert who, without wishing to deceive himself and others, would follow his convictions, must confess the unsuitability of the so-called single white coatings for special qualities of ware. The single white coating, since it must be laid on thicker to be sufficiently white, causes an average of 20-30 per cent. in repairs or patchwork. Moreover, the coverer will have his working capacity limited, and in reality will produce less than if two white coatings were put on. The patched wares generally require a further firing and another coating, so that such utensils are often unfavourably distinguished from other wares by their multitude of coats.

On the other hand, it is certain that for export, where often the tax is reckoned according to the weight and low price attached to wares which have only been white enamelled once, then what is lost in beauty is gained in the solidity consequent on a thinner enamel layer, since the thickness of the covering has a great influence on the durability of the ware, for the quality is inversely proportional to the thickness of the enamel layer, and directly to the cross section of the sheet metal.

For enamelled hardware the following data of enamel consumption hold good :—



The ground coating amounts to 0·90 per cent.,  
 The inner coating of white  
     enamel to . . . . . 4·20 „  
 The outer asphalt painting to . 0·24 „  
 And the loss on etching to . 0·30 „  
   of the final weight.

THE INCREASED WEIGHT OF METALLIC OBJECTS AFTER THEIR  
 PRIMARY COATING.

A Roll ( <i>Ronde</i> ) of Diameter, in cm.	Thickness of the Sheet Metal, in mm.	Surface, in sq. cm.	Net Weight, after Pickling, in grm.	Weight of the Roll after being coated by Ground- Enamel, in grm.	Consumption of Ground Enamel,	
					in grm.	per cent.
20	0·25	628	52·25	62·35	10·1	18·3
„	0·30	„	63·25	73·35	„	15·3
„	0·35	„	74·25	84·35	„	13·1
„	0·40	„	85·25	95·35	„	11·5
„	0·45	„	96·25	106·35	„	10·2
„	0·50	„	107·25	117·35	„	9·2
„	0·55	„	118·25	128·35	„	8·3
„	0·60	„	129·25	139·35	„	7·6
„	0·65	„	140·25	150·35	„	7·1
„	0·70	„	151·35	161·35	„	6·5
„	0·75	„	162·25	172·25	„	6·1
„	0·80	„	173·25	183·35	„	5·7
„	0·85	„	184·25	194·35	„	5·4
„	0·90	„	195·25	205·35	„	5·1
„	0·95	„	206·25	216·35	„	4·8
„	1·00	„	217·25	227·35	„	4·6

Objects which are to receive a second coating of white enamel should be as thinly enamelled as possible the first time. The second coat should give strength and appearance to the ware, and must be laid on with the greatest care.

Enamelled objects are usually provided with a red



enamelled border, which is prepared either after the first or, in some cases, only after the second coating.

A neat border gives a pleasing harmonious appearance to the ware, and therefore too much care cannot be exercised in its preparation.

Whether the so-called border or "anrollen" is made by hand or by rolling the utensil on a plane steel slab, depends on the respective works' routine. The bordering by means of a steel plate is made in a thin layer on the blue or black enamel, and gives a faultless edge.

The drying of the utensil enamelled in white or blue has usually to take place slowly, without the aid of a special source of heat, *i.e.* in the air. On the other hand, the white enamelled cast wares may be safely dried on a moderately heated hearth, and during the process every kind of vibration must be avoided.

It may be usually accepted that enamelled sheet wares are stable against rapid temperature change. Thanks to the present position of enamel technique, the preparation of a really durable ware is thoroughly understood. Where, however, a small capacity of resistance against abrupt temperature change is found, this may be traced to a variety of causes. The cover enamel must, under all circumstances, be suitable for the ground, just as the crude ware must be carefully prepared, in order to obtain the correct tension, especially at the base of the utensil. The basal curve of a forged utensil should be as round as possible, since the tension differences are expressed usually at the centre of the base. With respect to

this, a new process of a well-known enamel firm \* deserves mention, who attain an increased stability of the base by pressing in the centre diagrams standing in relief, such as trade-marks or similar impressions. The diameter of this relief should usually amount to one-seventh of the base. This idea is at all events worthy of note.

The total amount of enamel required by the finished enamelled sheet ware depends naturally on its size, and is usually expressed as a percentage of the final weight.

The following table shows the varying percentage enamel content of utensils of varying thickness :—

THE CONSUMPTION OF ENAMEL.

Thickness of Sheet, in mm.	Percentage Enamel Consumption.	
	Calculated upon the Initial Net Weight.	Calculation from the Final Weight.
0'10	128'0	56'0
0'20	64'0	39'0
0'30	43'0	30'0
0'35	37'0	27'0
0'40	32'0	24'0
0'50	26'0	20'0
0'60	21'0	17'6
0'70	18'0	15'5
0'80	16'0	14'0
0'90	14'3	12'5
1'00	12'5	11'0
2'00	6'4	6'0
3'00	4'3	4'0

\* Kl. 48c. Process for preventing the chipping away of the enamel on sheet-metal utensils in consequence of the unequal tension developed in the vessel by heat. D.R.-P. angem. St. 10,256. Stanz- und Emaillierwerk vorm Carl Thiel & Söhne, A.-G., Lübeck.

INITIAL WEIGHT OF METAL.

Thickness of Sheet, in mm.	1 Sq. Metre of Sheet weighs kg.	Thickness of Sheet, in mm.	1 Sq. Metre of Sheet weighs kg.
0·10	0·78	0·70	5·46
0·20	1·56	0·80	6·24
0·30	2·34	0·90	7·02
0·35	2·73	1·00	7·80
0·40	3·12	2·00	15·60
0·50	3·90	3·00	23·40
0·60	4·68		

Since most of the saleable utensils are prepared from sheet metal of 0·3–0·5 mm., the usual quantity of enamel required, amounting to 25–30 per cent., is calculated on the final weight of the object. In practice the true enamel consumption is really greater, in consequence of the unavoidable loss during the transit of the powdered enamel to the coating saucer, but chiefly during the covering operation itself. The object in all firms is to reduce to a minimum this over-consumption of enamel. The wash-waters from the separate coating saucers, as well as other enamel residues, are collected and carefully separated according to colour, in order that some may be directly used again after careful sieving for the first white covering, or remelted in the furnace and added to the colour enamel mixture. Only by noting exactly the enamel entry, and comparing this with the monthly production of enamelled wares, will one be able to determine the true amount of enamel consumption, and be in a position eventually to put a stop to waste.

## CHAPTER VI.

### FIRING THE ENAMELLED WARES.

THE so-called burning in or firing of the enamelled wares is conducted in the muffle, and has for its object the fusion of the enamel coating.

It has been mentioned that the burning in of the ground-enamel takes place at a high temperature ( $950-1000^{\circ}$  C.) and requires an average time of  $3-4\frac{1}{2}$  minutes. The white coating and also the blue require a somewhat lower temperature (about  $800-850^{\circ}$  C.) and a duration of  $3\frac{1}{2}-4$  minutes.

By an insufficient furnace temperature, or duration of burning in, the ware deteriorates in lustre.

At too high a temperature the white enamel will become glassy, lose its opacity, and appear common. The property of stannic oxide in producing opacity depends on the fact that, at a temperature up to  $900^{\circ}$ , it remains finely suspended in the molten enamel without dissolving, but at a higher temperature partial solution takes place, with the formation of tin silicate, which causes the white enamel to lose its covering power.



The modern furnaces have a muffle length of 1·80–2·50 m., a breadth of 80–110 cm., and a height of 70–95 cm. The muffles are composed of several shaped pieces or form single plates, but the latter are less worthy of recommendation. Double muffles, viz. two muffles heated by the same firing, are generally disadvantageous, since in case of repairs the first as well as the second muffle must be thrown out of action.

According to the mode of firing, the furnaces are distinguished as direct, semi-gas, or regenerative. With the increasing price of coal, direct firing is absolutely unprofitable, since a greater part of the heat is drawn away unused into the conduits. Semi-gas firing with stepped, plain, or fissured grates is most trustworthy, especially in works of average size where the heat is drawn away for use at the drying hearths.

Regenerative firing is, however, without a doubt the best, because it is technically the most complete. The fuel in the generators is transformed by incomplete distillation into carbon monoxide, and this combustible gas is burnt immediately to carbon dioxide in the conduits of the muffle by union with the previously heated air.

For the rational carrying out of the firing, the repeated analysis of the gases at the places where generated, viz. in the generator as well as immediately in front of the place of combustion (and therefore before union with the combustible air), is absolutely necessary. This analysis, together with

the examination of the conduit gases after combustion, affords the most certain guarantee for proper working, since it prevents the waste of coal and exposes defects.

It is important to know the content of carbon dioxide and carbon monoxide in the gas. Carbon monoxide varies from 20-30 per cent., while good generator gas should not contain more than 6 per cent. carbon dioxide. Through many generators steam is conducted for the purpose of obtaining an increase of temperature due to the partial formation of water-gas.

In this case the gas should contain :—

Hydrogen	.	.	.	up to 27 per cent.
Carbon monoxide	.	.	.	16-30 „
„ dioxide	.	.	.	3-13 „
Methane	.	.	.	1 „

The denser hydrocarbons are seldom present in gas generators.

The gas given off, *i.e.* the gas after combustion, should contain 18-19 per cent. carbon dioxide and 0.5-2 per cent. oxygen.

The average temperature of the gas produced varies from 1000-2000 C°.

The gas analysis is most appropriately carried out with an Orsat or Orsat-Schwackhöfer portable apparatus. This apparatus possesses three absorption vessels, the first being full of caustic potash solution (sp. gr.=1.26) for the absorption and determination of the carbon dioxide content; the second

is filled with mixture of pyrogallic acid (18 gr. in 40 c.cm. hot water) and caustic potash (sp. gr. = 1.28) to absorb the oxygen in the generator gas; and the last absorption vessel contains a cuprous chloride solution (35 gr. cuprous chloride + 200 gr. hydrochloric acid and 50 gr. of sheet copper turnings) to absorb the carbon monoxide. The manipulation of the apparatus is simple, and the analysis performed in a few minutes.

Gas analysis should generally find an extensive application in our industry, and up to the present this has been the case. The saving in coal realised by a well-regulated production of generator gas is very important.

At this stage a few words must be said concerning another measuring instrument, the use of which, for controlling the furnace temperatures necessary in a modern factory, is indispensable. This is the pyrometer or thermometer.

Distinction must be made between the water pyrometer, clay pyrometer or "segerkegel," electrical and optical pyrometers.

The segerkegel (clay pyrometer) consists of a small baked clay cone, which, corresponding to its varying content of alumina and silica, melts at different temperatures. In the enamel industry, where the temperatures employed vary from 800–900° C., clay pyrometers from Nos. 015 to 06 are chiefly used.

The connection between the number, chemical



composition, and temperature is given by the following table :—

Clay Pyrometer No.	Chemical Composition.				Temperature of Fusion.
015	$\left\{ \begin{array}{l} 0\cdot5 \text{ Na}_2\text{O} \\ 0\cdot5 \text{ PbO} \end{array} \right\}$	0·6 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot2 \text{ SiO}_2 \\ 1 \text{ B}_2\text{O}_3 \end{array} \right\}$		C. 800°
014	$\left\{ \begin{array}{l} 0\cdot5 \text{ Na}_2\text{O} \\ 0\cdot5 \text{ PbO} \end{array} \right\}$	0·65 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot3 \text{ SiO}_2 \\ 1 \text{ B}_2\text{O}_3 \end{array} \right\}$		830°
013	$\left\{ \begin{array}{l} 0\cdot5 \text{ Na}_2\text{O} \\ 0\cdot5 \text{ PbO} \end{array} \right\}$	0·7 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot4 \text{ SiO}_2 \\ 1 \text{ B}_2\text{O}_3 \end{array} \right\}$		860°
012	$\left\{ \begin{array}{l} 0\cdot5 \text{ Na}_2\text{O} \\ 0\cdot5 \text{ PbO} \end{array} \right\}$	0·75 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot5 \text{ SiO}_2 \\ 1 \text{ B}_2\text{O}_3 \end{array} \right\}$		890°
011	$\left\{ \begin{array}{l} 0\cdot5 \text{ Na}_2\text{O} \\ 0\cdot5 \text{ PbO} \end{array} \right\}$	0·8 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot6 \text{ SiO}_2 \\ 1 \text{ B}_2\text{O}_3 \end{array} \right\}$		920°
010	$\left\{ \begin{array}{l} 0\cdot3 \text{ K}_2\text{O} \\ 0\cdot7 \text{ CaO} \end{array} \right\}$	0·2 $\text{Fe}_2\text{O}_3$ 0·3 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot50 \text{ SiO}_2 \\ 0\cdot50 \text{ B}_2\text{O}_3 \end{array} \right\}$		950°
09	$\left\{ \begin{array}{l} 0\cdot3 \text{ K}_2\text{O} \\ 0\cdot7 \text{ CaO} \end{array} \right\}$	0·2 $\text{Fe}_2\text{O}_3$ 0·3 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot55 \text{ SiO}_2 \\ 0\cdot45 \text{ B}_2\text{O}_3 \end{array} \right\}$		970°
08	$\left\{ \begin{array}{l} 0\cdot3 \text{ K}_2\text{O} \\ 0\cdot7 \text{ CaO} \end{array} \right\}$	0·2 $\text{Fe}_2\text{O}_3$ 0·3 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot60 \text{ SiO}_2 \\ 0\cdot40 \text{ B}_2\text{O}_3 \end{array} \right\}$		990°
07	$\left\{ \begin{array}{l} 0\cdot3 \text{ K}_2\text{O} \\ 0\cdot7 \text{ CaO} \end{array} \right\}$	0·2 $\text{Fe}_2\text{O}_3$ 0·3 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot65 \text{ SiO}_2 \\ 0\cdot35 \text{ B}_2\text{O}_3 \end{array} \right\}$		1010°
06	$\left\{ \begin{array}{l} 0\cdot3 \text{ K}_2\text{O} \\ 0\cdot7 \text{ CaO} \end{array} \right\}$	0·2 $\text{Fe}_2\text{O}_3$ 0·3 $\text{Al}_2\text{O}_3$	$\left\{ \begin{array}{l} 3\cdot75 \text{ SiO}_2 \\ 0\cdot30 \text{ B}_2\text{O}_3 \end{array} \right\}$		1030°

The use of the clay pyrometer requires time and is, moreover, expensive. In a special clay vessel a series of clay pyrometers are placed, somewhere in between the fusion points of the extremes of which the temperature is believed to be, and the particular cone which melts after half an hour is noted. From the number of the cone the temperature present is obtained.

Siemens and Halske's electrical pyrometer, "Le Chatalier," is more agreeable to manipulate.



The most convenient of all, and the one from which the temperature may most quickly be obtained, is the optical pyrometer (*lunette pyrométrique*) constructed by Von Ducretel in Paris. The principle involved is the property of a shining body (*e.g.* the red glowing muffle) to give a sensitive colour which may be denoted by a certain angle of rotation. This angle varies according to the composition, *i.e.* colour of the light, and therefore according to the temperature. The angle of rotation corresponds to the angle of the incident light of a glowing body upon the plane of polarisation of a quartz disc. This apparatus, in the form of a small telescope, renders ready and satisfactory service, the muffle temperature being read almost exactly in a few seconds. The point of the apparatus is set at zero, and it is turned while observing the glowing muffle until the appearance of the rose tint.

After this slight theoretical deviation we turn again to the firing of the enamelled sheet ware, when the following might be mentioned :—

It will always be assumed that the position of the fuel chambers is under and about the muffle, and that the combustion or union of the gases with air takes place as far as possible at the fore end of the furnace. Where this is not the case, we shall see that the rear of the muffle will be overheated, and the front part underheated. Therefore the rear set of wares to be fired will be finished instantly, while in front the objects placed there will not be

fired sufficiently. Such an arrangement will naturally not suffice, and there will be inconvenience in consequence.

Odd wares suffer a deformation on firing, which must be set right again by treatment with a suitable shape. The operation is known as "Stösseln" (pestling), and must be performed immediately after firing, since the enamel has still a fiery glow and will therefore yield. As substratum for the form of the hot deformed objects a perfectly smooth horizontal iron slab serves, upon which an asbestos plate or a woven asbestos cloth is spread. A supplementary shape of the fired enamel cast ware is naturally impossible to obtain, as well as unnecessary.

The enamelled cast requires from 12–15 minutes for the proper burning in of the white enamel.

The outer black, tarry appearance remains so long as the ware is underheated.

The assortment of the wares to be fired should always take place immediately in front of the separate furnaces.

In every well-conducted works which depends principally on hand labour the unavoidable waste should not exceed 6–7 per cent.

A too strict supervision in order to reduce the unavoidable waste still further is unpractical, since the expense attached to it stands in no relation to the gain acquired.

The problem dealing with rational methods for reclaiming the crude ware from waste enamelled goods can scarcely at the present time be said to

have been solved. The enamel is removed from larger and more valuable pieces, especially cast wares such as baths, by means of the sand blast. The removal of the enamel chemically with fused caustic alkalies has not up to the present proved satisfactory. More important progress in this direction appears to have been achieved by a new patent by Gustav Spitz of Brünn.\*

The objects from which the enamel is to be removed are collected into a closed boiler and heated at a definite temperature under pressure with an alkaline or acid solution of fixed concentration.

The object from which enamel has been removed may be re-enamelled. The expensive enamel constituents may be reclaimed from the solution by well-known chemical processes for regeneration of the water solution.

This process actually gives good results with many firms, works economically, and appears to have succeeded in solving the question of removing the enamel satisfactorily from the waste goods by economical means.

**A Few Remarks on Mistakes in Manufacture and their Possible Causes.**—No branch of manufacture is dependent on such a number of factors for success as the ceramic industry generally, and the enamel industry in particular. With the best of intentions and the greatest indefatigability and experience, novel questions, fresh phenomena,

\* D. R.-P. Nr. 176,300, Kl. 48d, G 5, and foreign patent :  
“Process for the removal of enamel from enamelled objects.”



and new problems are continuously presenting themselves to the expert.

From the evidence afforded by the most complex errors, their cause cannot be fixed with certainty. The industry is unfortunately always dependent on too many conditions, viz. the quality of the sheet metal, the raw materials, the water, the construction of the furnace and temperature, on the heating, pickling, and enamelling, and finally on the composition of the enamel.

It is sought, below, to bring in a tabular form the most important failures in connection with their possible causes, but the author is well aware of the insufficiency and subjectivity of such a work. The nature of the flaws is ascribed by different experts to different causes, corresponding to local relations and individual experiences. A uniform law does not exist, but at all events the table should render service by the comparison of observations and investigations:—

POSSIBLE MISTAKES.	THEIR PROBABLE OR POSSIBLE CAUSES.
Chipping away of the enamel from the edges and base.	Incorrect heating of the crude ware. Moisture in the boards. Insufficient burning in of the ground-enamel. Scarcity of ground-enamel in places. A covering enamel which is too hard.
Development of scale or "nail-scratch" formation.	Incorrect heating of the crude ware. Insufficient heating. Defective composition of the primary enamel. An under-fused enamel, due to the furnace. The ground-enamel laid on too thickly. A badly burnt in ground-enamel, either at too low a temperature or not sufficiently long. Storage for too long a time of the fired ground-enamelled ware. Faults in the composition of the enamel.



POSSIBLE MISTAKES.	THEIR PROBABLE OR POSSIBLE CAUSES.
Development of hair-like cracks.	<p>The ground-enamel is too hard or too yielding in proportion to the cover-enamel.</p> <p>The muffle was not hot enough.</p> <p>The object had been burnt at the base instead of at the edges.</p> <p>The lime content in the clay. Too large an amount of felspar in the enamel.</p> <p>The enamel coated too thickly.</p>
The object after firing has a dull lustre.	<p>Gas emanation.</p> <p>The muffle walls not tight.</p> <p>Too large a silica, stannic oxide, or clay content.</p> <p>The glaze too hard.</p> <p>Impure acid water, when manipulating the drawing instruments.</p> <p>The object had been fired repeatedly, causing devitrification to set in.</p>
Blister development on the enamelled object, in definite, mostly parallel, directions.	<p>Flaws in the sheet metal. Cracked and impure metallic texture due to defective manufacture of the sheet metal.</p>
Irregular blister development.	<p>The moist enamel has been contaminated by organic substances, such as soapy water, etc.</p> <p>The crude ware was insufficiently heated and cleaned.</p> <p>The clay contained organic matter.</p> <p>The enamel was raw, <i>i.e.</i> not properly fused.</p> <p>The ware had been stored too long in a finished fired condition, when the glass and enamel absorbed carbon dioxide from the air, and then afterwards fired, <i>e.g.</i> when decorated.</p> <p>The grinding water was contaminated.</p> <p>Addition of excess of vehicle to the enamel.</p> <p>Accessory contamination of the dried ware by organic dust, rain, etc.</p> <p>The metallic texture destroyed by planing or pressing.</p>
Spot development on the fired utensil.	<p>The utensil may have been touched before firing with a perspiring hand, whereby reduction in places of the coloured metallic oxides sets in.</p>

This table showing the manifold possible mistakes is capable of further extension. At all events it emphasises the indispensability of absolute cleanliness, strict supervision of all the materials employed, and the thorough control of each separate stage in the process, even to the most minute detail.

## CHAPTER VII.

### THE DECORATION OF ENAMELLED OBJECTS—ENAMEL PAINTING.

SINCE the process of enamelling has no other purpose than to provide an object made from sheet or cast iron with a covering similar to porcelain in appearance, it is obvious that the enamel industry is not limited to covering utensils with one or two coloured enamels, but that attempts have also been made to utilise the secrets and art of porcelain painting. The process, from its nature, was capable of adaptation, and so it seemed desirable that the white porcelain-like enamel surface of a utensil should be decorated and painted. This new branch of enamel painting, a section of porcelain painting, has been for a long time the object of assiduous experiment and indefatigable care, with, however, continued success. He who has opportunity to admire the often artistically finished and decorated enamel wares in the show-case, will be entranced by the variety of the design and the distinguished impression which many of the decorated articles convey.

In general we may distinguish in the modern occupation of enamel painting three modes of decorating enamelled utensils: the exclusive hand-painting for especially high-class wares, decorating by means of transfers or impressions from etched steel plates (the so-called reprinting process), and finally the air-brush painting (*Spritzmalerei*).

Hand-painting in its artistic form is employed only for expensive articles such as toilet services, etc.

The preparation of ceramic transfer pictures is similar to that of chromo-lithographs, using enamel colours. Chromo-lithographic impressions are transferred to paper, and since these pictures on transference would adhere badly to the enamel surface, it is provided with a thin coating of collodion, which disappears when burning in the picture.

For a long time, in porcelain and enamel painting, the technical method used for producing toned coloured surfaces was by covering the enamel colour with linseed and lavender oil, and shading away these surfaces by means of a linen pad, and this has in later years found an increased use through the discovery of air-brush painting. The coloured enamels corresponding to the best oil colours, which have been very finely ground when moist, are thrown by means of air pressure from the tube of a spray diffuser. In this way expensive coloured surfaces may be reproduced by a simple method.

By using patterns made by spray painting effective decorations are produced.



The colours used in enamel painting consist, as a rule, exclusively of an intimate mixture of natural metallic oxides (cobalt, nickel, chromium, manganese, copper, lead, tin, uranium, and cadmium oxides) or metallic salts, together with the fluxes.

The flux material, or simply flux (known as *Fondant*), is nothing more than a very easily fusible flint glass or glass of similar composition.

The fluxes frequently contain lead, since lead compounds make possible a fiery, glossy, easily fusible flux. Since the colours for decorating purposes are only used for external ornamentation, any danger due to the use of lead flux is excluded. Nevertheless, a lead-free flux is very largely employed at the present time.

The flux must have a composition suitable for the various coloured bodies.

*E.g.*, an easily fusible flux :—

Flint	.	.	.	.	10 parts.
Red lead	.	.	.	.	38 „
Fused borax	.	.	.	.	40 „

For blue and iron red colours :—

Red lead	.	.	.	.	75–80 parts.
Silica	.	.	.	.	20–25 „

Carmine flux for carmine and purple :—

Red lead	.	.	.	.	11 parts.
Silica	.	.	.	.	33 „
Fused borax	.	.	.	.	55 „

For chromium green, blue-green, etc. :—

Red lead	. . . . .	73 parts.
Silica	. . . . .	18 „
Boric acid	. . . . .	9 „

Examples of an ordinary lead-free flux :—

Flint	. . . . .	3·0 parts.
Saltpetre	. . . . .	2·5 „
Stannic oxide	. . . . .	4·0 „

Or

Silica (pure white)	. . . . .	6–7 parts.
Chalk	. . . . .	2–3 „
Borax	. . . . .	9–10 „

The flux is first of all melted in a crucible, finely powdered, and ground in the dry mill together with the colour substances.

The addition of coloured bodies to the flux is made in varying proportions. The majority of the enamel works obtain the enamel colours ready for use from special firms, a method more worthy of recommendation than the preparation of these bodies in the works itself.

The firing of the decorated utensil requires much care and experience, and the decoration of the ware should take place as quickly as possible, for if it be stored too long, then on firing a blister development may possibly take place.

Regarding further artistic operations there remains little more to be said, since these are too many and various, and, moreover, are dependent on the taste and experience of each separate worker.

## CHAPTER VIII.

### DECORATION OF THE ENAMELLED WARE—PHOTO-CERAMICS.

THE intimate relation which exists between porcelain and enamel painting, as exhibited in the production of artistic effects by almost identical means and methods, suggests the similar production of photographs capable of being burnt in on enamelled objects. This kind of ornamentation has come to be a special branch of our industry, and deserves our closest attention.

The preparation of photographic coloured pictures capable of being branded meets with little difficulty.

Usually three processes are distinguished, but in practice the first is almost entirely used :—

#### I. Process using chromium salts :

- (a) The dust process (*Einstäubeverfahren*),
- (b) The pigment process,
- (c) The light printing process ;

#### II. Process using iron chloride ;

#### III. The substitution process.

The dust process, which is the most important and generally used, will now be described.

This process was invented in 1859 by two Frenchmen, Salmon and Garnier, on the principle that a mixture of potassium bichromate and gum, albumen, gelatine, etc., when exposed to the influence of sunlight, becomes insoluble.

On a glass plate covered with such a mixture, those places which are protected from the action of the light can retain a colour powder (in our case, therefore, an enamel colour) when scattered over, while the illuminated spots are not so capable. In this way, from a positive photograph on glass prepared in the usual way, a positive impression may be obtained in enamel colours, capable of being burnt in.

Six operations may be distinguished :—

1. A glass plate is covered with the mixture (chrome gelatine) sensitive to light and then dried.
2. The plate is exposed to light when under the positive.
3. The image is rendered visible by fusible colour powder, *i.e.* developed.
4. It is covered with collodion, treated with alkaline water to dissolve the chromium compounds, and transferred with the collodion layer to the enamel plate.
5. The collodion is removed by solution.
6. The image is then burnt in.



The chrome gelatine is prepared according to various formulæ. A cold saturated solution of potassium dichromate (100 grm.) in water (300 grm.) is made, and allowed to cool.

Further, a second solution is prepared from :—

Water	.	.	.	.	.	1 l.
Grape-sugar	.	.	.	.	.	50 grm.
Gum arabic	.	.	.	.	.	50 „
Honey	.	.	.	.	.	10 „
Sugar	.	.	.	.	.	20 „
Glycerine	.	.	.	{ 4 c.c. in summer.		
				{ 3 c.c. in winter.		
Alcohol	.	.	.	.	.	10 c.c.

Both solutions are carefully filtered, allowed to stand several hours, and the clear upper portions poured off into clean bottles.

Immediately before use (but not earlier) 100 c.c. from the first bottle are mixed with 250 c.c. from the second, and the mixture kept in the dark. A larger quantity is not prepared than will be required on the same day.

A second formula for the preparation of a fluid sensitive to light is the following :—

Water	.	.	.	.	.	100 c.c.
Sugar	.	.	.	.	.	10 grm.
Gum arabic	.	.	.	.	.	10 „
Potassium dichromate	.	.	.	.	.	4-5 „

Garin and Aymard, the well-known French photo-ceramic experts, prescribe :—

Water . . . . .	100 c.c.
Gum arabic . . . . .	5 gm.
Sugar . . . . .	10 „
Saturated solution of ammonium bichromate . . . . .	25 c.c.

In damp weather a little grape-sugar is added, and in very dry weather only 15 c.c. of ammonium bichromate.

For glass plates, on which the chrome gelatine is poured, only plate-glass is used, the size of which must always be smaller than the positive, in order to avoid fracture by expansion. The plate-glass must be most carefully cleaned. The solution is poured on in semi-darkness, the plate being held inclined.

For drying purposes the plate is laid upon a thick sheet-iron slab about 15 × 20 cm., which stands on two feet of 15 cm. and two of 20 cm. in height. Underneath a spirit-lamp is placed, and the whole warmed carefully for one or two minutes.

The exposure under the positive takes place in the usual copying frame, the glass side of the sensitive plate being underneath. The time of exposure in the sun is  $\frac{1}{2}$ –1 minute, 5–10 minutes in the shade, and here a photometer may be used with advantage. The light incident on the chrome-gelatinised glass plate renders these places insoluble, and therefore the fusible colour powder strewn over by means of an absolutely dry brush will not adhere to the exposed places. The shorter the time of exposure the darker will be the picture, this being the exact

opposite to the silver chloride process. After 20 to 30 seconds' exposure a veil of moisture forms, a sign that the exposure should soon terminate.

The operation is best conducted in broad daylight.

By sprinkling the colour powder the image will be slowly developed. The colour is spread over the plate several times by a brush, and no loose particles of colour must remain adhering. A correctly exposed picture develops by degrees. Through insufficient exposure and humidity of the materials a smearing of the picture may take place.

The picture is then washed to dissolve away the soluble chromium salt, and, in order not to injure the picture, a coat of collodion is given to it. After the developing process the picture may be retouched.

The transference of the image to the enamel plate is performed by the aid of leather viscose (1 litre collodion and 2-3 c.c. resinous oil). The picture is carefully freed from dust, the prepared collodion poured upon it, the picture lifted by the corners, and the glass plate laid in a dish with caustic potash solution (2 per cent.) until the yellow coloration has quite disappeared. The picture is placed in pure water, which is carefully changed twice, and to the last water a few drops of nitric acid are added to prevent the development of disturbing air-bubbles. The picture is now transferred to the enamel plate, allowed to dry, and then burnt in carefully in the muffle furnace.

Should the image be transferred with the collodion

side underneath, then a reversed picture will be obtained, so that when preparing the glass positive allowance must be made. (The negative is placed reversed in the copying camera.)

If the picture lies between the enamel plate and collodion, then the latter is dissolved by means of the following mixture :—

Alcohol . . . .	50 c.c.
Ether . . . .	50 „
Lavender oil . . . .	100 „
Turpentine oil . . . .	3 „

For colours the ordinary easily fusible enamel colours are used.

The second process, the process of sprinkling with iron chloride, is distinguished from the former in that the layer sensible to light becomes hygroscopic on exposure, and therefore the enamel colour adheres on the exposed places.

Poitevin offers the following formula :—

Water . . . .	100 c.c.
Ferric chloride . . . .	10 grm.
Tartaric acid . . . .	4 „

The exposure lasts 5–10 minutes.

Finally, the substitution process consists in the production of a positive collodion picture according to the negative to be copied, and in this, by treatment with gold, platinum, or iridium chloride solutions, the silver is replaced or substituted by another metal. Further particulars are to be found in Dr Paul



Ed. Liesegang's *Fusible Photographic Colour Pictures* (*Photographische Schmelzfarbenbilder*).

The photo-ceramic art occupies in many senses an elevated position. After some practice the production of relatively inexpensive enamel pictures capable of resisting wear and tear may easily and quickly be performed.

## CHAPTER IX

### STATISTICS AND GENERAL INFORMATION

THE enamelling of sheet and cast wares is almost exclusively performed by hand-labour, demanding application and manual dexterity of the worker. It is a fact worthy of note that nations called progressive—that is, who follow cultured occupations and have an undeniable inclination for invention and industrial activity—possess an increasingly small enamel industry. The smallness of the enamel industry in such countries may be traced to three causes : scarcity of sufficient technical skill ; more expensive mode of existence in these countries, with consequent higher wages ; together with the lack of the most important mineral products necessary for producing enamels. An industry which depends on skilled hand-labour is generally not compatible with too high wages. In proportion as the wages of all places rise with the times, and as the standard of life of the worker is improved, so must greater exertion be expended in order to compensate by progress in manufacture for the increased cost due to rising wages, higher price

for materials, etc. If this progress should not be caused by a rise, often too sudden, in the cost of production, then it must be due to more economical working. Experiments undertaken with the object of replacing hand-labour by the cheaper and more uniform working power of a machine have, in contrast with all other occupations, more or less missed fire in the ceramic and enamel industry. Every so-called coating machine designed for covering objects with enamel has been up to the present far removed from being a really efficient substitute for hand-labour. The difficulties in constructing such machines ridicule the inventive power of the engineer, especially those concerned with wares produced in many kinds and sizes, and in particular with the complicated rolling motion requisite for correct covering.

It may, however, be premature to exclude the possibility of sooner or later constructing a really successful coating machine, since the first steps have already been taken.

Another pressing question, full of deep concern to the interests of many firms, is the management of the works.

It is necessary in many firms to work in two sections, viz. day and night. This is so obviously a nuisance, that every firm should endeavour to work exclusively by day, with the natural exception of the furnace and some other special operations. Most enamel works, the foundation of which dates back thirty to forty years, began business in a

way suitable to the condition of the industry at that time, *i.e.* on a small scale. By the unprecedented growth of our industry, it has been necessary to enlarge the plant, and this with as little disturbance as possible. These extensions always lagged behind the increasing demand for enamelled goods, with the result that in the majority of works there was a permanent lack of space, necessitating two shifts working day and night in the factory. The manifold inconveniences attached to the night-shift from a productive, qualitative, as well as from a hygienic aspect are obvious, and it is just these facts which give a certain superiority to many of the more recent firms that work only by day.

**Competitors of Enamelled Kitchen Utensils.** — According as a definite branch of industry is understood to be in the ascendant, caused by growing need and intelligence in the use of common utensils designed for greater convenience, so will the indefatigable inventive spirit of mankind ever seek to displace an older industry by a new invention.

The unexampled success with which the enamel industry has displaced the unsuitable, ungainly, easily broken and therefore expensive earthenware from the kitchen, has in turn encouraged others to supplant the enamelled utensil with purely metallic vessels, such as nickel, aluminium, metal-plated, and other varieties. On the whole, however, this has met with little success.

A nickel vessel will always be a luxurious kitchen



utensil, and the spending capacity of the majority of consumers is limited, apart from the fact that the enamelled vessel is easily cleaned, and its appearance preferable both from a hygienic and æsthetic standpoint. The slightest amount of dirt is detected with ease.

Aluminium has generally proved disappointing, and has not fulfilled the great hopes entertained for it. More recently the proper channel for the use of aluminium has been discovered, which, however, is not to be sought for in the manufacture of household utensils, but in the great utility of the aluminium alloys for certain technical processes. Sheet aluminium is prepared to-day with a purity of 98 per cent., and exhibits among other things a peculiar behaviour towards water, and particularly towards moisture. For long the phenomenon could not be explained, viz. that aluminium utensils, which had been full of pure water, were afterwards frequently found to have undergone decomposition, forming aluminium oxide or alumina; and in like manner many an inoffensive bed-warmer made of aluminium exhibited after a little while a perforated surface. These perforations are surrounded by little white incrustations of the decomposition product, viz. alumina.

Experiments have shown that aluminium utensils which have not been most carefully dried after use (a particular in housekeeping which is never the case), under the influence of the moisture left behind and of the air, probably generate a feeble

galvanic current (aluminium, nickel, or iron content = 2 per cent., and carbonic acid from the air), whereby the water is electrolytically decomposed, and the oxygen so formed causes a partial oxidation of the sheet aluminium, forming a white incrustation of aluminium oxide. If added to this is the difficult process of cleaning, the small mechanical resisting capacity of sheet aluminium, together with the price, it may safely be said that no serious competition is threatened the enamel industry from this quarter.

In another direction, too, the same applies. To the degree that our industry has progressed, by virtue of which enamelled house utensils are produced at present absolutely free from poison, pleasing to the eye, durable and inexpensive, no noteworthy advance of the purely ceramic industry in the direction of manufacturing kitchen utensils can be recorded.

In addition, we have to note the versatility of the use of enamelled sheet or cast vessels for technical and hygienic purposes, such as the manufacture of door-plates, trade and industrial appliances, wainscot plates, hooks, screws, tubs, bottles, baths, wash-basins, water-closets and pipes.

Some statistical data, taken from the book by Dr Hermann Wuppermann already cited, will best illustrate the progress of the industry, especially in Germany and Austria-Hungary. To give absolutely reliable statistics of a relatively modern industry, taking into account the origin of the manufacture,

the original methods pursued by different firms, wages, and balance-sheets, is a difficult matter, and only capable of partial solution. Yet every stage in this industry must be regarded as progress.

As to-day we see the ramparts of many a town pulled down to afford the inhabitants more space and possibilities of expansion, so also in the enamel industry, corresponding to its progressive development, will many a cupboard, hitherto jealously locked up, be thrown open, without injury to the industry. True progress is rather to be sought in the training of a capable works personnel, in conscientious management, and in industry and the performance of duty on the part of all those employed.

In the year 1904 there existed about 71 enamel firms in Germany, which were spread chiefly over Saxony, Rhineland, Westphalia, and South Germany. The active capital in the German enamel industry is estimated at about  $2\frac{1}{2}$  to 3 millions sterling. The number of workers is taken in Germany as 22,000. In Austria-Hungary 12,000 workers may find employment in the enamel industry.

In addition a large number of workers are indirectly engaged in supplying the great demand for sheet-metal, paper, chemical products, etc.

The output of the separate works is different, and depends on the locality, management, and intelligence of the workers. One firm will produce more with the same number of workers than another. Equally decisive for the output of a works is the complete-



ness of its technical equipment. The quantity of enamelled sheet ware produced per annum in Germany is estimated at 70,000 to 85,000 tons. As an average price per kilo. of enamelled ware  $8\frac{1}{2}$ d. is accepted.

Single enamel firms show a yearly total of £400,000 to £450,000, and it is worthy of note that there is a continual tendency to enlarge existing works.

If the average value of the forged sheet metal be stated at 24s. per 100 kg., then the average sheet-metal consumption per annum for our industry in Germany may be put at 70,000 to 85,000 tons, with a value of about £850,000 to £1,000,000 sterling.

The highest price for sheet metal was paid in the year 1899, and was 32s. per 100 kg.

The dividends paid by the larger firms vary in different years, and, for example, in one firm were 10 per cent. (1898), 12 per cent. (1899), 8 per cent. (1900), 4 per cent. (1901), 4 per cent. (1902), 5 per cent. (1903), 7 per cent. (1904).

The number of workers engaged in single firms varies from 3000 to 4000.

For lighter work many women are engaged. The dangers to the worker in the enamel industry are, apart from the crude-ware manufacture, insignificant. The average working period is ten hours, but the furnace workmen are divided into three sections of eight hours.

The customs comparisons for different countries



throw considerable light on the enamel industry, which exports a part of its produce.

SUMMARY OF THE TAXES LEVIED ON ENAMELLED SHEET-METAL UTENSILS BY DIFFERENT STATES.\*

Germany . . . . .	7/6	per 100 kg. (per 2 cwt.).
Austria-Hungary . . . . .	42/6	" "
Sweden . . . . .	55/0	" "
United States of America, about	28/0	" " (40% of the value).
Belgium . . . . .	10/6	" " (15% " " ).
France . . . . .	24/0	" "
Switzerland . . . . .	17/7 $\frac{1}{4}$	" "
Russia . . . . .	59/0 $\frac{3}{4}$	" "
Roumania . . . . .	80/0	" "
Italy . . . . .	24/0	" "
Spain . . . . .	22/3 $\frac{1}{2}$	" "
Turkey . . . . . about	5/7 $\frac{1}{4}$	" " ( 8% of the value).
Denmark . . . . .	7/6	" "
The Netherlands . . . . .	3/6	" " ( 5% " " ).
Great Britain . . . . .	...	

Taxes on sheet iron when imported into Germany, according to the recent German tariff of 25th December, 1902 (Items 786-788), sheet metal :—

786. Crude, forged, turned, dressed, varnished : In thicknesses of more than 1 mm., 30s. per ton ; in thickness of 1 mm. or under, 46s. per ton.

A comment on items 786 and 788 is important, viz.:—"For sheet iron of smaller thickness than 5 mm. which is cut otherwise than rectangular (*i.e.* rolls) the tax is increased 25 per cent."

Finally, the export of enamelled sheet utensils from Germany may be noticed.

\* The data are likewise taken from the work of Dr Hermann Wuppermann, entitled *The Industry of the Enamelled Sheet-Metal Utensils in Germany*.

## ENAMELLED WARES.

	1907.	1906.	1905.	1904.	1903.	1902.
Total import . dz.*	3,737	5,784	3,451	3,612	3,959	3,872
Value in £ sterling	18,700	26,100	13,400	13,600	14,850	18,400
<i>From</i>						
France . dz.	—	266	944	1,034	1,240	1,125
Value	—	1,200	2,450	2,700	4,650	5,350
Austria-Hungary dz.	1,820	3,466	1,531	1,571	1,613	1,434
Value	—	16,550	7,050	7,250	6,050	6,800
Switzerland . dz.	564	489	58	87	23	46
Value	—	2,450	200	250	100	200
Total export : . dz.	295,149	288,575	266,218	243,441	238,658	209,949
Value	1,475,750	1,364,850	958,400	852,050	835,300	839,800
<i>To</i>						
Belgium . dz.	4,327	9,209	11,066	6,067	3,751	4,147
Value	—	42,700	39,850	21,250	20,150	16,600
Denmark . dz.	4,147	5,201	9,207	6,744	6,349	5,439
Value	—	23,300	33,150	23,600	22,200	21,750
France . dz.	4,873	5,597	5,106	5,410	6,845	5,727
Value	—	26,650	18,400	18,950	23,950	22,900
Great Britain . dz.	48,494	52,485	45,450	45,464	48,987	46,200
Value	—	248,250	103,600	159,150	171,450	184,800
Italy . dz.	14,044	13,068	13,772	10,717	8,783	9,989
Value	—	61,750	49,600	37,500	39,750	39,950
Holland . dz.	22,769	21,878	31,634	29,719	27,043	22,642
Value	—	102,000	113,900	104,000	9,465	90,600
Norway . dz.	1,804	2,120	2,019	2,409	1,588	1,525
Value	—	9,900	72,500	84,500	5,550	6,100
Austria-Hungary dz.	3,447	3,823	4,697	4,151	3,759	2,560
Value	—	17,650	16,900	14,550	131,500	10,250
Russia . dz.	24,101	18,665	16,326	14,123	14,430	13,437
Value	—	85,500	58,750	49,450	50,500	53,750
Finland . dz.	2,160	1,263	1,124	1,043	958	573
Value	—	6,200	4,050	3,650	3,350	2,300
Switzerland . dz.	4,556	6,212	9,664	6,650	6,202	5,452
Value	—	29,050	34,800	23,300	21,700	21,850
Spain . dz.	4,511	6,390	5,062	3,754	5,614	4,723
Value	—	30,550	18,200	13,150	19,650	18,900
Turkey in Europe dz.	2,379	2,089	1,300	1,558	1,176	1,104
Value	—	10,050	4,700	5,450	4,100	4,400
Turkey in Asia . dz.	1,359	1,112	1,158	1,092	935	688
Value	—	5,450	4,150	3,800	3,300	2,750
Egypt . dz.	3,043	2,406	1,942	4,945	3,819	2,574
Value	—	11,250	7,000	17,300	13,350	10,300

\* Dz. stands for 2 cwt.

ENAMELLED WARES—*continued.*

	1907.	1906.	1905.	1904.	1903.	1902.
British S. Africa dz.	4,081	4,782	4,482	4,284	11,040	9,710
Value	—	22,650	16,150	15,000	38,650	38,800
British W. Africa dz.	4,304	3,019	2,569	2,539	2,339	2,207
Value	—	14,550	9,250	8,900	8,200	8,900
British India . dz.	13,475	11,816	5,663	11,573	11,355	7,231
Value	—	57,100	20,400	40,500	39,750	28,950
Straits Settlements dz.	1,487	2,069	1,355	1,112	876	879
Value	—	9,850	4,850	3,900	3,050	3,500
China . . dz.	3,477	4,797	2,136	1,169	1,982	1,457
Value	—	23,200	7,700	4,100	6,950	5,850
Dutch Indies . dz.	3,814	3,498	1,971	1,644	651	979
Value	—	16,900	7,600	5,750	2,300	3,900
Argentina . dz.	10,985	12,044	10,518	8,963	7,748	2,268
Value	—	57,450	37,850	31,350	27,100	9,100
Brazil . . dz.	16,966	13,944	11,583	10,022	7,263	7,887
Value	—	66,800	41,700	35,100	2,540	31,550
Chili . . dz.	10,105	7,108	7,541	5,292	5,002	3,069
Value	—	33,200	27,150	18,500	17,500	12,300
Columbia . . dz.	1,899	1,989	2,108	3,018	2,068	982
Value	—	9,400	7,600	10,550	7,250	3,950
Cuba . . dz.	4,970	3,979	3,072	2,788	3,263	2,373
Value	—	18,900	11,050	9,700	11,400	9,500
Mexico . . dz.	8,261	6,957	6,529	5,487	4,546	4,426
Value	—	33,400	23,500	19,200	15,900	17,700
Peru . . dz.	2,905	1,989	2,218	2,226	1,411	1,667
Value	—	9,400	8,000	7,800	4,950	6,650
Uruguay . . dz.	2,512	1,956	1,676	774	1,310	799
Value	—	9,400	60,500	2,700	4,600	3,200
Venezuela . dz.	1,386	1,249	1,321	2,045	1,241	688
Value	—	5,850	4,750	7,150	4,350	2,750
U.S.A. . . dz.	24,776	24,544	19,620	15,864	16,725	21,563
Value	—	116,100	65,650	55,550	58,550	86,250
Federal Australia dz.	8,799	6,898	5,332	4,567	—	—
Value	—	32,300	19,200	16,000	—	—

The dashes in the preceding tables mean that the respective entries according to the official statistics cannot, at all events at present, be given.

We see from the foregoing tables the economic significance to which the enamel industry has attained. At the same time, however, the inference is drawn, that in proportion as our industry has spread in

different countries, the natural endeavour of each government has been to protect its home industry by high import taxes. The enamel industry is therefore always compelled to capture new markets, and by strenuous labour for fresh progress, for improvements, and for more efficient methods of working, to meet the difficulties of growing competition. Yet the greater the obstacles are, even more so will the spirit of invention work for the building up of our industry, and give always to our manufacture a new direction and a new impetus. In the economic war waged in all departments of industry, the palm of victory and success will fall to those firms that study the modern technical acquisitions, and unreservedly put into practice the doctrines of technical science.



## APPENDIX.

### EXTRACT FROM THE HISTORY OF THE ENAMEL ARTS AND OF ENAMEL ORNAMENTATION.

For a complete understanding of the natural evolution of the modern enamel industry applied to iron, a knowledge of the history of our predecessors in the enamel arts and enamel painting is necessary.

The enamelling of metals is of great antiquity, and the art has probably come from the Scythians, who introduced it into China at the time of the Emperor Thäiwonti. At all events the art was known in India before its introduction into China.

The Egyptians, Phoenicians, and Assyrians had already prepared enamelled jewellery, but during the period of classical culture the art remained Oriental, since neither the Greeks nor the Romans accomplished anything noteworthy in this direction.

The principal producing countries remained the Black Sea territories of Persia and North India, and from here the Byzantines transported the art into Europe about the eleventh century. The industry flourished especially in Italy, France, and Central Germany. Already the Merovingian epoch contained the rudiments of a primitive art of enamelling bronze utensils in Byzantine fashion.

It may almost be affirmed that up to the above period the enamel arts belonged to barbaric civilisation, while at this time the Indians of the Punjaub and the Persians

created truly masterpieces. These were the Sikhs of the Punjab, who employed enamels in the artistic crafts of Central India. In Lahore, the capital of Central India, the crude enamels were prepared from most remote times, and to-day these are sent to the Indian artists in Djeïpour and other places. These latter understand how to prepare truly artistic enamelled utensils, but not the crude enamels themselves. The artists of Lahore, Benares, and Lucknow still enjoy great authority.

In perfection these enamels were only equalled by the French, and but partially excelled, as we shall learn from the following short history of the enamel arts and enamel painting.

The original procedure for the preparation of artistic enamelled utensils was the so-called "champlevé." Portions of metallic objects were excavated, the intermediate parts thereby weakened were shaped into ornaments, and the cavities filled with different coloured enamels, which were then fired. After cooling, the object was ground so that the metallic edges appeared as the outline of the ornament. The "émail champlevé" was principally used in Rhineland and Limoges.

The second mode frequently employed, which at present has almost been lost, is characterised by the enamels being in cells each containing several colours, which were formed into geometrical figures, unless the intermediate spaces between the separate coloured enamel cells had been formed by metallic strips. The most antique objects discovered, made of enamelled bronze, were principally equestrian, etc. Next were found in 1866 artistic enamelled bottles in calabash form among the ruins of ancient Pinguentum (30 km. from Trieste), with medallions of Antonius the Pious (138-161).

At the beginning of the fifth century the barbarians overrunning Europe introduced another artistic enamelling method, viz. the "émail cloisonné." The ornamentation on the metallic surfaces was made with metal strips, which were soldered or gummed on, and the spaces filled with enamel, thus obtaining a brilliant mosaic. As the most antique example of this art may be mentioned the sword and jewels of Childeric, king of the Franks (465-481), discovered at Tournai in 1653.

The "émail cloisonné" was in the possession of certain families during the Middle Ages, and was then known as "electron." Justin I. (518-527) sent to Pope Hormisdas an enamelled lamp (*gabata elekrinam*).

We have to thank the monk Theophilus,\* who lived in the eleventh century, for many valuable historical communications respecting the art of enamelling. In his work Theophilus is also designated Rutgerus, whereby the theory of certain archæologists appears confirmed, viz. that a portable altar, worked in silver, which is to be found among the cathedral treasures at Paderborn, had been finished by a monk Rutcherus at Helmarshausen in Franconia about the eleventh century, who may be the Theophilus mentioned.

To the most antique objects of the "émail cloisonné," which are, together with the majority at this period, of Byzantine origin, belongs the famous iron crown of Theodolinde, crowned queen of Lombardy (A.D. 625), now in possession of the Cathedral of Monza, near Milan.

The shrine relics of the True Cross in the Church of St George at Limburg (Nassau) are among the most famous of the enamelled gold vessels. The following also belong to the eleventh century: the eight valuable enamelled gold plates which were discovered in 1860 while tilling a field

\* *Diversarum artium schedula.*



in Nyitra-Ivanka, in the Neutraer Comitatus, in Hungary, of which seven are to be seen in the museum at Budapest, these probably constituting the remnant of a crown ; and the figures of Constantine, Emperor of the Romans, also of the Empresses Theodora and Zöe, daughters of Constantine VIII. The crown of St Stephen in the castle at Budapest, which was presented by the Emperor Michael Ducas to King Geza I. of Hungary (A.D. 1077), belongs to the most noteworthy of the Byzantine enamelled works of art.

It may be mentioned that the Byzantine enamel artists were familiar with white, fiery-red, brown-red, deep-blue, green, and black enamels.

In Germany the Byzantine art was introduced under the reign of Otto II., son of Otto the Great. Otto II. married in 971 Theophanie, a daughter of the Roman Emperor at Byzantium and granddaughter of Constantine P. Orphiprogenetus. To the most antique art vessels of this period belong the three gold crucifixes in the church at Essen (already of German origin), which show insufficient technical knowledge. Henry II., the Saint, encouraged the art of enamelling and brought it to a higher perfection in Germany. About this period we meet for the first time the expression "smalture" for enamel.\* According to Littré, the name "émail" or "esmail" is derived from the Old High German "smelzen," "smaltzen," or "schmelzen." The Germans were the first to enamel copper objects in place of gold, whereby the art was greatly extended. At the same time the technique of the "émail champlevé" was simplified.

The difficulty of preparing certain parts of the body in enamel caused the German artists to execute the head, legs, and hands of figures in metal, and only articles of

\* Anastasius, *The Life of Leo IV.* (Gemnis et margaritis a. c. smaltis optimis adornatum).



clothing in enamel. Yet a further and later development caused an economy in metal for the whole figure, only the exterior being filled out with enamel (see the church treasures in Bamberg, Cologne, and the so-called Guelph jewels, etc.). From Cologne the new Rhenish art spread from France to Verdun, where at the beginning of the twelfth century a celebrated goldsmiths' school was founded.

This school belonged to the famous Nicolas of Verdun, who, in the College of Klosterneuburg, near Vienna, prepared the altar-cover or antependium in 1181, which was recast in the fourteenth century into an altar-top.\* About the time of Nicolas of Verdun the development of a specific French enamel art took place (the so-called school of Limoges).† This school rests on the Rhenish technique (*champlevé*), and from now onwards runs parallel with it. As an example of this period may be named a plate showing the vision of St Francis of Assisi, in the Louvre at Paris.

The enamel arts of the goldsmiths at Limoges continued to grow in importance, the artists of this town being summoned to England and other countries. This French school soon confined itself to enamelling the *fonds* (backgrounds) of artistic vases, while it deserted the real goldsmithing, *i.e.* the artistic execution of figures in gold, and quickly converted the art into an industry.

The *cloisonné* of the enamel, which on account of its technique gives to ornaments and figures a certain ungainliness and imperfection, was, after an interval of a century, first supplanted by the dainty, artistic, even if expensive, "*champlevé*." This revival is ascribed to the art of John of Pisa (1250-1358). From Italy the art of the "*émail*

\* G. Herder, *The Altar-top at Klosterneuburg*, Vienna, 1860.

† Ed. Garnier, *Histoire de la Verrerie et de l'Émaillerie*; Emile Molinier, *Dictionnaire des Émailleurs*, 1885.

champlevé" made its reappearance in France, Germany, and Holland. Proof specimens are to be found in the Benedictine monastery at Maibingen, near Nordlingen, in Bavaria.

As further technique, the translucent "à jour cloisonné" technique must be mentioned. The most antique works of this species are found mentioned in the inventory of the Vatican (*esmalta clara, esmaillo per quod videtur dies*). A beautiful goblet of Cosroë I., king of the Persians (A.D. 579), may be mentioned among the oldest discoveries of this art.

Finally we come to the last variety of the artistic enamels, viz. to the enamel covering on previously worked metallic objects, from which art our present iron enamel technique has finally evolved. This artistic enamel first appeared in the fourteenth century in France, Germany, and Italy. In the chapel at Alt-Oetting in Bavaria is found the so-called "Golden Rössel" (steed), a magnificent specimen of this art.

The gradual decay of the art of Limoges in the preparation of "émail champlevé" began in the fifteenth century. Forced by adverse circumstances, these artists discovered an enamelling process which would resuscitate the Limoges school and its art to a new life.\*

The masters of Limoges soon understood how to impress upon the artistic trade engaged in preparing enamel pictures the stamp of true art. The most famous representatives in this movement were Nardon Pénicaud (1503) and Jean Pénicaud.

About 1525 the art of enamel painting received a further impetus through the so-called "émail en grisaille." This simple process permitted the best artistic effects to be produced, and consisted essentially in that a thick black enamel layer was fused upon enchased and cleansed

\* Claudius Popelin, *L'Art de l'Email*, 1868.

copper objects, on which substratum a thin layer of white, finely powdered enamel was placed, which after drying allowed the black substratum to shine through. The desired pattern is traced on this surface and the white enamel round the contour is scratched away by means of a point, so that a kind of gray silhouette was obtained, which was once more burnt in. Afterwards the artist puts on more white enamel according to the requirements of the several parts, and so magnificent plastic figures or designs are obtained.

Among the most famous grisaille artists are the members of the Limosin family : Léonard Limosin (A.D. 1576), Léonard II. and François Limosin (A.D. 1646) ; further, the Nouailhers, viz. Pierre Nouailher, Jacques Nouailher (A.D. 1674), Pierre II. Nouailher ; again, Pierre Reymond (A.D. 1584), Pierre Courteys, Noël and Nicolas Laudin (A.D. 1682).

A kind of enamel painting consists in covering a copper plate with white enamel, and decorating it before branding with pulverised metallic oxides. After firing, pictures are produced similar to those obtained in faience, using a hotter fire. Painting on enamel decreased towards the end of the seventeenth century, but acquired new life under Louis XV. The principal artists of this period are Aubert, Liot, Taunay, J. B. Weyler, the Englishman Sikes (1752), Chodowiecky, the famous Graveur (A.D. 1801, in Berlin), Zincke of Dresden, Jeremias Meyer from Tübingen (A.D. 1789), and Collins from London.

Enamel painting in other countries affords no special items of interest up to the eighteenth century.

In Italy the art flourished in Florence, and is characterised by a special design of vessel. In Germany the once flourishing art decayed strongly in Cologne, although we meet in the eighteenth century the note-



worthy works of the Augsburg and Nuremberg enamellers (collection in the Museum at the Green Vault in Dresden). As representatives of this period Melchior Dinglinger (A.D. 1731) from Ulm, Wenzel Jamnitzer (1508-1586) from Nuremberg, Christof Jamnitzer (1563-1618), Hans Muelich or Mielick, and especially David Attemstetter from Augsburg, deserve mention. The enamel pictures are usually inferior to the French works. In Vienna worked Ph. H. Schindler from Dresden (1770), the Director of the Imperial Academy, who painted chiefly *Tabatières*. There may still be mentioned Jacob Bodmer from Nottingen (A.D. 1829, at Vienna).

In Spain enamel painting and art developed under difficulties, while the English enamels attained high credit; the enamel works at Battersea, founded by the Frenchman Etienne Théodore Janssen (1753), produced prominent works of art, characterised by their elegant design and the purity of their enamels and ornamentation. The English were the first to use the reprinting process for decorating purposes,\* in Battersea, Worcester, and Staffordshire. The art of enamelling experienced a new impetus in France about the middle of the nineteenth century, at which time Augustine (A.D. 1832) deserves mention. Thanks to the encroachment of the national manufacture at Sèvres, the half-forgotten art of Limoges has been raised from the dead. Single artists of this period, such as Meyer-Heine, Paul Avisse, and Apoil, directly rendered eminent service. Apoil was the first to execute real masterpieces of the enamelling art on an iron substratum.

Among the more recent French representatives of the art are Christofle and Falize, also Thesmar and James Tissot.

\* E. Molinier, *L'Emaillerie*, 1891.



## INDEX.

- ACID-PROOF enamel, 63.  
 Acids for pickling crude ware, 73.  
 Addition of vehicle to enamel, 59.  
 Additions on grinding, 58 *et seq.*  
 Air-brush, use of, in decoration,  
     100.  
 Alumina, in felspar, 6.  
 Aluminium utensils, 113.  
 Ammonium carbonate, 13.  
 Antimony, 16.  
 Application of the ground-  
     enamel, 79, 81.  
     of further coats, 84.  
 Arsenic in enamel, 66.  
 Artificial cryolite, 11.  
  
 BALANCE, importance of, in  
     works, 53.  
 Barium chromate, 29.  
 Black enamel, 21, 63.  
 Blast furnace, 53.  
 Blisters, 80, 97.  
 Blue enamel, 21, 62.  
 Boracic acid, 9.  
 Borax, 7.  
 Border, addition of, to enamelled  
     ware, 85.  
 Brown enamel, 24, 29.  
 Bruises, removal of, 79.  
  
 CADMIUM sulphide, 29.  
 Calcium fluoride, 7.  
 Carbonate of ammonia, 13.  
 Carmine, 31.  
 Cassius, purple of, 30.  
 Cast iron, 44.  
 Cause of mistakes, 95.  
  
 Charge at melt, 53.  
 Chipping, 96.  
 Chromic oxide, 26.  
     preparation of, 27.  
 Chromo-lithographs, 100.  
 Clay, addition of, to ground-  
     enamel, 58.  
     analysis and composition, 36.  
     pyrometer, 91.  
     sources of, 38.  
     treatment of, 38.  
 Coal, 41 *et seq.*  
 Coating-machines, 111.  
 Coating of enamel, application  
     of, 79.  
 Cobalt, 21, 80.  
     substitute for, 22, 80.  
 Colours used in painting on  
     enamel, 100.  
 Composition of some enamels,  
     68.  
 Consumption of enamel, 84, 86.  
 Copper oxide, 26.  
 Cracks, 97.  
 Crucible furnace, 53.  
 Crude ware, cleaning, 72.  
     heating, 70.  
     pickling, 72.  
     preparation of, 70.  
 Cryolite, 9.  
     artificial, 11.  
 Cupric oxide, 26, 28.  
  
 DECORATION of enamelled wares,  
     99, 103.  
 Deformation on firing, 94.  
 Drying, 81, 85.  
 Dullness, 97.

- ELECTRICAL pyrometer, 92.  
 Enamel, acid-proof, 63.  
   black, 24, 63.  
   black specks in, 14.  
   blue, 21, 62.  
   brown, 24.  
   carmine, 31.  
   coefficient of expansion, 22  
   consumption of, 84.  
   effect of high temperature on,  
     54.  
   formulae, 51 *et seq.*  
   green, 27.  
   grinding, 57.  
   lustrous, 33.  
   melting, 53.  
   mixing, 51.  
   preparation of, 50.  
   purple, 30.  
   removal of, 95.  
   rose-coloured, 29.  
   specific gravity of, 60.  
   splintering, 56.  
   use of antimony and lead in,  
     17.  
   violet, 24.  
   white, 51, 58, 63, 66.  
   yellow, 29.  
 Enamelled ware, decoration of,  
   99.  
 Enamelling, process of, 79.  
   history of, 121.  
 Enamels, composition of, 68.  
 Expansion of enamel, 22.  
   of iron, 22.  
 FELSPAR, 6.  
 Ferric oxide, 25.  
 Ferrous chromite, 29.  
 Firing the coated utensil, 88, 93.  
   deformation during, 94.  
 Flaws in the crude ware, 70.  
 Fluorspar, 7.  
 Formulae for enamel, 51 *et seq.*  
 Furnaces, 53, 89.  
 GLAZE, 16, 18, 64.  
 Gold salts, 29.  
   glance, 31.  
   recovery from waste, 33.  
 Green enamel, 26, 28, 58.  
 Grinding fused enamel, 57.  
 HAND-PAINTING on enamelled  
   wares, 100.  
   colours used in, 101.  
 History of enamelling, 121.  
 Hydrochloric acid, for pickling  
   crude ware, 73.  
   test for, 40.  
 IRON, cast, 44, 47.  
   oxide, 25.  
   sheet, 44.  
   storage of, 46.  
   use of fragments, 46.  
 KAOLIN, 36.  
 Kitchen utensils, 112.  
 LAYING on the enamel, 79.  
 Lead chromate, 29.  
   glaze, 18.  
   oxide, 18.  
   use of, 16.  
 Lignite, composition of, 42.  
 Limonite, 24.  
 Lustrous enamels, 33.  
 MANAGEMENT of the works, 111.  
 Manganese peroxide, 24.  
 Melting the enamel mixture, 53.  
 Metal, storage of, 46.  
 Mills for grinding fused enamels,  
   57.  
 Mistakes and their causes, 95.  
 Mixing enamel, 51.  
 Mixtures, examples of, 69.  
 Moulds for casting, 49.  
 NICKEL, 22, 80.  
   utensils, 112.  
 Night-shifts, 111.  
 OPACITY, 18, 88.  
 Optical pyrometer, 93.  
 PAINTING enamelled wares, 99.  
   colours used, 101.  
   spray, 100.

- Photo-ceramics, 103.  
Pickling the crude ware, 72.  
    acids for, 73.  
    loss of metal during, 75.  
    vats for, 75.  
Potash, 9.  
Potassium carbonate, 9.  
    nitrate, 9.  
Preparation of enamel, 50.  
    of the crude ware, 70.  
Purple of Cassius, 30.  
Pyrolusite, 24.
- QUARTZ, 7.
- REGENERATIVE firing, 89.  
Removal of enamel, 95.  
Repairs, 83.  
Rose-coloured enamels, 29, 58.  
Rutile, 19.
- SALTPETRE, 9.  
Sand-blast for crude ware, 72.  
Scaling, 96.  
Second coat of enamel, 84.  
Sheet iron, 44 *et seq.*  
Soda, 9.  
Sodium nitrate, 9.  
Spots, 97.
- Spray painting, 100.  
Stannic oxide, 14, 30.  
    substitutes for, 15.  
Sulphuric acid, 25, 40.  
    for pickling, 73.
- TEMPERATURE during prepara-  
    tion of enamel, 54.  
    during firing, 88.  
    during measuring, 91.
- Tin, 14, 30.  
    scarcity of, 17.  
    substitute for, 15.  
Titanium oxide, 19.  
Transfers, 100.
- URANIUM salts, use of, 29.
- VATS for pickling crude ware, 75.  
Vehicle, addition of, to enamel, 59.  
Violet enamel, 24.
- WARES, preparation of crude, 70.  
Water, 39.  
White enamel, 51, 58, 63, 66.  
    effect of temperature on, 88.
- YELLOW enamel, 29, 58.





**CHARLES GRIFFIN & COMPANY,  
LIMITED.**

**A SELECTION FROM  
CHARLES GRIFFIN & CO.'S PUBLICATIONS.**

**SCIENTIFIC AND TECHNICAL WORKS.**



MESSRS. CHARLES GRIFFIN & COMPANY'S PUBLICATIONS may be obtained through any Bookseller in the United Kingdom, or will be sent on receipt of a remittance to cover published price and postage. To prevent delay, Orders should be accompanied by a Cheque or Postal Order crossed "UNION OF LONDON AND SMITH'S BANK, Chancery Lane Branch."

Telephone—  
1634 City.

**LONDON:**

Telegrams—  
Explanatus.

**12 EXETER STREET, STRAND.**

M.T. 64. 3-X.

	PAGE		PAGE
ADAMS (W. P.), Motor Car Mechanism, -	21	KNECHT & RAWSON, Dyeing, -	6
AITKEN (T.), Road Making, -	63	LAFAR, Technical Mycology, -	58
ALFORD (C. J.), Mining Law, -	42	LAMBERT, Glue, Gelatine, &c., -	65
ALLINGHAM (W.), Meteorology, -	84	LARARD (C. E.), Eng. Calculations, -	25
ANDREWS (L.), Electricity Control, -	29	LAW (E. F.), Alloys, -	49
ANGLIN (S.), Design of Structures, -	15	LAWN (J. G.), Mine Accounts, -	42
ARCHBUTT & DEELEY, Lubrication, -	22	LEEDS (F. H.), Acetylene, -	61
ATHERTON (Wm.), Design of Beams, -	15	LIECKFELD (G.), Oil Motors, -	21
BARKER (D. W.), Works, by, -	33, 34	LIVERSIDGE, Engine-Room Practice, -	19
BERINGER (J. J. & C.), Assaying, -	51	MACKENZIE (T.), Mechanics, -	35
BIEBEL & LARSEN, Explosives, -	43	MACLEOD (W. A.) and WALKER (O.), Metallurgical Chemistry, -	51
BILES (Prof.), Works, by, -	19, 31	MACLAREN (R. S.), Elem. Mech. Eng., -	23, 75
BJORLING (P. R.), Peat, -	59	McMILLAN (W. G.), Electro-Metallurgy, -	52
BLACKMORE (E.), Mercantile Marine, -	33	— & BORCHERS, Electric Smelting, -	52
BLOUNT & BLOXAM, Chemistry, -	55	McWILLIAM, Foundry Practice, -	53
BLYTH (A. Wynter), Foods and Poisons, -	56	MASTUN (J.) Scientific Romances, -	76
BOHLE & ROBERTSON, Transformers, -	29	MIDDLETON (S.), Hydrographic Surveying, -	16
BOHRENS (Dr.), Electric Smelting, -	52	MILL (Dr. R. H.), Water Supply, -	61
BROUGH (R. H.), Mine Surveying, -	41	MILLAR (W. J.), New Lands, -	45
BROWNE (W. R.), Works by, -	26	MILLAR (W. J.), Latitude & Longitude, -	56
BRUCE (Robt.), Food Supply, -	45	MITCHELL (C. A.), Flesh Foods, -	56
BUCK (R. C.), Algebra & Trigonometry, -	35	— & HEPWORTH (T. C.), Inks, -	65
BURNS (D. J.), Colliery Electricity, -	42	MORGAN (J. J.), Works by, -	52, 53
BUTLER, Carburettors, -	21	MUNRO & JAMIESON'S Elect. Pkt.-bk., -	30
BUTTERFIELD, (W. J. A.), Gas, -	61	MUNRO (R. D.), Works by, -	23
CAIN & THORPE, Synthetic Dyestuffs, -	66	NAYLOR (W.), Trades' Waste, -	60
CARTER (H. R.), Long Fibre Spinning, -	67	NICHOLSON (W.), Smoke Abatement, -	60
CASTELL-EVANS, Chemical Tables, -	55	NORMANDY (F.), Sea Water Distillation, -	17
CHATELY (H.), Works by, -	23, 31	NORTH (S.), Oil Fuel, -	54
CLARK (J.), Soil Bacteria, -	57	OPPENHEIMER (C.), Works by, -	58
CLAYWORKER'S HANDBOOK, -	59	OSMOND & STEAD, Micro. Anal. Metals, -	52
COLE (Prof. G. A. J.), Works by, -	46, 71	PARK (J.), Works by, -	11, 44
COLE (W. H.), Light Railways, -	20	PEARCE (W. J.), Painting, -	64
COLLINS (H. F.), Lead and Silver, -	49	PETTIGREW (W. F.), Loco. Eng., -	20
COX (S. H.), Prospecting for Minerals, -	45	PHILLIPS & BAUERMAN, Metallurgy, -	51
CROTCH (A.), Telegraphic Systems, -	30	PHIPSON (Dr. T. L.), Earth's Atmosphere, -	46
CUNNINGHAM, Docks and Harbours, -	16	POYNTING (J. H.), Mean Density, -	72
DAVEY (H.), Pumping Machinery, -	17	— & THOMSON, Physics, -	73
DAVIS (J. R. A.), Works by, -	70	PRAEGER (R. L.), Open Air Botany, -	71
DIXON (C.), Bird Life, -	71	PUPPE (J.), Rolling Mills, -	23
DONKIN (Bryan), Works, -	22	RANKINE'S Works, -	28
DUERER (Geo.), Bleaching, &c., -	68	RAWSON, GARDNER, & LAYCOCK, Dictionary of Dyestuffs, -	66
DUNBAR (Prof.), Sewage Treatment, -	60	BEDGRAVE (G. R.), Cements, -	60
DUPRE & HAKE, Manual of Chemistry, -	69	REDWOOD (Sir Boverton), Petroleum, -	54
EIEHHORN, Wireless Telegraphy, -	29	— & THOMSON, Handbook, Petroleum, -	54
ETHERIDGE (R.), Geology, -	46	REED (Sir E. J.), Stability of Ships, -	31
FARNSWORTH, Cons. Steel Work, -	15	REID (Geo., M.D.), Sanitation, -	62
FARRELL (F. J.), Dyeing and Cleaning, -	68	RICHMOND (H. D.), Works by, -	57
FIDLER (Prof.), Bridge Construction, -	15	RIEMER (J.), Shaft Sinking, -	43
FIELD (E. R.), Mining Report Book, -	42	ROBERTS-AUSTEN, Metallurgy, -	48
FOSTER (Sir C. Le Neve), Works by, -	39	ROBINSON (Prof.), Hydraulics, -	17
GAIRNS (J. F.), Loco. Compounding, -	20	ROSE (T. L.), Gold, Metallurgy of, -	48
GATEHOUSE (F.), Cement Handbook, -	60	ROTHWELL (C. F. S.), Textile Printing, -	67
GINSBURG (Dr.), Shipmasters' Duties, -	36	SCHWARTZ (Dr. von), Fire Risks, -	61
GISSING (F. T.), Peat, -	59	SEATON (A. E.), Works by, -	13
GOLDING (H. A.), Bonus Tables, -	25	SEXTON (Prof.), Works by, -	51, 69
— Horse-Power Computers, -	25	SHELLON-BEY, Mechanic's Guide, -	26
GROSSMAN (J.), Chem. Engineering, -	69	SHOWELL (P. G.), Navigation Definitions, -	37
GRUNWALD (J.), Enamelling on Metal, -	63	SINDALL, Paper Technology, -	59
GULLIVER (G.), Metallic Alloys, -	52	SMITH (C. A.), Suction Gas Plants, -	27
GURDEN (R.), Traverse Tables, -	25	SMITH (J. W.), Dustless Roads, -	61
GUTTMANN (O.), Blasting, -	43	SMITH (Prof. R. H.), Works by, -	26
HALSE (E.), Spanish Mining Terms, -	67	SMITH (W.), Shipmasters' Medical Help, -	26
HANNAN (W. L.), Textile Fibres, -	42	SOLOMON (H. G.), Electricity Meters, -	29
HARBORD (J. W.), Steel, -	50	SOLO, Ceramic Literature, -	59
HARRISON (J. W.), Sanitation, -	62	STEWART (R. W.), Elementary Physics, -	72
HEIL & ESCH, Rubber Goods, -	65	STRICKLAND (F.), Petrol Motors, -	21
HEWLETT (G.), Dist. Sea Terms, -	37	SUPLEE (H. H.), Mech. Pocket-Book, -	26
HEYLIN (H.), Cot. Weavers' Handbook, -	67	— The Gas Turbine, -	22
HICKS (J. A.), Mineral Oil Testing, -	54	SYKES (Dr. W. J.), Brewing, -	58
HOBBS (L.), Engine Design, -	18	TRAILL (T. W.), Boilers, -	19
HODGSON (R. E.), Emery Grinding, -	23	TROTMAN (S. R.), Leather, -	65
HOOGHWINKEL (G.), Signalling in Mines, -	43	TUNZELMANN (G.), Electrical Theory, -	30
HUGHES (H. W.), Coal Mining, -	40	TURNER (Thos.), Works by, -	50, 51, 53
HUGHES-GIBB (Mrs.), Works by, -	70	WALTON (T.), Works by, -	32, 36
HURST (Chas.), Works by, -	24	WANG (C. Y.), Antimony, -	50
HURST (G. H.), Works by, -	64	WEBER (Dr. C. O.), India Rubber, -	65
INGLE (H.), Agricultural Chemistry, -	57	WELLS (S. H.), Engineering Drawing, -	24
JAGGER (J. E.), Mechanical Drawing, -	24	WIGLEY (T. B.), Jeweller's Art, -	53
JAMIESON (Prof.), MANUALE, -	27	WILLOUGHBY (Dr. E. F.), Milk, -	57
JOHNSON (J. C. F.), Getting Gold, -	44	WOOD (Francis), Sanitary Engineering, -	62
JUDE (A.), Steam Turbine, -	19	WORDINGHAM, Electrical Stations, -	29
JULIAN (H. F.) and SMART (E.), Cyaniding Gold and Silver Ores, -	44	WRIGHT (Dr. A.), Oils and Fats, -	55
KASSNER (T.), Gold Seeking, -	44	ZERR & RUBENCAMP, Colour Manuf., -	64
KERR (G. L.), Works by, -	40		

FIFTH EDITION, Revised. In Large 8vo. Pp. i-xxiv + 511. With 255 Diagrams, Examples, and Tables, and a Chapter on Foundations. Cloth, 16s.

## THE DESIGN OF STRUCTURES:

A Practical Treatise on the Building of Bridges, Roofs, &c.

By S. ANGLIN, C.E.,

Master of Engineering, Royal University of Ireland, late Whitworth Scholar, &c.

"We can unhesitatingly recommend this work not only to the Student, as the BEST Text-Book on the subject, but also to the professional engineer as an EXCEEDINGLY VALUABLE book of reference."—*Mechanical World*.

In Large Crown 8vo. Cloth. Pp. i-xiv + 236. With 201 Illustrations. 6s. net.

AN INTRODUCTION TO

## THE DESIGN OF BEAMS, GIRDERS, AND COLUMNS IN MACHINES AND STRUCTURES.

With Examples in Graphic Statics.

By WILLIAM H. ATHERTON, M.Sc., M.I. MECH. E.

"A very useful source of information. . . . A work which we commend very highly."—*Nature*.

FOURTH EDITION, Thoroughly Revised. Royal 8vo. Pp. i-xxx + 456. With 239 Illustrations in the Text, and 13 Lithographic Plates. Handsome Cloth. Price 30s.

## A PRACTICAL TREATISE ON BRIDGE-CONSTRUCTION:

Being a Text-Book on the Construction of Bridges in Iron and Steel.

FOR THE USE OF STUDENTS, DRAUGHTSMEN, AND ENGINEERS.

By T. CLAXTON FIDLER, M. Inst. C. E.,

Late Prof. of Engineering, University College, Dundee.

"The new edition of Mr. Fidler's work will again occupy the same CONSPICUOUS POSITION among professional text-books and treatises as has been accorded to its predecessors. SOUND, SIMPLE, AND FULL."—*The Engineer*.

In Medium 8vo. Pp. i-xv + 248. With 103 Illustrations. Price 10s. 6d. net.

## CONSTRUCTIONAL STEELWORK:

Being Notes on the Practical Aspect and the Principles of Design, together with an Account of the Present Methods and Tools of Manufacture.

By A. W. FARNSWORTH,

Associate Member of the Institute of Mechanical Engineers.

"A worthy volume, which will be found of much assistance. . . . A book of particular value."—*Practical Engineer*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



SECOND EDITION, Revised. In Large 8vo. Handsome Cloth, Gilt.  
With 37 Folding Plates and nearly 500 Illustrations in  
the Text. 30s. net.

## The Principles and Practice of **DOCK ENGINEERING.**

By BRYSSON CUNNINGHAM.

### GENERAL CONTENTS.

Historical and Discursive.—Dock Design.—Constructive Appliances.—  
Materials.—Dock and Quay Walls.—Entrance Passages and Locks.—  
Jetties, Wharves, and Piers.—Dock Gates and Caissons.—Transit Sheds  
and Warehouses.—Dock Bridges.—Graving and Repairing Docks.—  
Working Equipment of Docks.—INDEX.

"We have never seen a more profusely-illustrated treatise. It is a most important  
standard work, and should be in the hands of all dock and harbour engineers."—*Steamship.*

"Will be of the greatest service to the expert as a book of reference."—*Engineer.*

In Large 8vo. Pp. i - xii + 283. With 18 Plates, 11 Tables, and 220  
Illustrations in the Text. 16s. net.

### A COMPANION VOLUME TO "DOCK ENGINEERING."

## THE PRINCIPLES AND PRACTICE OF **HARBOUR ENGINEERING.**

By BRYSSON CUNNINGHAM.

CONTENTS.—Introductory.—Harbour Design.—Surveying, Marine and  
Submarine.—Piling.—Stone, Natural and Artificial.—Breakwater Design.—  
Breakwater Construction.—Pierheads, Quays, and Landing Stages.—  
Entrance Channels.—Channel Demarcation.—INDEX.

"The best and most complete book we have seen on the subject."—*Steamship.*

"This is a standard work . . . sure to prove a valuable book of reference."—  
*Shipping World.*

In Crown 8vo. Handsome Cloth. Fully Illustrated.

## **HYDROGRAPHIC SURVEYING.**

For the Use of Beginners, Amateurs, and Port and  
Harbour Masters.

By COMMANDER S. MESSUM, R.N.,

Instructor in Nautical Surveying, R.N. College, Greenwich.

CONTENTS.—Sextant.—Protractor.—Station Pointer.—Theodolite.—Projections.—  
Symbols and Abbreviations.—Plotting and Triangulation of a Small Plan.—Mast-head  
Angle Survey.—Meridian Distances.—APPENDIX.—INDEX.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



THIRD EDITION, *Thoroughly Revised and Enlarged.* Pp. i-xvi + 227.  
With 60 Plates and 71 other Illustrations. Handsome Cloth. 25s. net.

## HYDRAULIC POWER

AND

### HYDRAULIC MACHINERY.

By HENRY ROBINSON, M.INST.C.E., F.G.S.,

FELLOW OF KING'S COLLEGE, LONDON; PROF. EMERITUS OF CIVIL ENGINEERING,  
KING'S COLLEGE, ETC., ETC.

CONTENTS.—Discharge through Orifices.—Flow of Water through Pipes.—Accumulators.—Presses and Lifts.—Hoists.—Rams.—Hydraulic Engines.—Pumping Engines.—Capstans.—Traversers.—Jacks.—Weighing Machines.—Riveters and Shop Tools.—Punching, Shearing, and Flanging Machines.—Cranes.—Coal Discharging Machines.—Drills and Cutters.—Pile Drivers, Excavators, &c.—Hydraulic Machinery applied to Bridges, Dock Gates, Wheels and Turbines.—Shields.—Various Systems and Power Installations.—Meters, &c.—INDEX.

"The standard work on the application of water power."—*Cassier's Magazine*.

*Second Edition, Greatly Enlarged.* Pp. i-xiv + 336. With Frontispiece,  
12 Plates, and 279 other Illustrations. 21s. net.

THE PRINCIPLES AND CONSTRUCTION OF

## PUMPING MACHINERY

(STEAM AND WATER PRESSURE).

With Practical Illustrations of ENGINES and PUMPS applied to MINING,  
TOWN WATER SUPPLY, DRAINAGE of Lands, &c., also Economy  
and Efficiency Trials of Pumping Machinery.

By HENRY DAVEY,

Member of the Institution of Civil Engineers, Member of the Institution of  
Mechanical Engineers, F.G.S., &c.

CONTENTS.—Early History of Pumping Engines.—Steam Pumping Engines—Pumps and Pump Valves—General Principles of Non-Rotative Pumping Engines.—The Cornish Engine, Simple and Compound—Types of Mining Engines.—Pit Work—Shaft Sinking—Hydraulic Transmission of Power in Mines—Electric Transmission of Power—Valve Gears of Pumping Engines.—Water Pressure Pumping Engines—Water Works Engines—Pumping Engine Economy and Trials of Pumping Machinery—Centrifugal and other Low-Lift Pumps—Hydraulic Rams. Pumping Mains, &c.—INDEX.

"By the 'one English Engineer who probably knows more about Pumping Machinery than any other.' . . . A VOLUME RECORDING THE RESULTS OF LONG EXPERIENCE AND STUDY."—*The Engineer*.

*In Large Crown 8vo. Handsome Cloth. Fully Illustrated. 6s. net.*

## SEA WATER DISTILLATION.

By FRANK NORMANDY, of the Middle Temple, Barrister-at-Law.

CONTENTS.—Distilling Machinery.—Sea Water.—Steam.—Multiple Distillation.—The Evaporator.—The Distilling Condenser.—Pumping Machinery.—Useful Memoranda.—The Filter, Prevention of Corrosion and Decay of Metals, Removal of Scale, Cleaning, Overhauling, &c.—INDEX.

"The analytical treatment of the problem is concise and comprehensive in its scope."  
—*Marine Engineer*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET STRAND.

SIXTEENTH EDITION, *Thoroughly Revised. Large 8vo, Cloth.*  
 pp. i-xxiv+712. *With 250 Illustrations, reduced from*  
*Working Drawings, and 8 Plates. 21s. net.*

## A MANUAL OF MARINE ENGINEERING:

COMPRISING THE DESIGNING, CONSTRUCTION, AND  
WORKING OF MARINE MACHINERY.

By A. E. SEATON, M.I.C.E., M.I.Mech.E., M.I.N.A.

GENERAL CONTENTS.—PART I.—Principles of Marine Propulsion.  
 PART II.—Principles of Steam Engineering. PART III.—Details of  
 Marine Engines: Design and Calculations for Cylinders, Pistons, Valves,  
 Expansion Valves, &c. PART IV.—Propellers. PART V.—Boilers.  
 PART VI.—Miscellaneous.

"The Student, Draughtsman, and Engineer will find this work the **MOST VALUABLE**  
**HANDBOOK** of Reference on the Marine Engine now in existence."—*Marine Engineer.*

TENTH EDITION, *Thoroughly Revised. Pocket-Size, Leather. 8s. 6d.*

## A POCKET-BOOK OF MARINE ENGINEERING RULES AND TABLES, FOR THE USE OF

**Marine Engineers, Naval Architects, Designers, Draughtsmen,  
Superintendents and Others.**

By A. E. SEATON, M.I.C.E., M.I.Mech.E., M.I.N.A.,

AND

H. M. ROUNTHWAITE, M.I.Mech.E., M.I.N.A.

"The best book of its kind, and the information is both up-to-date and reliable."—  
*Engineer*

In Large 8vo. Handsome Cloth. With Frontispiece, 6 Plates,  
 65 other Illustrations, and 60 Tables. 12s. 6d. net.

## THE SCREW PROPELLER

And other Competing Instruments for Marine Propulsion.

By A. E. SEATON, M.I.C.E., M.I.Mech.E., M.I.N.A.

"Contains all that is useful to know about the screw propeller. . . . Thoroughly  
 up-to-date."—*Steamship.*

In Large Crown 8vo. Handsome Cloth. 4s. 6d. net.

## THE THERMO-DYNAMIC PRINCIPLES OF ENGINE DESIGN.

By LIONEL M. HOBBS,

Engineer-Lieutenant, R.N.; Instructor in Applied Mechanics and Marine Engine  
 Design at the Royal Naval College, Greenwich.

"Serves its purpose admirably . . . should prove of invaluable service . . . well  
 up-to-date."—*Shipping World.*

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

SECOND EDITION, Revised. Cloth. Profusely Illustrated.

## THE THEORY OF THE STEAM TURBINE.

A Treatise on the Principles of Construction of the Steam Turbine,  
with Historical Notes on its Development.

By ALEXANDER JUDE.

CONTENTS.—Fundamental.—Historical Notes on Turbines.—The Velocity of Steam.—Types of Steam Turbines.—Practical Turbines.—The Efficiency of Turbines, Type I.—Trajectory of the Steam.—Efficiency of Turbines, Types II., III. and IV.—Turbine Vanes.—Disc and Vane Friction in Turbines.—Specific Heat of Superheated Steam.—Strength of Rotating Discs.—Governing Steam Turbines.—Steam Consumption of Turbines.—The Whirling of Shafts.—Speed of Turbines.—INDEX.

"One of the latest text-books . . . also one of the best . . . there is absolutely no padding."—*Sir William White* in the *Times Engineering Supplement*.

In Large Crown 8vo. Handsome Cloth. With 131 Illustrations. 6s. net.

## LECTURES ON THE MARINE STEAM TURBINE.

By PROF. J. HARVARD BILES, M.INST.N.A.,

Professor of Naval Architecture in the University of Glasgow.

"This is the best popular work on the marine steam turbine which has yet appeared."—*Steamship*.

SIXTH EDITION, Revised. Large Crown 8vo. Pp. i-xi + 392. With  
5 Plates and 111 Illustrations in Text. 6s. net.

## ENGINE-ROOM PRACTICE:

A Handbook for Engineers and Officers in the Royal Navy and Mercantile Marine, including the Management of the Main and Auxiliary Engines on Board Ship.

By JOHN G. LIVERSIDGE, ENGR.-COMM. R.N., A.M.I.C.E.

Contents.—General Description of Marine Machinery.—The Conditions of Service and Duties of Engineers of the Royal Navy.—Entry and Conditions of Service of Engineers of the Leading S.S. Companies.—Raising Steam.—Duties of a Steaming Watch on Engines and Boilers.—Shutting off Steam.—Harbour Duties and Watches.—Adjustments and Repairs of Engines.—Preservation and Repairs of "Tank" Boilers.—The Hull and its Fittings.—Cleaning and Painting Machinery.—Reciprocating Pumps, Feed Heaters, and Automatic Feed-Water Regulators.—Evaporators.—Steam Boats.—Electric Light Machinery.—Hydraulic Machinery.—Air-Compressing Pumps.—Refrigerating Machines.—Machinery of Destroyers.—The Management of Water-Tube Boilers.—Regulations for Entry of Assistant Engineers, R.N.—Questions given in Examinations for Promotion of Engineers, R.N.—Regulations respecting Board of Trade Examinations for Engineers, &c.

"This VERY USEFUL BOOK. . . ILLUSTRATIONS are of GREAT IMPORTANCE in a work of this kind, and it is satisfactory to find that SPECIAL ATTENTION has been given in this respect."—*Engineers' Gazette*.

FOURTH EDITION, Revised. Pocket-Size, Leather. Pp. i-xiii + 583.  
12s. 6d.

## BOILERS, MARINE AND LAND: THEIR CONSTRUCTION AND STRENGTH.

A HANDBOOK OF RULES, FORMULÆ, TABLES, &C., RELATIVE TO MATERIALS,  
SCANTLINGS, AND PRESSURES, SAFETY VALVES, SPRINGS,  
FITTINGS AND MOUNTINGS, &C.

FOR THE USE OF ENGINEERS, SURVEYORS, BOILER-MAKERS,  
AND STEAM USERS.

By T. W. TRAILL, M. INST. C.E., F.E.R.N.,

Late Engineer Surveyor-in-Chief to the Board of Trade.

"Contains an ENORMOUS QUANTITY OF INFORMATION arranged in a very convenient form. . . A MOST USEFUL VOLUME . . . supplying information to be had nowhere else."—*The Engineer*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



THIRD EDITION, Revised. Pp. i-xv + 356. With Frontispiece, 8 Plates and 218 Illustrations in the Text. 21s.

## A MANUAL OF LOCOMOTIVE ENGINEERING:

A Practical Text-Book for the Use of Engine Builders,  
Designers and Draughtsmen, Railway  
Engineers, and Students.

BY WILLIAM FRANK PETTIGREW, M.INST.C.E.

*Contents.*—Historical Introduction, 1763-1863.—Modern Locomotives: Simple.—Modern Locomotives: Compound.—Primary Consideration in Locomotive Design.—Cylinders, Steam Chests, and Stuffing Boxes.—Pistons, Piston Rods, Crossheads, and Slide Bars.—Connecting and Coupling Rods.—Wheels and Axles, Axle Boxes, Hornblocks, and Bearing Springs.—Balancing.—Valve Gear.—Slide Valves and Valve Gear Details.—Framing, Bogies and Axle Trucks, Radial Axle Boxes.—Boilers.—Smokebox, Blast Pipe, Firebox Fittings.—Boiler Mountings.—Tenders.—Railway Brakes.—Lubrication.—Consumption of Fuel, Evaporation and Engine Efficiency.—Repairs, Running, Inspection, and Renewals.—Three Appendices.—Index.

"The book is very truly a full treatise on the locomotive to date."—*Cassier's Magazine*.

"The work CONTAINS ALL THAT CAN BE LEARNT from a book upon such a subject. It will at once rank as THE STANDARD WORK UPON THIS IMPORTANT SUBJECT."—*Railway Magazine*.

In Large 8vo. Pp. i-xxi + 189. With Frontispiece and 148 other  
Illustrations. 8s. 6d. net.

## LOCOMOTIVE COMPOUNDING AND SUPERHEATING.

BY J. F. GAIRNS.

*CONTENTS.*—Introductory.—Compounding and Superheating for Locomotives.—A Classification of Compound Systems for Locomotives.—The History and Development of the Compound Locomotive.—Two-Cylinder Non-Automatic Systems.—Two-Cylinder Automatic Systems.—Other Two-Cylinder Systems.—Three-Cylinder Systems.—Four-Cylinder Tandem Systems.—Four-Cylinder Two-Crank Systems (other than Tandem).—Four-Cylinder Balanced Systems.—Four-Cylinder Divided and Balanced Systems.—Articulated Compound Engines.—Triple-Expansion Locomotives.—Compound Rack Locomotives.—Concluding Remarks Concerning Compound Locomotives.—The Use of Superheated Steam for Locomotives.—INDEX.

"A welcome addition to the library of the railway engineer."—*Engineering Times*.

In Large 8vo. Handsome Cloth. Pp. i-xi + 339. With 9 Plates. 16s.

## LIGHT RAILWAYS AT HOME AND ABROAD.

BY WILLIAM HENRY COLE, M.INST.C.E.,

Late Deputy-Manager, North-Western Railway, India.

"The whole subject is EXHAUSTIVELY and PRACTICALLY considered. The work can be cordially recommended as INDISPENSABLE to those whose duty it is to become acquainted with one of the prime necessities of the immediate future."—*Railway Official Gazette*

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND



In Crown 8vo, Handsome Cloth. Very Fully Illustrated.

## **MOTOR-CAR MECHANISM AND MANAGEMENT.**

By W. POYNTER ADAMS, M.INST.E.E.

### **PART I.—THE PETROL CAR. 5s. net.**

SECOND EDITION. Pp. i-xii + 204. With 36 Illustrations, including 6 Plates and Frontispiece.

"Should be carefully studied by those who have anything to do with motors."—*Automobile and Carriage Builders' Journal*.

### **PART II.—ELECTRICAL AND PETROL ELECTRICAL MOTOR CARS. 5s. net.**

Pp. i-x + 202. With 50 Illustrations, including Frontispiece and 3 Plates, contains also 13 page Glossary.

"Cleverly written . . . will be found of considerable value."—*Practical Engineer*

In Large 8vo. Handsome Cloth. Pp. i.ix + 376. With 12 Folding Tables and 329 Illustrations. 18s. net.

## **A MANUAL OF**

## **PETROL MOTORS AND MOTOR-CARS.**

*Comprising the Designing, Construction, and Working of Petrol Motors.*

By F. STRICKLAND.

GENERAL CONTENTS.—PART I.: ENGINES.—Historical.—Power Required.—General Arrangement of Engines.—Ignition.—Carburettors.—Cylinders, Pistons, Valves, &c.—Crank Shafts, Crank Chambers, Cams, Runners, Guides, &c.—Pumps.—Flywheels.—Pipe Arrangements.—Silencers.—Engine Control, Balancing.—Motor Cycle Engines.—Marine Motors.—Two-Cycle Motors.—Paraffin Carburettors.—Gas Producers. PART II.: CARS.—General Arrangements.—Clutches.—Transmission.—Differential Gears.—Universal Joints.—Axles.—Springs.—Radius Rods.—Brakes.—Wheels.—Frames.—Steering Gear.—Radiator.—Steps, Mudguards, Bonnets, &c.—Lubrication.—Ball Bearings.—Bodies.—Factors of Safety.—Calculations of Stresses.—Special Change Speed Gears.—Special Cars.—Commercial Vehicles.—Racing Cars.—INDEX.

"Thoroughly practical and scientific. . . . We have pleasure in recommending it to all."—*Mechanical Engineer*.

In Medium 8vo. Handsome Cloth. Pp. i-xv + 272. With 306 Illustrations. 15s. net.

## **OIL MOTORS.**

*Their Development, Construction, and Management.*

By G. LIECKFELD. (Authorised English Edition).

CONTENTS.—Liquid Fuels for Power Production.—Development of the Petrol and Paraffin Motors.—Working of the Later Paraffin and Petrol Engines.—Ignition Devices.—Examples of Stationary Petrol, Alcohol, Paraffin, and Crude Oil Engines.—Automobiles.—Ship Boat, and Air-ship Engines.—Vehicles, &c., Driven by Internal Combustion Engines.—Erection and Attendance of Engines Driven with Liquid Fuel.—Correcting Irregularities in Running.

"One of the most comprehensive publications we have perused, and one that can be thoroughly recommended."—*Petroleum Review*.

In Demy 8vo. Handsome Cloth. Pp. i-xi + 176. With 130 Illustrations. 6s. net.

## **CARBURETTORS, VAPORISERS, & VALVES,** *used in Internal Combustion Engines.*

By EDWARD BUTLER, M.I.Mech.E.

"Mr. Butler writes with an intimate practical knowledge of his subject, and the book is one we have every pleasure in recommending."—*Mechanical Engineer*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND

FOURTH EDITION, Revised and Enlarged. With additional Illustrations.  
Large 8vo, Handsome Cloth. 25s. net.

## A TEXT-BOOK ON GAS, OIL, AND AIR ENGINES.

By BRYAN DONKIN, M.INST.C.E., M.INST.MECH.E.

Revised throughout by T. GRAVES SMITH. With important New Chapter  
by Prof. BURSTALL.

In Quarto, Handsome Cloth. With Numerous Plates. 25s.

## THE HEAT EFFICIENCY OF STEAM BOILERS (LAND, MARINE, AND LOCOMOTIVE).

With Tests and Experiments on Different Types, Heating Value of Fuels.  
Analyses of Gases, Evaporation, and Suggestions for Testing Boilers.

By BRYAN DONKIN, M.INST.C.E.

"Probably the most EXHAUSTIVE *resumé* that has ever been collected. A PRACTICAL  
Book by a thoroughly practical man."—*Iron and Coal Trades Review*.

In Large Crown 8vo. Cloth. Pp. i-vii + 198. With 55 Illustrations.  
5s. net.

## SUCTION GAS PLANTS.

By PROF. C. A. SMITH, of the East London Technical College.

CONTENTS.—Introduction.—Details of Construction.—Fuel and Testing.—Application  
and Uses of Suction Plants.—Working the Plant.—Typical Plants.—Plants for Special  
Purposes.—Total H.P.—Effluent.—Cost of Gas Production.—The Gas Engine.—Biblio-  
graphy.—Calorific Value of Coal Gas.—Of Solid Fuels.—Gas Analysis.—Destruction of  
Tar in the Producer.—Detection of CO in Exhaust.—Capital Cost.—INDEX.

"This book is one we can cordially recommend as affording a complete knowledge of  
the theoretical aspect of Suction Plants."—*Gas World*.

In Handsome Cloth. Pp. i-iv + 262. With 93 Illustrations. 12s. 6d. net.

## THE GAS TURBINE.

Progress in the Design and Construction of Turbines  
Operated by Gases of Combustion.

By HENRY HARRISON SUPLEE, B.Sc.

SECOND EDITION. Large 8vo, Handsome Cloth. Pp. i-xxxix + 538.  
With 157 Illustrations, 97 Tables, &c. 21s. net.

## Lubrication & Lubricants:

A Treatise on the Theory and Practice of Lubrication, and on the  
Nature, Properties, and Testing of Lubricants.

By  
LEONARD ARCHBUTT, F.I.C., F.C.S.,  
Chemist to the Mid. Ry. Co.

AND  
R. M. DEELEY, M.I.Mech.E., F.G.S.  
Chief Loco. Super., Mid. Ry. Co.

CONTENTS.—I. Friction of Solids.—II. Liquid Friction or Viscosity, and Plastic  
Friction.—III. Superficial Tension.—IV. The Theory of Lubrication.—V. Lubricants,  
their Sources, Preparation, and Properties.—VI. Physical Properties and Methods of  
Examination of Lubricants.—VII. Chemical Properties and Methods of Examination  
of Lubricants.—VIII. The Systematic Testing of Lubricants by Physical and Chemical  
Methods.—IX. The Mechanical Testing of Lubricants.—X. The Design and Lubrication  
of Bearings.—XI. The Lubrication of Machinery.—INDEX.

"A most valuable and comprehensive treatise on a subject of the greatest importance-  
to engineers."—*Engineering*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

In Crown 8vo, Cloth. Illustrated with Diagrams. 3s. net.

## THE FORCE OF THE WIND.

By HERBERT CHATLEY, B.Sc. ENG. (LOND.),

Professor of Civil Engineering, Tong Shan Engineering College, N. China.

CONTENTS. — Practical Importance of Wind Pressure. — Impulsive Force of the Wind. — Variations in Velocity. — Stream Line Theory. — Stress in Structures due to Wind. — Windmills. — Train and Motor Resistance. — Effect of Wind on Water. — Scouring Effect of Wind. — INDEX.

In Crown 8vo. Handsome Cloth. With 22 Diagrams. 3s. 6d. net.

## STRESSES IN MASONRY.

By HERBERT CHATLEY, B.Sc. ENG. (LOND.).

CONTENTS. — Strength of Stone. — Walls. — Columns and Piers. — Brackets and Cantilevers. — Simple Arches. — Vaults and Skew Arches. — Domes. — Retaining Walls and Domes. — Artificial Stone. — Re-inforced Concrete. — INDEX.

*In Handsome Cloth. With 11 Folding Tables.*

## EXPERIMENTAL INVESTIGATIONS ON THE POWER REQUIRED TO DRIVE ROLLING MILLS.

TRANSLATED FROM THE GERMAN OF J. PUPPÉ.

FOURTH EDITION. Pp. i-xii + 157. With 50 Illustrations. Cloth, 4s. 6d.

## STEAM - BOILERS:

THEIR DEFECTS, MANAGEMENT, AND CONSTRUCTION,

By R. D. MUNRO,

*Chief Engineer of the Scottish Boiler Insurance and Engine Inspection Company.*

"A valuable companion for workmen and engineers engaged about Steam Boilers, ought to be carefully studied, and ALWAYS AT HAND."—*Coll. Guardian.*

By THE SAME AUTHOR.

## KITCHEN BOILER EXPLOSIONS: Why they Occur, and How to Prevent their Occurrence. A Practical Handbook based on Actual Experiment. With Diagram and Coloured Plate. 3s.

In Crown 8vo, Cloth. Pp. i-xii + 180. With 143 Illustrations. 5s. net.

## EMERY GRINDING MACHINERY.

A Text-Book of Workshop Practice in General Tool Grinding, and the Design, Construction, and Application of the Machines Employed.

By R. B. HODGSON, A.M. INST. MECH. E.

"Eminently practical . . . cannot fail to attract the notice of the users of this class of machinery, and to meet with careful perusal."—*Chem. Trade Journal.*

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



In Crown Quarto. Cloth. Fully Illustrated.

## AN ELEMENTARY TEXT-BOOK ON MECHANICAL DRAWING.

By JOHN E. JAGGER, M.Sc.(Vic), WHIT. SCH.

A work produced from Notes and Observations made during many years of Practice and Teaching, and presenting the subject of Machine Construction and Drawing in a rational manner.

FIFTH EDITION, Thoroughly Revised and Greatly Enlarged. Pp. i-x+258.  
With 10 Plates and 246 other Illustrations. Price 10s. 6d.

## VALVES AND VALVE-GEARING:

*A Practical Text-book for the use of Engineers, Draughtsmen, and Students.*

By CHARLES HURST, PRACTICAL DRAUGHTSMAN.

PART I.—Steam Engine Valves.

PART II.—Gas Engine Valves and Gears.

PART III.—Air Compressor Valves and Gearing.

PART IV.—Pump Valves.

"MR. HURST'S VALVES AND VALVE-GEARING will prove a very valuable aid, and tend to the production of Engines of SCIENTIFIC DESIGN and ECONOMICAL WORKING. . . . Will be largely sought after by Students and Designers."—*Marine Engineer*.

"As a practical treatise on the subject, the book stands without a rival."—*Mechanical World*.

**Hints on Steam Engine Design and Construction.** By CHARLES HURST, "Author of Valves and Valve Gearing." SECOND EDITION, Revised. In Paper Boards, 8vo., Cloth Back. Pp. i-vi+62. With 32 Illustrations. Price 1s. 6d. net.

CONTENTS.—I. Steam Pipes.—II. Valves.—III. Cylinders.—IV. Air Pumps and Condensers.—V. Motion Work.—VI. Crank Shafts and Pedestals.—VII. Valve Gear.—VIII. Lubrication.—IX. Miscellaneous Details.—INDEX.

"A handy volume which every practical young engineer should possess."—*The Model Engineer*.

FIFTH EDITION. In Two Parts, Published Separately.

## A TEXT-BOOK OF Engineering Drawing and Design.

By SIDNEY H. WELLS, WH.Sc., A.M.I.C.E., A.M.I.MECH.E.

VOL. I.—PRACTICAL GEOMETRY, PLANE, AND SOLID.

Pp. i-xi+149. With 101 Illustrations, and an Appendix of 43 pages with 70 Illustrations. 4s. 6d.

VOL. II.—MACHINE AND ENGINE DRAWING AND DESIGN.

Pp. i-xi+321. With over 200 Illustrations. 4s. 6d.

"A CAPITAL TEXT-BOOK, arranged on an EXCELLENT SYSTEM, calculated to give an intelligent grasp of the subject, and not the mere faculty of mechanical copying. . . . Mr. Wells shows how to make COMPLETE WORKING-DRAWINGS, discussing fully each step in the design."—*Electrical Review*

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



SECOND EDITION, Enlarged. In Crown 8vo. Cloth. Pp. i-xiii + 463.  
With 212 Illustrations. 6s. net.

## PRACTICAL CALCULATIONS FOR ENGINEERS.

BY CHARLES E. LARARD,

A.M.Inst.C.E., M.I.Mech.E., Wh.Exh.,  
Head of the Mechanical Engineering Department at the Northampton Institute, London, E.C.

AND H. A. GOLDING, A.M.I.Mech.E.

"Exactly what it should be in order to make it useful to students and practitioners of engineering."—*Manchester Guardian*.

In Crown 8vo. Handsome Cloth. Pp. i-xii + 282. With 107  
Illustrations. 5s. net.

## MECHANICAL ENGINEERING FOR BEGINNERS.

By R. S. M'LAREN.

CONTENTS.—Materials.—Bolts and Nuts, Studs, Set Screws.—Boilers.—Steam Raising  
Accessories.—Steam Pipes and Valves.—The Steam Engine.—Power Transmission.—  
Condensing Plant.—The Steam Turbine.—Electricity.—Hydraulic Machinery.—Gas and  
Oil Engines.—Strength of Beams, and Useful Information.—INDEX.

"The best of its kind we have seen, and should be in the hands of every apprentice."  
—*Steamship*.

SIXTH EDITION. Folio, strongly half-bound, 21s.

## TRAVERSE TABLES:

Computed to Four Places of Decimals for every Minute of Angle  
up to 100 of Distance.

For the Use of Surveyors and Engineers.

By RICHARD LLOYD GURDEN,

Authorised Surveyor for the Governments of New South Wales and Victoria.

\* \* \* *Published with the Concurrence of the Surveyors-General for New South  
Wales and Victoria.*

"Those who have experience in exact SURVEY-WORK will best know how to appreciate  
the enormous amount of labour represented by this valuable book. Every Surveyor in  
active practice has felt the want of such assistance FEW KNOWING OF THEIR (the Tables)  
PUBLICATION WILL REMAIN WITHOUT THEM."—*Engineer*.

Strongly Bound in Super Royal 8vo. Cloth Boards. 7s. 6d. net.

## BONUS TABLES:

For Calculating Wages on the Bonus or Premium Systems.

*For Engineering, Technical and Allied Trades.*

By HENRY A. GOLDING, A.M.I.MECH.E.,

"Cannot fail to prove practically serviceable to those for whom they have been  
designed."—*Scotsman*.

## HORSE-POWER COMPUTERS.

By H. A. GOLDING, A.M.I.MECH.E., A.M.I.A.E.

For Steam, Gas, and Oil Engines. Complete with Explanatory  
Pamphlet. In Box. 5s. net.

For Petrol Motors. Complete with Explanatory Pamphlet. In  
Envelope. 6d. net.

*Detailed Prospectus on Application.*

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

SECOND EDITION, *Revised. In Crown 8vo, extra, with Diagrams and Folding-Plate. 7s. 6d. net.*

**THE CALCULUS FOR ENGINEERS  
AND PHYSICISTS,  
INTEGRATION AND DIFFERENTIATION,  
With Applications to Technical Problems;  
AND  
CLASSIFIED REFERENCE LIST OF INTEGRALS.**

By PROF. ROBERT H. SMITH, A.M. INST. C.E., M.I. MECH. E., &C.

"Interesting diagrams, with practical illustrations of actual occurrence, are to be found here in abundance. THE VERY COMPLETE CLASSIFIED REFERENCE TABLE will prove very useful in saving the time of those who want an integral in a hurry."—*The Engineer.*

*In 4to, Boards. 7s. 6d.*

**MEASUREMENT CONVERSIONS  
(English and French):**

**43 GRAPHIC TABLES OR DIAGRAMS, ON 28 PLATES.**

Showing at a glance the MUTUAL CONVERSION OF MEASUREMENTS  
in DIFFERENT UNITS

Of Lengths, Areas, Volumes, Weights, Stresses, Densities, Quantities  
of Work, Horse Powers, Temperatures, &c.

*For the use of Engineers, Surveyors, Architects, and Contractors*

By PROF. ROBERT H. SMITH, A.M. INST. C.E., M.I. MECH. E., &c.

THIRD EDITION. Pocket Size, Leather Limp, with Gilt Edges and Rounded Corners,  
printed on Special Thin Paper, with Illustrations, pp. i-xii + 834. Price 18s. net.

**THE MECHANICAL ENGINEER'S REFERENCE BOOK.**

By HENRY HARRISON SUPLEE, B.Sc., M.E.

"We feel sure it will be of great service to mechanical engineers."—*Engineering.*

With Diagrams. Crown 8vo. Cloth, 4s. 6d.

**THE STUDENT'S MECHANICS:  
An Introduction to the Study of Force and Motion.**

By WALTER R. BROWNE, M.A., M. INST. C.E.

"Clear in style and practical in method, 'THE STUDENT'S MECHANICS' is cordially to be recommended from all points of view."—*Athenæum.*

By THE SAME AUTHOR.

**FOUNDATIONS OF MECHANICS.**

Papers reprinted from the *Engineer*. In Crown 8vo, 1s.

SECOND EDITION. Crown 8vo. Illustrated. 7s. 6d.

**THE MECHANIC'S GUIDE.**

A Handbook for Engineers and Artisans. With Copious Tables and  
Valuable Recipes for Practical Use.

By W. VINCENT SHELTON-BEY,

Foreman to the Imperial Ottoman Gun Factories, Constantinople.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

## WORKS BY

ANDREW JAMIESON, M.INST.C.E., M.I.E.E., F.R.S.E.,

*Formerly Professor of Electrical Engineering, The Glas. and W. of Scot. Tech. Coll.*

## PROFESSOR JAMIESON'S ADVANCED TEXT-BOOKS.

*In Large Crown 8vo. Fully Illustrated.***STEAM AND STEAM-ENGINES, INCLUDING TURBINES**

AND BOILERS. For the Use of Engineers and for Students preparing for Examinations. With 800 pp., over 400 Illustrations, 11 Plates, many B. of E., C. and G., Questions and Answers, and all Inst. C.E. Exams. on *Theory of Heat Engines*. SIXTEENTH EDITION, Revised. 10s. 6d.

"The BEST BOOK yet published for the use of Students."—*Engineer*.

**APPLIED MECHANICS & MECHANICAL ENGINEERING.**

SEVENTH EDITION. In Five Volumes. *Including All the Inst. C.E. Exams.* in Section A, (1) Applied Mechanics; (2) Strength and Elasticity of Materials; (3a) Theory of Structures; Section B (Group ii.) Hydraulics; Theory of Machines. Also B. of E.; C. and G. Questions

VOL. I.—Applied Mechanics. Large Cr. 8vo. Pp. i-xviii + 382. 6s.

„ II.—Strength of Materials. Large Cr. 8vo. Pp. i-xviii + 264. 5s.

„ III.—Theory of Structures. Large Cr. 8vo. Pp. i-xviii + 232. 5s.

„ IV.—Hydraulics. Large Cr. 8vo. Pp. i-xvi + 274. 5s.

„ V.—Theory of Machines. Large Cr. 8vo. Shortly.

\*.\* *In Five volumes, each complete in itself, and sold separately.*

## PROFESSOR JAMIESON'S INTRODUCTORY MANUALS

*Crown 8vo. With Illustrations and Examination Papers.***STEAM AND THE STEAM-ENGINE (Elementary**

Manual of). For First-Year Students, forming an Introduction to the Author's larger Work. TWELFTH EDITION, Revised and Enlarged. 3/6.

"Should be in the hands of EVERY engineering apprentice."—*Practical Engineer*.

**MAGNETISM AND ELECTRICITY (Practical Elementary**

Manual of). For First-Year Students. With Stud. Inst. C.E. and B. of E. Exam. Questions. EIGHTH EDITION, Revised and Enlarged. 3/6.

"A THOROUGHLY TRUSTWORTHY Text-book. PRACTICAL and clear."—*Nature*.

**APPLIED MECHANICS (Elementary Manual of).**

For First-Year Students. With B. of E., C. and G.; and Stud. Inst. C.E. Questions. NINTH EDITION, Revised and Greatly Enlarged. 3/6.

"The work has VERY HIGH QUALITIES, which may be condensed into the one word 'CLEAR.'"—*Science and Art*.

**A POCKET-BOOK of ELECTRICAL RULES and TABLES.**

For the Use of Electricians and Engineers. By JOHN MUNRO, C.E., and Prof. JAMIESON. Pocket Size. Leather, 8s. 6d. NINETEENTH EDITION.

[See p. 30.]

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



## WORKS BY W. J. MACQUORN RANKINE, LL.D., F.R.S.

Thoroughly Revised by W. J. MILLAR, C.E.

**A MANUAL OF APPLIED MECHANICS:** Comprising the Principles of Statics and Cinematics, and Theory of Structures, Mechanism, and Machines. With Numerous Diagrams. Crown 8vo, Cloth. EIGHTEENTH EDITION. 12s. 6d.

**A MANUAL OF CIVIL ENGINEERING:** Comprising Engineering Surveys, Earthwork, Foundations, Masonry, Carpentry, Metal Work, Roads, Railways, Canals, Rivers, Waterworks, Harbours, &c. With Numerous Tables and Illustrations. Crown 8vo, Cloth. TWENTY-THIRD EDITION. 16s.

**A MANUAL OF MACHINERY AND MILLWORK:** Comprising the Geometry, Motions, Work, Strength, Construction, and Objects of Machines, &c. With nearly 300 Illustrations. Crown 8vo, Cloth. SEVENTH EDITION. 12s. 6d.

**A MANUAL OF THE STEAM-ENGINE AND OTHER PRIME MOVERS.** With a Section on GAS, OIL, and AIR ENGINES, by BRYAN DONKIN, M.Inst.C.E. With Folding Plates and Numerous Illustrations. Crown 8vo, Cloth. SEVENTEENTH EDITION. 12s. 6d.

**USEFUL RULES AND TABLES:** For Architects, Builders, Engineers, Founders, Mechanics, Shipbuilders, Surveyors, &c. With APPENDIX for the use of ELECTRICAL ENGINEERS. By Professor JAMIESON, M.Inst.C.E., M.I.E.E. EIGHTH EDITION. 10s. 6d.

**A MECHANICAL TEXT-BOOK:** A Practical and Simple Introduction to the Study of Mechanics. By Professor RANKINE and E. F. BAMBER, C.E. With Numerous Illustrations. Crown 8vo, Cloth. FIFTH EDITION. 9s.

\*.\* The "MECHANICAL TEXT-BOOK" was designed by Professor RANKINE as an INTRODUCTION to the above Series of Manuals.

**MISCELLANEOUS SCIENTIFIC PAPERS.** Part I. Temperature, Elasticity, and Expansion of Vapours, Liquids, and Solids. Part II. Energy and its Transformations. Part III. Wave-Forms, Propulsion of Vessels, &c. With Memoir by Professor TAIT, M.A. With fine Portrait on Steel, Plates, and Diagrams. Royal 8vo. Cloth. 3ls. 6d.

"No more enduring Memorial of Professor Rankine could be devised than the publication of these papers in an accessible form. . . . The Collection is most valuable on account of the nature of his discoveries, and the beauty and completeness of his analysis."  
—*Architect*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



**ELECTRICAL ENGINEERING.**

SECOND EDITION, Revised. In Large 8vo. Cloth. Pp. i-xvi + 496.  
With 145 Illustrations, including 7 Plates. 24s. net.

**CENTRAL ELECTRICAL STATIONS:**

**Their Design, Organisation, and Management.**

By CHAS. H. WORDINGHAM, A.K.C., M.INST.C.E., M.INST.MECH.E.,  
Late Memb. of Council Inst.E.E., and Electrical Engineer to the City of Manchester ;  
Electrical Engineer-in-Chief to the Admiralty.

"One of the MOST VALUABLE CONTRIBUTIONS to Central Station literature we have had for some time."—*Electricity*.

In Large 8vo. Handsome Cloth. Pp. i-xv + 231. With 2 Plates and  
204 other Illustrations. 12s. 6d. net.

**ELECTRICITY CONTROL.**

**A Treatise on Electric Switchgear and Systems of Electric Transmission.**

By LEONARD ANDREWS,

Associate Member of the Institution of Civil Engineers, Member of the Institution of  
Electrical Engineers, &c

General Principles of Switchgear Design.—Constructional Details.—Circuit Breakers or Arc Interrupting Devices.—Automatically Operated Circuit Breakers.—Alternating Reverser Current Devices.—Arrangement of 'Bus Bars, and Apparatus for Parallel Running.—General Arrangement of Controlling Apparatus for High Tension Systems.—General Arrangement of Controlling Apparatus for Low Tension Systems.—Examples of Complete Installations.—Long Distance Transmission Schemes.

"Not often does the specialist have presented to him so satisfactory a book as this. . . . We recommend it without hesitation to Central Station Engineers, and, in fact, to anyone interested in the subject."—*Power*.

Large 8vo. Cloth. Pp. i-x + 333 and 307 Illustrations. 16s. net.

**ELECTRICITY METERS.**

By HENRY G. SOLOMON, A.M.Inst.E.E.

"An earnest and successful attempt to deal comprehensively with modern methods of measuring current or power in electrical installations."—*Engineering*.

In Large 8vo. Handsome Cloth. Fully Illustrated.

**TRANSFORMERS.**

By HERMANN BOHLE, M.I.E.E.,

Prof. of Electrotechnics, S.A. College, Cape Town,

AND PROFESSOR DAVID ROBERTSON, B.Sc., A.I.E.E., OF BRISTOL.

CONTENTS.—General Principles.—Magnetising and No-Load Currents.—Losses in Transformers.—Iron Losses.—Copper Losses.—Temperature Rise.—Magnetic Leakage.—Leakage Inductance.—Vector Diagrams for Transformers.—Systematic Testing of Transformers.—Insulating Materials.—Examples of Construction.—Design of Transformers.—Applications of Transformers.—Regulating and Phase-Changing Transformers.—INDEX.

In Large 8vo. Pp. i-x + 116. With 79 Illustrations. 8s. 6d. net.

**WIRELESS TELEGRAPHY.**

By GUSTAVE EICHHORN, Ph.D.

"Well written . . . and combines with a good deal of description a careful investigation of the fundamental theoretical phenomena."—*Nature*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

In Large Crown 8vo. Cloth. Pp. i-xvi+268. With 222 Illustrations.  
5s. net.

## TELEGRAPHIC SYSTEMS, AND OTHER NOTES.

*A Handbook of the Principles on which Telegraphic Practice is Based.*

By ARTHUR CROTCH, of the Engineer-in-Chief's Department, G.P.O.

CONTENTS. — Batteries, Primary and Secondary. — Universal Battery Working. — Duplex Telegraphy. — Duplex and Quadruplex Telegraphy. — Automatic Telegraphy. — Multiplex Telegraphy. — The Hughes Type Printing Instrument. — The Baudot System. — The Murray Type Printing Telegraph. — Test and Battery Boxes. — Circuit Concentration, &c. — Repeaters. — Submarine Telegraphy. — Wireless Telegraphy. — INDEX. — LIST OF DIAGRAMS OF CONNECTIONS.

"This book is a particularly good one . . . we can thoroughly recommend it . . . a handy book of ready reference."—*Electrical Review*.

"The treatise will be of much help to the telegraph engineer, and to the student in his preparatory training and it can be thoroughly recommended."—*Electrician*.

NINETEENTH EDITION. Leather, Pocket Size, with 810 pages. 8s. 6d.

## A POCKET-BOOK OF ELECTRICAL RULES & TABLES

FOR THE USE OF ELECTRICIANS AND ENGINEERS.

By JOHN MUNRO, C.E., & PROF. JAMIESON, M.INST.C.E., F.R.S.E.

"WONDERFULLY PERFECT. . . . Worthy of the highest commendation we can give it."—*Electrician*.

**GRIFFIN'S ELECTRICAL PRICE-BOOK:** For Electrical, Civil, Marine, and Borough Engineers, Local Authorities, Architects, Railway Contractors, &c. Edited by H. J. DOWSING. SECOND EDITION. 8s. 6d.

ELECTRIC SMELTING AND REFINING. [See p. 52.]

ELECTRO METALLURGY, A Treatise on. [See p. 52.]

ELECTRICAL PRACTICE IN COLLIERIES. [See p. 42.]

ELECTRICAL SIGNALLING IN MINES. [See p. 43.]

In Large Crown 8vo. Handsome Cloth.

## ELECTRICAL THEORY AND THE PROBLEM OF THE UNIVERSE.

By G. W. DE TUNZELMANN, B.Sc., LONDON,

Member of the Institute of Electrical Engineers; formerly Professor of Natural Philosophy and Astronomy, H.M.S. "Britannia," Dartmouth.

CONTENTS. — Fundamental Electrical Phenomena. — Units and Measurement. — Meaning and Possibility of a Mechanical Theory of Electricity. — The Ether. — The Ether as a Framework of Reference for Motion. — The Relations between Ether and Moving Matter. — Electric Conduction in Gases. — The Faraday-Maxwell Theory. — The Electron Theory. — Magnetism and the Dissipation of Energy. — Contract Electrification and Electrolysis. — Metallic Conduction. — Optical Phenomena. — The Mechanism of Radiation. — General Phenomena of Radio Activity. — Transmutations of Radio-Active Substances. — Ages of the Sun and Earth. — The Solar Corona, The Aurora, and Comets' Tails. — Radio-Activity in Stars and Nebulae. — Arrangement and Number of Atoms in a Molecule. — Changes in the Aspect of Fundamental Mechanical Principals. — Gravitation and Cohesion. — The Place of Mind in the Universe. — Mathematical and other Appendices. — INDEX.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

In Large 8vo. Handsome Cloth. Profusely Illustrated. In Two VOLUMES, Each Complete in itself, and SOLD SEPARATELY.

# THE DESIGN AND CONSTRUCTION OF SHIPS.

By JOHN HARVARD BILES, M.Inst.N.A.,  
Professor of Naval Architecture in Glasgow University.

**Volume I.—CALCULATIONS AND STRENGTH.** With 36 Folding Plates, and 245 other Illustrations. Pp. i-viii+423. Complete in itself, with Index. 25s. net.

CONTENTS.—PART I.—Areas, Volumes, and Centres of Gravity. PART II.—Ship Calculations. PART III.—Strength of Ships.

"No teacher of naval architecture nor scientifically-equipped student of the same subject can afford to be without it. . . . A work with up-to-date information which will doubtless remain the standard for many years."—*Times' Engineering Supplement*.

**Volume II.,** dealing with Stability, Waves, Oscillations, Resistance and Propulsion, Design and Construction, is in active preparation, and will be ready very shortly.

## BY PROFESSOR BILES. LECTURES ON THE MARINE STEAM TURBINE.

With 131 Illustrations. Price 6s. net.

See page 19.

Royal 8vo. Handsome Cloth. With numerous Illustrations and Tables. 25s.

## THE STABILITY OF SHIPS.

By SIR EDWARD J. REED, K.C.B., F.R.S., M.P.,

KNIGHT OF THE IMPERIAL ORDERS OF ST. STANILAUS OF RUSSIA; FRANCIS JOSEPH OF AUSTRIA; MEHJIDIE OF TURKEY; AND RISING SUN OF JAPAN; VICE-PRESIDENT OF THE INSTITUTION OF NAVAL ARCHITECTS.

"Sir EDWARD REED'S 'STABILITY OF SHIPS' is INVALUABLE. The NAVAL ARCHITECT will find brought together and ready to his hand, a mass of information which he would otherwise have to seek in an almost endless variety of publications, and some of which he would possibly not be able to obtain at all elsewhere."—*Steamship*.

## AERONAUTICAL ENGINEERING.

SECOND EDITION, Revised. In Large 8vo. Cloth. With many Illustrations. 10s. 6d. net.

## THE PROBLEM OF FLIGHT.

A TEXT-BOOK OF AERIAL ENGINEERING.

By HERBERT CHATLEY, B.Sc.(Eng.), LONDON,  
Professor of Civil Engineering, Tong Shan Engineering College, N. China.

CONTENTS.—The Problem of Flight.—The Helix.—The Aëroplane.—The Aviplane.—Dirigible Balloons.—Form and Fittings of the Airship.—APPENDICES (*The Possibility of Flight, Weight, A Flexible Wing, Theory of Balance, Bibliography*).—INDEX.

"An epitome of the knowledge available on the subject."—*Scotsman*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



WORKS BY THOMAS WALTON,  
NAVAL ARCHITECT.

FOURTH EDITION. Pp. i-xvi + 332. With 18 Plates and 237 other Illustrations, including 59 Folding Diagrams. 18s. net.

**STEEL SHIPS:**  
**THEIR CONSTRUCTION AND MAINTENANCE.**

*A Manual for Shipbuilders, Ship Superintendents, Students,  
and Marine Engineers.*

By THOMAS WALTON, NAVAL ARCHITECT,

AUTHOR OF "KNOW YOUR OWN SHIP."

CONTENTS.—I. Manufacture of Cast Iron, Wrought Iron, and Steel.—Composition of Iron and Steel, Quality, Strength, Tests, &c. II. Classification of Steel Ships. III. Considerations in making choice of Type of Vessel.—Framing of Ships. IV. Strains experienced by Ships.—Methods of Computing and Comparing Strengths of Ships. V. Construction of Ships.—Alternative Modes of Construction.—Types of Vessels.—Turret, Self Trimming, and Trunk Steamers, &c.—Rivets and Rivetting, Workmanship. VI. Pumping Arrangements. VII. Maintenance.—Prevention of Deterioration in the Hulls of Ships.—Cement, Paint, &c.—INDEX.

"So thorough and well written is every chapter in the book that it is difficult to select any of them as being worthy of exceptional praise. Altogether, the work is excellent, and will prove of great value to those for whom it is intended."—*The Engineer*.

In Cloth. Pp. i.-xii. + 224. With 9 Plates and 163 other Illustrations, including 40 Folding Diagrams. 7s. 6d. net.

**PRESENT-DAY SHIPBUILDING.**

*For Shipyard Students, Ships' Officers, and Engineers.*

By THOS. WALTON.

GENERAL CONTENTS.—Classification.—Materials used in Shipbuilding.—Alternative Modes of Construction.—Details of Construction.—Framing, Plating, Rivetting, Stem Frames, Twin-Screw Arrangements, Water Ballast Arrangements, Loading and Discharging Gear, &c.—Types of Vessels, including Atlantic Liners, Cargo Steamers, Oil carrying Steamers, Turret and other Self Trimming Steamers, &c.—INDEX.

"Simple language . . . clear and easily followed illustrations."—*Times Engineering Supplement*.

"We heartily recommend it to all who have to do with ships."—*Steamship*.

ELEVENTH EDITION. In Crown 8vo. Cloth. Pp. i-xvi + 363. With 142 Illustrations, including 2 Folding Diagrams. 7s. 6d.

The Chapters on Tonnage and Freeboard have been brought thoroughly up to date, and embody the latest (1906) Board of Trade Regulations on these subjects.

**KNOW YOUR OWN SHIP.**

By THOMAS WALTON, NAVAL ARCHITECT.

*Specially arranged to suit the requirements of Ships' Officers, Shipowners, Superintendents, Draughtsmen, Engineers, and Others,*

CONTENTS.—Displacement and Deadweight.—Moments.—Buoyancy.—Strain.—Structure.—Stability.—Rolling.—Ballasting.—Loading.—Shifting Cargoes.—Effect of Admission of Water into Ship.—Trim Tonnage.—Freeboard (Load-line).—Calculations.—Set of Calculations from Actual Drawings.—INDEX.

"The work is of the highest value, and all who go down to the sea in ships should make themselves acquainted with it."—*Shipping World* (on the new edition).

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

**GRIFFIN'S NAUTICAL SERIES.***Introductory Volume. Pp. i-xix + 248. Price 3s. 6d.*

THE

**British Mercantile Marine.**

BY EDWARD BLACKMORE,

MASTER MARINER; ASSOCIATE OF THE INSTITUTION OF NAVAL ARCHITECTS;  
MEMBER OF THE INSTITUTION OF ENGINEERS AND SHIPBUILDERS  
IN SCOTLAND; EDITOR OF GRIFFIN'S "NAUTICAL SERIES."

**GENERAL CONTENTS.**—**HISTORICAL:** From Early Times to 1486—Progress under Henry VIII.—To Death of Mary—During Elizabeth's Reign—Up to the Reign of William III.—The 18th and 19th Centuries—Institution of Examinations—Rise and Progress of Steam Propulsion—Development of Free Trade—Shipping Legislation, 1862 to 1875—"Locksley Hall" Case—Shipmasters' Societies—Loading of Ships—Shipping Legislation, 1884 to 1894—Statistics of Shipping. **THE PERSONNEL:** Shipowners—Officers—Mariners—Duties and Present Position. **EDUCATION:** A Seaman's Education: what it should be—Present Means of Education—Hints. **DISCIPLINE AND DUTY:** Postscript—The Serious Decrease in the Number of British Seamen, a Matter demanding the Attention of the Nation.

"INTERESTING AND INSTRUCTIVE . . . may be read WITH PROFIT AND ENJOYMENT."—*Glasgow Herald*.

"EVERY BRANCH of the subject is dealt with in a way which shows that the writer 'knows the ropes' familiarly."—*Scotsman*.

"THIS ADMIRABLE book . . . TEEMS with useful information—Should be in the hands of every Sailor."—*Western Morning News*.

**FIFTH EDITION, Thoroughly Revised. Pp. i-xvi + 250. With Frontispiece, 24 Plates (3 Coloured), and 63 Illustrations in the Text and new Chapter on Clouds. Price 6s.**

**A MANUAL OF****ELEMENTARY SEAMANSHIP.**

BY

D. WILSON-BARKER, MASTER MARINER; F.R.S.E., F.R.G.S., &c., &c.  
YOUNGER BROTHER OF THE TRINITY HOUSE.

**GENERAL CONTENTS.**—The Building of a Ship; Parts of Hull, Masts, &c.—Ropes, Knots, Splicing, &c.—Gear, Lead and Log, &c.—Rigging, Anchors—Sailmaking—The Sails, &c.—Handling of Boats under Sail—Signals and Signalling—Rule of the Road—Keeping and Relieving Watch—Points of Etiquette—Glossary of Sea Terms and Phrases—Index.

\*. The volume contains the NEW RULES OF THE ROAD.

"THIS ADMIRABLE MANUAL by CAPT. WILSON-BARKER of the 'Worcester,' seems to us PERFECTLY DESIGNED, and holds its place excellently in 'GRIFFIN'S NAUTICAL SERIES.' . . . Although intended for those who are to become Officers of the Merchant Navy, it will be found useful by ALL YACHTSMEN."—*Athenæum*.

LONDON: CHARLES GRIFFIN &amp; CO., LIMITED, EXETER STREET, STRAND.

**GRIFFIN'S NAUTICAL SERIES.**

SECOND EDITION, Revised. Pp. i-xii + 156. With 61  
Illustrations. Price 3s. 6d.

# NAVIGATION:

## PRACTICAL AND THEORETICAL.

By DAVID WILSON-BARKER, R.N.R., F.R.S.E., &c., &c.,

AND

WILLIAM ALLINGHAM,

FIRST-CLASS HONOURS, NAVIGATION, SCIENCE AND ART DEPARTMENT.

**With Numerous Illustrations and Examination Questions.**

**GENERAL CONTENTS.**—Definitions—Latitude and Longitude—Instruments of Navigation—Correction of Courses—Plane Sailing—Traverse Sailing—Day's Work—Parallel Sailing—Middle Latitude Sailing—Mercator's Chart—Mercator Sailing—Current Sailing—Position by Bearings—Great Circle Sailing—The Tides—Questions—Appendix: Compass Error—Numerous Useful Hints. &c.—Index.

"PRECISELY the kind of work required for the New Certificates of competency in grades from Second Mate to extra Master. . . . Candidates will find it INVALUABLE."—*Dundee Advertiser*.

"A CAPITAL LITTLE BOOK . . . specially adapted to the New Examinations. The Authors are CAPT. WILSON-BARKER (Captain-Superintendent of the Nautical College, H.M.S. 'Worcester,' who has had great experience in the highest problems of Navigation), and MR. ALLINGHAM, a well-known writer on the Science of Navigation and Nautical Astronomy."—*Shipping World*.

*Handsome Cloth. Pp. i-xvi + 182. With 10 Plates and 34 other  
Illustrations. Price 7s. 6d.*

# MARINE METEOROLOGY,

## FOR OFFICERS OF THE MERCHANT NAVY.

By WILLIAM ALLINGHAM,

Joint Author of "Navigation, Theoretical and Practical."

With numerous Plates, Maps, Diagrams, and Illustrations, and a facsimile  
Reproduction of a Page from an actual Meteorological Log-Book.

### SUMMARY OF CONTENTS.

**INTRODUCTORY.**—Instruments Used at Sea for Meteorological Purposes.—Meteorological Log-Books.—Atmospheric Pressure.—Air Temperatures.—Sea Temperatures.—Winds.—Wind Force Scales.—History of the Law of Storms.—Hurricanes, Seasons, and Storm Tracks.—Solution of the Cyclone Problem.—Ocean Currents.—Icebergs.—Synchrous Charts.—Dew, Mists, Fogs, and Haze.—Clouds.—Rain, Snow, and Hail.—Mirage, Rainbows, Coronas, Halos, and Meteors.—Lightning, Comets, and Auroras.—**QUESTIONS.—APPENDIX.—INDEX.**

"Quite the BEST publication, AND certainly the MOST INTERESTING, on this subject ever presented to Nautical men."—*Shipping Gazette*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



**GRIFFIN'S NAUTICAL SERIES.**

THIRD EDITION, REVISED. Pp. i-xii + 175. With 54 Illustrations.  
Price 3s. 6d.

## **PRACTICAL MECHANICS:** **Applied to the Requirements of the Sailor.**

By THOS. MACKENZIE, *Master Mariner, F.R.A.S.*

**GENERAL CONTENTS.**—Resolution and Composition of Forces—Work done by Machines and Living Agents—The Mechanical Powers: The Lever; Derricks as Bent Levers—The Wheel and Axle: Windlass; Ship's Capstan; Crab Winch—Tackles: the "Old Man"—The Inclined Plane; the Screw—The Centre of Gravity of a Ship and Cargo—Relative Strength of Rope: Steel Wire, Manilla, Hemp, Coir—Derricks and Shears—Calculation of the Cross-breaking Strain of Fir Spar—Centre of Effort of Sails—Hydrostatics: the Diving-bell; Stability of Floating Bodies; the Ship's Pump, &c.

"WELL WORTH the money . . . will be found **EXCEEDINGLY HELPFUL**."—*Shipping World*.

"No SHIPS' OFFICERS' BOOKCASE will henceforth be complete without CAPTAIN MACKENZIE'S 'PRACTICAL MECHANICS.' Notwithstanding my many years' experience at sea, it has told me *how much more there is to acquire*."—(Letter to the Publishers from a Master Mariner).

### **WORKS BY RICHARD C. BUCK,**

of the Thames Nautical Training College, H.M.S. 'Worcester.'

THIRD EDITION, Revised and Corrected. Pp. i-viii + 113.  
With 38 Illustrations. Price 3s. 6d.

## **A MANUAL OF TRIGONOMETRY:**

*With Diagrams, Examples, and Exercises.*

\* \* Mr. Buck's Text-Book has been SPECIALLY PREPARED with a view to the Examinations of the Board of Trade, in which Trigonometry is an obligatory subject.

"This **EMINENTLY PRACTICAL** and **RELIABLE VOLUME**."—*Schoolmaster*.

SECOND EDITION, Revised. Pp. i-viii + 158. Price 3s. 6d.

## **A MANUAL OF ALGEBRA.**

*Designed to meet the Requirements of Sailors and others.*

\* \* These elementary works on ALGEBRA and TRIGONOMETRY are written specially for those who will have little opportunity of consulting a Teacher. They are books for "SELF-HELP." All but the simplest explanations have, therefore, been avoided, and ANSWERS to the Exercises are given. Any person may readily, by careful study, become master of their contents, and thus lay the foundation for a further mathematical course, if desired. It is hoped that to the younger Officers of our Mercantile Marine they will be found decidedly serviceable. The Examples and Exercises are taken from the Examination Papers set for the Cadets of the "Worcester."

"Clearly arranged, and well got up. . . . A first-rate Elementary Algebra."—*Nautical Magazine*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

**GRIFFIN'S NAUTICAL SERIES.**

SECOND EDITION, Revised. With Diagrams. Price 2s.

**LATITUDE AND LONGITUDE: How to Find them.**

By W. J. MILLAR, C.E.,

*Late Secretary to the Inst. of Engineers and Shipbuilders in Scotland.*"CONCISELY and CLEARLY WRITTEN . . . cannot but prove an acquisition to those studying Navigation."—*Marine Engineer.*"Young Seamen will find it HANDY and USEFUL, SIMPLE and CLEAR."—*The Engineer.*

SECOND EDITION, Revised. In Crown 8vo. Pp. i-xvii+230. Price 4s. 6d.

**THE LEGAL DUTIES OF SHIPMASTERS.**

By BENEDICT WM. GINSBURG, M.A., LL.D. (CANTAB.),

Of the Inner Temple and Northern Circuit; Barrister-at-Law.

**General Contents.**—Qualification for Position of Shipmaster.—Contract with Shipowner.—Duty in respect of the Crew: Engagement; Apprentices; Discipline; Provisions, Accommodation, and Medical Comforts; Payment of Wages and Discharge.—Passengers.—Financial Responsibilities.—Cargo.—Casualty.—Duty to certain Public Authorities.—Pilots, Signals, Flags, and Light Dues.—Arrival at the Port of Discharge.—Appendices on Legal Matters: B.O.T. Certificates, Dietary Scales, Stowage of Grain Cargoes, Load Line Regulations, Life-saving Appliances, Carriage of Cattle.—INDEX.

"No intelligent Master should fail to add this to his list of necessary books. A few lines of it may SAVE A LAWYER'S FEE, BESIDES ENDLESS WORRY."—*Liverpool Journal of Commerce.*

**FIRST AID AT SEA.**

THIRD EDITION, Revised. Pp. i-xviii+349. With 82 Illustrations and the latest Regulations on the Carriage of Medical Stores. 6s.

**A MEDICAL AND SURGICAL HELP**

For Shipmasters and Officers in the Merchant Navy.

By WM. JOHNSON SMITH, F.R.C.S.,

Principal Medical Officer, Seamen's Hospital, Greenwich.

"\* The attention of all interested in our Merchant Navy is requested to this exceedingly useful and valuable work. It is needless to say that it is the outcome of many years PRACTICAL EXPERIENCE amongst Seamen.

"SOUND, JUDICIOUS, REALLY HELPFUL."—*The Lancet.*

ELEVENTH EDITION, Revised and Enlarged. Price 7s. 6d.

**KNOW YOUR OWN SHIP.**

By THOMAS WALTON, NAVAL ARCHITECT.

*Specially arranged to suit the requirements of Ships' Officers, Shipowners, Superintendents, Draughtsmen, Engineers, and Others.*

For Contents and further particulars of this work, and other works by the same author, see p. 32.

LONDON: CHARLES GRIFFIN &amp; CO., LIMITED. EXETER STREET, STRAND.

## OTHER WORKS OF INTEREST TO SAILORS.

In Pocket Size. With 368 Pages. 3s. 6d. net.

## ENGLISH-SPANISH AND SPANISH-ENGLISH SEA TERMS AND PHRASES.

BY FLEET-PAYMASTER GRAHAM-HEWLETT.

"Most complete . . . useful . . . we can heartily recommend it."—*Steamship*.

In Crown 8vo. Handsome Cloth. Many Diagrams. 2s. 6d. net.

## DEFINITIONS IN NAVIGATION & NAUTICAL ASTRONOMY.

BY P GROVES-SHOWELL,

Head of the Navigation Department, L.C.C. School, Poplar.

CONTENTS.—**Definitions.**—General.—Navigation.—Nautical Astronomy.—Time.—Miscellaneous.—Notes. **Measurements.**—Mariner's Compass.—Chronometer.—Azimuth Compass.—Pelorus.—Sextant.—Vernier.—Artificial Horizon.—Sounding Machine.—Log.—Station Pointer.—Barometer.—Thermometer.—Hygrometer.—Hydrometer. **Miscellaneous.**—Star Nomenclature.—Greek Alphabet.—Planetary Symbols.—Weights and Measures.—Areas.—Volumes.—Useful Notes.—INDEX.

"Mr. Groves-Showell writes with a full knowledge of his subject, and with admirable clearness."—*Shipbuilder*.

Attention is also drawn to the following:—

**HYDROGRAPHIC SURVEYING.** By COMMANDER S. MESSUM, R.N. [See page 16.]

**THEODOLITE SURVEYING.** By Professor JAMES PARK. [See page 41.]

**THE FORCE OF THE WIND.** By HERBERT CHATLEY, B.Sc. [See page 23.]

**THE EARTH'S ATMOSPHERE.** By Dr. T. L. PHIPSON. [See page 46.]

**WIRELESS TELEGRAPHY.** By GUSTAVE EICHORN, Ph.D. [See page 29.]

LONDON: CHARLES GRIFFIN & CO., LIMITED, 5, FETTER STREET, STRAND.



## **MINING WORKS.**

**Pages 39-45.**

WORKS BY  
SIR CLEMENT LE NEVE FOSTER, D.Sc., F.R.S.

SIXTH EDITION. With Frontispiece and 712 Illustrations. Price 28s. net.

# ORE & STONE MINING.

By SIR C. LE NEVE FOSTER, D.Sc., F.R.S.,

LATE PROFESSOR OF MINING, ROYAL COLLEGE OF SCIENCE.

REVISED, AND BROUGHT UP-TO-DATE

By PROF. S. H. COX, Assoc.R.S.M.,

PROFESSOR OF MINING, ROYAL COLLEGE OF SCIENCE.

## GENERAL CONTENTS.

**INTRODUCTION.** Mode of Occurrence of Minerals.—Prospecting.—Boring.—Breaking Ground.—Supporting Excavations.—Exploitation.—Haulage or Transport.—Hoisting or Winding.—Drainage.—Ventilation.—Lighting.—Descent and Ascent.—Dressing—Principles of Employment of Mining Labour.—Legislation affecting Mines and Quarries.—Condition of the Miner.—Accidents.—Index

"We have seldom had the pleasure to review a work so thorough and complete as the present one. Both in manner and in matter it is FAR SUPERIOR TO ANYTHING ON ITS SPECIAL SUBJECT HITHERTO PUBLISHED IN ENGLAND."—*Athenæum*.

"Not only is this work the acknowledged text-book on metal mining in Great Britain and the Colonies, but that it is so regarded in the United States of America is evidenced by the fact that it is the book on that subject recommended to the students in most of the mining schools of that country."—*The Times*.

SECOND EDITION, Revised. In Crown 8vo. Handsome Cloth.

With nearly 300 Illustrations. Price 7s. 6d. net.

# THE ELEMENTS OF MINING AND QUARRYING.

*An Introductory Text-Book for Mining Students.*

By SIR C. LE NEVE FOSTER, D.Sc., F.R.S.,

Late Professor of Mining at the Royal College of Science.

Revised by Prof. S. H. Cox, A.R.S.M., &c.

**GENERAL CONTENTS.**—INTRODUCTION.—Occurrence of Minerals.—Prospecting.—Boring.—Breaking Ground.—Supporting Excavations.—Exploitation.—Haulage or Transport.—Hoisting or Winding.—Drainage.—Ventilation.—Lighting.—Descent and Ascent.—Dressing, &c.—INDEX.

"A remarkably clear survey of the whole field of mining operations."—*Engineer*.

"Barely does it fall to the lot of a reviewer to have to accord such unqualified praise as this book deserves. . . . The profession generally have every reason to be grateful to Sir C. Le Neve Foster for having enriched educational literature with so admirable an elementary Text-book."—*Mining Journal*.

In Large Crown 8vo. Fully Illustrated. 6s. net.

# THE INVESTIGATION OF MINE AIR:

*An Account by Several Authors of the Nature, Significance, and Practical Methods of Measurement of the Impurities met with in the Air of Collieries and Metalliferous Mines.*

EDITED BY

SIR CLEMENT LE NEVE FOSTER, D.Sc., F.R.S.,

AND J. S. HALDANE, M.D., F.R.S.

"We know of nothing essential that has been omitted. The book is liberally supplied with illustrations of apparatus."—*Colliery Guardian*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

## **WORKS ON COAL-MINING.**

FIFTH EDITION, Revised and Greatly Enlarged. With 4 Plates and  
690 Illustrations. Price 24s. net.

### **A TEXT-BOOK OF COAL-MINING:** *FOR THE USE OF COLLIERY MANAGERS AND OTHERS ENGAGED IN COAL-MINING.*

BY HERBERT WILLIAM HUGHES, F.G.S.,  
Assoc. Royal School of Mines, General Manager of Sandwell Park Colliery.

GENERAL CONTENTS.—Geology.—Search for Coal.—Breaking Ground.—  
Sinking.—Preliminary Operations.—Methods of Working.—Haulage.—  
Winding.—Pumping.—Ventilation.—Lighting.—Works at Surface.—Pre-  
paration of Coal for Market.—INDEX.

"Quite THE BEST BOOK of its kind . . . as PRACTICAL in aim as a book can be . . . The  
illustrations are EXCELLENT."—*Athenæum*.

"We cordially recommend the work."—*Colliery Guardian*.

"Will soon come to be regarded as the STANDARD WORK of its kind."—*Birmingham Daily Gazette*.

FOURTH EDITION, Thoroughly Revised and Greatly Enlarged. Re-set  
throughout. Large Crown 8vo. Handsome Cloth. 12s. 6d.

### **PRACTICAL COAL-MINING:** **A MANUAL FOR MANAGERS, UNDER-MANAGERS, COLLIERY ENGINEERS, AND OTHERS.**

*With Worked-out Problems on Haulage, Pumping, Ventilation, &c.*

BY GEORGE L. KERR, M.E., M.INST.M.E.

CONTENTS.—The Sources and Nature of Coal.—The Search for Coal.—  
Sinking.—Explosives.—Mechanical Wedges.—Rock Drills and Coal-cutting  
Machines.—Coal-cutting by Machinery.—Transmission of Power.—Modes of  
Working.—Timbers.—Roadways.—Winding Coal.—Haulage.—Pumping.—  
Ventilation.—Safety Lamps.—Surface Arrangements, Surveying, Levelling,  
&c.

"AN ESSENTIALLY PRACTICAL WORK, and can be confidently recommended. No department  
of Coal-Mining has been overlooked."—*Engineers' Gazette*.

SECOND EDITION, Revised. In Crown 8vo. Handsome Cloth.  
With 200 Illustrations. 3s. 6d.

### **ELEMENTARY COAL-MINING:** **FOR THE USE OF STUDENTS, MINERS, AND OTHERS PREPARING FOR EXAMINATIONS.**

BY GEORGE L. KERR, M.E., M.INST.M.E.

CONTENTS.—Sources and Nature of Coal.—Exploration and Boring for  
Coal.—Breaking Ground.—Explosives, Blasting, &c.—Sinking and Fitting  
of Shafts.—Modes of Working.—Timbering Roadways.—Winding and  
Drawing.—Haulage.—Pumping and Drainage.—Ventilation.—Cleaning and  
Sorting Coal.—Surveying, &c.

"An abundance of information conveyed in a popular and attractive form. . . . Will be  
of great use to all who are in any way interested in coal mining."—*Scottish Critic*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND



FOURTEENTH EDITION, Revised. With Numerous Diagrams.  
Cloth, 7s. 6d.

## A TREATISE ON MINE-SURVEYING:

*For the use of Managers of Mines and Collieries, Students  
at the Royal School of Mines, &c.*

By BENNETT H. BROUGH, ASSOC. R.S.M., F.G.S.

REVISED BY L. H. COOKE,  
Instructor of Mine-Surveying, Royal School of Mines.

CONTENTS. — General Explanations. — Measurement of Distances. — Miners Dial. — Variation of the Magnetic Needle. — Surveying with the Magnetic Needle in the Presence of Iron. — Surveying with the Fixed Needle. — The German Dial. — The Theodolite. — Traversing Underground. — Surface Surveys with the Theodolite. — Plotting the Survey. — Calculation of Areas. — Levelling. — Connection of the Underground and Surface Surveys. — Measuring Distances by Telescope. — Setting-out. — Mine-Surveying Problems. — Mine Plans. — Application of the Magnetic Needle in Mining. — Photographic Surveys. — APPENDICES — INDEX.

"Its CLEARNESS of STYLE, LUCIDITY of DESCRIPTION, and FULLNESS of DETAIL have long ago won for it a place unique in the literature of this branch of mining engineering, and the present edition fully maintains the high standard of its predecessors. To the student, and to the mining engineer alike, ITS VALUE is inestimable. The illustrations are excellent."—*The Mining Journal*.

In Crown 8vo. Handsome Cloth. Fully Illustrated. 6s. net.

## A HANDBOOK ON THEODOLITE SURVEYING AND LEVELLING.

*For the use of Students in Land and Mine Surveying.*

By PROFESSOR JAMES PARK, F.G.S.

CONTENTS.—The Scope and Object of Surveying.—Land Surveying.—The Theodolite.—Chains and Steel Bands.—Obstacles to Allignment.—Meridian and Bearings.—The Theodolite Traverse.—Co-ordinates of a Station.—Calculation of Omitted or Connecting Line in a Traverse.—Calculation of Areas.—Subdivision of Land.—Triangulation.—Determination of True Meridian, Latitude and Time.—Levelling.—Railway Curves.—Mine Surveying.—Surveying Boreholes.—INDEX.

"A book which should prove as useful to the professional surveyor as to the student."—*Nature*.

SECOND EDITION, Revised. Crown 8vo. Handsome Cloth. Illustrated. 6s.

## MINING GEOLOGY.

A TEXT-BOOK FOR MINING STUDENTS AND MINERS.

By PROF. JAMES PARK, F.G.S., M.Inst.M.M.,

Professor of Mining and Director of the Otago University School of Mines; late Director  
Thames School of Mines, and Geological Surveyor and Mining Geologist to the  
Government of New Zealand

GENERAL CONTENTS.—Introduction.—Classification of Mineral Deposits.—Ore Veins, their Filling, Age, and Structure.—The Dynamics of Lodes and Beds.—Ore Deposits Genetically Considered.—Ores and Minerals Considered Economically.—Mine Sampling and Ore Valuation.—The Examination and Valuation of Mines.—INDEX.

"A work which should find a place in the library of every mining engineer."—*Mining World*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

## WORKS FOR MINERS AND STUDENTS.

THIRD EDITION. *In Crown 8vo. Handsome Cloth. With 30 New Illustrations. 7s. 6d. net.*

## ELECTRICAL PRACTICE IN COLLIERIES.

By PROF. D. BURNS, M.E., M.INST.M.E.,

Professor of Mining and Geology to the Glasgow and West of Scotland Technical College.

Units of Measurement, Conductors, &c.—The Theory of the Dynamo.—The Dynamo, Details of Construction and Working.—Motors.—Lighting Installations in Collieries.—Pumping by Electricity.—Electrical Haulage.—Coal Cutting.—Miscellaneous Applications of Electricity in Mines.—Coal Mines Regulation Act (Electricity).—INDEX.

"A clear and concise introduction to electrical practice in collieries."—*Mining Journal*.

*In Crown 8vo, Handsome Cloth. 8s. 6d. net.*

## MINING LAW OF THE BRITISH EMPIRE.

By CHARLES J. ALFORD, F.G.S., M.INST.M.M.

CONTENTS.—The Principles of Mining Law.—The Mining Law of Great Britain.—British India.—Ceylon.—Burma.—The Malay Peninsula.—British North Borneo.—Egypt.—Cyprus.—The Dominion of Canada.—British Guiana.—The Gold Coast Colony and Ashanti.—Cape of Good Hope.—Natal.—Orange River Colony.—Transvaal Colony.—Rhodesia.—The Commonwealth of Australia.—New Zealand, &c.—INDEX.

"Cannot fail to be useful . . . we cordially recommend the book."—*Mining World*.

FIFTH IMPRESSION. *In Large 8vo. Price 10s. 6d.*

## 'MINE ACCOUNTS AND MINING BOOK-KEEPING.

For Students, Managers, Secretaries, and others.

*With Examples taken from Actual Practice of Leading Companies.*

By JAMES GUNSON LAWN, A.R.S.M., A.M.INST.C.E., F.G.S.,  
Head of the Mining Department, Camborne School of Mines.

EDITED BY SIR C. LE NEVE FOSTER, D.Sc., F.R.S.

"It seems impossible to suggest how Mr. LAWN's book could be made more COMPLETE or more VALUABLE, careful, and exhaustive."—*Accountants' Magazine*.

THIRD EDITION. *In Pocket Size, Strongly Bound in Leather, 3s. 6d.*  
Provided with Detachable Blank Pages for MS.

THE MINING ENGINEERS' REPORT BOOK  
AND DIRECTORS' AND SHAREHOLDERS' GUIDE TO MINING REPORTS.

By EDWIN R. FIELD, M.INST.M.M.

*With Notes on the Valuation of Property, and Tabulating Reports,  
Useful Tables, and Examples of Calculations, &c.*

"An ADMIRABLY compiled book which Mining Engineers and Managers will find  
EXTREMELY USEFUL."—*Mining Journal*.

*In Crown 8vo. Handsome Cloth. Illustrated. 10s. 6d. net.*

A DICTIONARY OF  
SPANISH-ENGLISH AND SPANISH-AMERICAN MINING,  
METALLURGICAL, AND ALLIED TERMS.

*To which some Portuguese and Portuguese-American (Brazilian) Terms are added.*

By EDWARD HALSE, A.R.S.M.,

Mem. Inst. Ming. and Metall., of the Eng. Inst. of Ming. and Metall. Engrs., &c., &c.

"Will be found of the greatest service to the mining profession."—*Mining Journal*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

**WORKS ON SINKING, EXPLOSIVES, &c.**

In Medium 8vo, Handsome Cloth. With 18 Figures in the Text,  
and 19 Folding Plates. 10s. 6d. net.

**SHAFT-SINKING IN DIFFICULT CASES.**

By J. RIEMER,

TRANSLATED BY J. W. BROUGH, A.M. INST. C.E.

CONTENTS.—Shaft Sinking by Hand.—Shaft Sinking by Boring.—The Freezing Method.—The Sinking Drum Process.—BIBLIOGRAPHY.—INDEX.

"The translator deserves the thanks of the mining community for placing this valuable work before them. . . . The work is one which every mining engineer should include in his library."—*Mining World*.

SECOND EDITION, Revised. In Large 8vo, with Numerous Illustrations  
and Folding Plates. 10s. 6d.

**BLASTING: AND THE USE OF EXPLOSIVES.**

By OSCAR GUTTMANN, M. INST. C.E., F.I.C., F.C.S.

CONTENTS.—Historical Sketch.—Blasting Materials.—Qualities and Handling of Explosives.—The Choice of Blasting Materials.—Preparation of Blasts.—Chamber Mines.—Charging of Boreholes.—Determination of Charge.—Blasting in Boreholes.—Firing.—Results of Working.—Various Blasting Operations.—INDEX.

"Should prove a *vade-mecum* to Mining Engineers and all engaged in practical work."—*Iron and Coal Trades Review*.

In Medium 8vo, Cloth. With many Illustrations in the Text.  
Four Full Page Plates and Four Folding Tables. 6s. net.

**NEW METHODS OF  
TESTING EXPLOSIVES.**

By O. E. BICHEL.

TRANSLATED AND EDITED BY ALEX. LARSEN, M. INST. C.E.

CONTENTS.—Introductory.—Historical.—Testing Stations.—Power Gauges.—Products of Combustion.—Rate of Detonation.—Length and Duration of Flame.—After-Flame Ratio.—Transmission of Explosion.—Conclusions.—Efficiency.

"Its pages bristle with suggestions and actual experimental results to an extent seldom found in a volume of five times its size."—*Arms and Explosives*.

In Crown 8vo. Handsome Cloth. Fully Illustrated.

**A MANUAL ON  
ELECTRICAL SIGNALLING IN MINES.**

By GERALD J. HOOHWINKEL, M. INST. E.E., M.I. MIN. E.

CONTENTS.—SECTION I.—Electric Haulage Signals—(a) Acoustic Signals.—(b) Optical Signals.—(c) Acoustic Optical Signals.—Current Supply.—Batteries.—Accumulators.—Main Supply.—Design and Construction of Signalling Installations.—Maintenance of Signalling Installations. SECTION II.—Electric Shaft Signals—(a) Acoustic Signals.—(b) Electro-Mechanical Signals.—(c) Optical Acoustic Signals.—Signals for Winding Minerals.—For Winding Men.—Signalling from the Cage.—Emergency Signals.—Bells.—Mine Telegraphs.—Mine Telephones. SECTION III.—Special Applications in Mines.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND



SECOND EDITION, *Revised Throughout. In Medium 8vo. With Numerous Plates, Maps, and Illustrations. 21s. net.*

## CYANIDING GOLD & SILVER ORES.

A Practical Treatise on the Cyanide Process; its Application, Methods of Working, Design and Construction of Plant, and Costs.

By H. FORBES JULIAN,

Mining and Metallurgical Engineer; Specialist in Gold: Late Technical Adviser of the Deutsche Gold und Silber Scheide Anstalt, Frankfurt-on-Maine.

AND EDGAR SMART, A.M.I.C.E.,

Civil and Metallurgical Engineer.

"A handsome volume of 400 pages which will be a valuable book of reference for all associated with the process."—*Mining Journal*.

"The authors are to be congratulated upon the production of what should prove to be a standard work."—*Page's Magazine*.

*In Large Crown 8vo. With 13 Plates and many Illustrations in the Text. Handsome Cloth. 7s. 6d. net.*

## THE CYANIDE PROCESS OF GOLD EXTRACTION.

A Text-Book for the Use of Metallurgists and Students at Schools of Mines, &c.

By JAMES PARK, F.G.S., M.INST.M.M.,

Professor of Mining and Director of the Otago University School of Mines; late Director Thames School of Mines, and Geological Surveyor and Mining Geologist to the Government of New Zealand.

FOURTH ENGLISH EDITION. Thoroughly Revised and Greatly Enlarged. With additional details concerning the Siemens-Halske and other recent processes.

"Deserves to be ranked as amongst the BEST OF EXISTING TREATISES."—*Mining Journal*.

THIRD EDITION, Revised. *With Plates and Illustrations. Cloth, 3s. 6d.*

## GETTING GOLD:

A GOLD-MINING HANDBOOK FOR PRACTICAL MEN.

By J. O. F. JOHNSON, F.G.S., A.I.M.E.,

Life Member Australasian Mine-Managers' Association.

GENERAL CONTENTS.—Introductory: Prospecting (Alluvial and General)—Lode or Reef Prospecting—Genesisiology of Gold—Auriferous Lodes—Drifts—Gold Extraction—Lixiviation—Calcination—Motor Power and its Transmission—Company Formation—Mining Appliances and Methods—Australasian Mining Regulations.

"PRACTICAL from beginning to end . . . deals thoroughly with the Prospecting, Sinking, Crushing, and Extraction of gold."—*Brit. Australasian*.

*In Crown 8vo. Illustrated. Fancy Cloth Boards. 4s. 6d.*

## GOLD SEEKING IN SOUTH AFRICA:

A Handbook of Hints for intending Explorers, Prospectors, and Settlers.

By THEO KASSNER,

Mine Manager, Author of the Geological Sketch Map of the De Kaap Gold Fields.

*With a Chapter on the Agricultural Prospects of South Africa.*

"As fascinating as anything ever penned by Jules Verne."—*African Commerce*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND

**GRIFFIN'S "NEW LAND" SERIES.**

*Practical Hand-Books for the Use of Prospectors, Explorers, Settlers, Colonists, and all Interested in the opening up and Development of New Lands.*

EDITED BY GRENVILLE A. J. COLE, M.R.I.A., F.G.S.,  
Professor of Geology in the Royal College of Science for Ireland, and Examiner in  
the University of London.

*In Crown 8vo. Handsome Cloth. 5s.*

*With Numerous Maps Specially Drawn and Executed for this Work.*

# NEW LANDS:

## THEIR RESOURCES AND PROSPECTIVE ADVANTAGES.

By HUGH ROBERT MILL, D.Sc., LL.D., F.R.S.E.,

"A want admirably supplied. . . . Has the advantage of being written by a pro-  
cessed Geographer."—*Geographical Journal*.

*With many Engravings and Photographs. Handsome Cloth, 4s. 6d.*

# FOOD SUPPLY.

By ROBERT BRUCE,

Agricultural Superintendent to the Royal Dublin Society.

With Appendix on Preserved Foods by C. A. MITCHELL, B.A., F.I.C.

"The work is one which will appeal to those intending to become farmers at home or in the Colonies, and who desire to obtain a general idea of the true principles of farming in ALL ITS BRANCHES."—*Journal of the Royal Colonial Inst.*

FIFTH EDITION. *With Illustrations. Handsome Cloth, 5s.*

# PROSPECTING FOR MINERALS.

*A Practical Handbook for Prospectors, Explorers, Settlers, and all interested in the Opening up and Development of New Lands.*

By S. HERBERT COX, Assoc.R.S.M., M.Inst.M.M., F.G.S.,

Professor of Mining at the Royal School of Mines.

**GENERAL CONTENTS.**—Introduction and Hints on Geology—The Determination of Minerals: Use of the Blow-pipe, &c.—Rock-forming Minerals and Non-Metallic Minerals of Commercial Value: Rock Salt, Borax, Marbles, Lithographic Stone, Quartz and Opal, &c., &c.—Precious Stones and Gems—Stratified Deposits: Coal and Ores—Mineral Veins and Lodes—Irregular Deposits—Dynamics of Lodes: Faults, &c.—Alluvial Deposits—Noble Metals: Gold, Platinum, Silver, &c.—Lead—Mercury—Copper—Tin—Zinc—Iron—Nickel, &c.—Sulphur, Antimony, Arsenic, &c.—Combustible Minerals—Petroleum—General Hints on Prospecting—Glossary—Index.

"This ADMIRABLE LITTLE WORK . . . written with SCIENTIFIC ACCURACY in a CLEAR and LUCID style. . . . An IMPORTANT ADDITION to technical literature . . ."  
—*Mining Journal*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND

*Demij 8vo, Handsome cloth, 34s.*

# Stratigraphical Geology & Palæontology,

ON THE BASIS OF PHILLIPS.

BY ROBERT ETHERIDGE, F.R.S.,

OF THE NATURAL HIST. DEPARTMENT, BRITISH MUSEUM, LATE PALÆONTOLOGIST TO THE  
GEOLOGICAL SURVEY OF GREAT BRITAIN, PAST PRESIDENT OF THE  
GEOLOGICAL SOCIETY, ETC.

**With Map, Numerous Tables, and Thirty-six Plates.**

"No such compendium of geological knowledge has ever been brought together before."—*Westminster Review*.

"If PROF. SKELEY's volume was remarkable for its originality and the breadth of its views, Mr. ETHERIDGE fully justifies the assertion made in his preface that his book differs in construction and detail from any known manual. . . . Must take HIGH RANK AMONG WORKS OF REFERENCE."—*Athenæum*.

SIXTH EDITION, Thoroughly Revised. With Frontispiece and  
Illustrations. Cloth. 10s. 6d.

## AIDS IN PRACTICAL GEOLOGY:

WITH A SECTION ON PALÆONTOLOGY.

BY PROFESSOR GRENVILLE COLE, M.R.I.A., F.G.S.

GENERAL CONTENTS.—

PART I.—SAMPLING OF THE EARTH'S CRUST.

PART II.—EXAMINATION OF MINERALS.

PART III.—EXAMINATION OF ROCKS.

PART IV.—EXAMINATION OF FOSSILS.

"DESERVING OF THE HIGHEST PRAISE. Here indeed are 'Aids' INNUMERABLE and INVALUABLE. All the directions are given with the utmost clearness and precision."—*Athenæum*.

"That the work deserves its title, that it is full of 'AIDS,' and in the highest degree PRACTICAL, will be the verdict of all who use it."—*Nature*.

## OPEN-AIR STUDIES IN GEOLOGY:

An Introduction to Geology Out-of-doors.

BY PROFESSOR GRENVILLE COLE, M.R.I.A., F.G.S.

For details, see Griffin's Introductory Science Series, p. 71.

*In Crown 8vo. Handsome Cloth. 2s. 6d.*

## RESEARCHES ON THE PAST AND PRESENT HISTORY OF THE EARTH'S ATMOSPHERE.

*Including the latest Discoveries and their Practical Applications.*

BY DR. THOMAS LAMB PHIPSON.

PART I.—The Earth's Atmosphere in Remote Geological Periods.

PART II.—The Atmosphere of our present period. Appendices; Index.

"The book should prove of interest to general readers, as well as to meteorologists and other students of science."—*Nature*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



## Griffin's Metallurgical Series.

### STANDARD WORKS OF REFERENCE

FOR

Metallurgists, Mine-Owners, Assayers, Manufacturers,  
and all interested in the development of  
the Metallurgical Industries.

EDITED BY

Sir W. ROBERTS-AUSTEN, K.C.B., D.C.L., F.R.S.

*In Large 8vo, Handsome Cloth. With Illustrations.*

#### INTRODUCTION to the STUDY of METALLURGY.

By the EDITOR. SIXTH EDITION. (See p. 48.)

**GOLD** (The Metallurgy of). By THOS. KIRKE ROSE, D.Sc., Assoc. R.S.M., F.C.S., Chemist and Assayer of the Royal Mint. FIFTH EDITION. 21s. (See p. 48.)

**LEAD** (The Metallurgy of). By H. F. COLLINS, Assoc. R.S.M., M.Inst.M.M. SECOND EDITION. (See p. 49.)

**SILVER** (The Metallurgy of). By H. F. COLLINS, A.R.S.M., M.Inst.M.M. SECOND EDITION. (See p. 49.)

**IRON** (The Metallurgy of). By T. TURNER, A.R.S.M., F.I.C., F.C.S. THIRD EDITION, Revised. 16s. net. (See p. 50.)

**STEEL** (The Metallurgy of). By F. W. HARBORD, Assoc.R.S.M., F.I.C., with a Section on Mechanical Treatment by J. W. HALL, A.M.Inst.C.E. THIRD EDITION. 25s. net. (See p. 50.)

**ALLOYS.** By EDWARD F. LAW, Assoc.R.S.M. With Frontispiece in Colours, and Fine Series of Micro-photographs. 12s. 6d. net. (See p. 49.)

**ANTIMONY.** By C. Y. WANG, M.A., B.Sc. Fully Illustrated. 12s. 6d. net. (See p. 50.)

*Will be Published at Short Intervals.*

**METALLURGICAL MACHINERY:** the Application of Engineering to Metallurgical Problems. By HENRY CHARLES JENKINS, Wh.Sc., Assoc. R.S.M.

**COPPER** (The Metallurgy of). By THOS. C. CLOUD, Assoc. R.S.M.

\* \* Other Volumes in Preparation.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

---

**GRIFFIN'S METALLURGICAL SERIES.**


---

SIXTH EDITION, thoroughly Revised and considerably Enlarged. Large 8vo, with numerous Illustrations and Micro-Photographic Plates of different varieties of Steel.

An Introduction to the Study of  
**METALLURGY.**

BY

Sir W. ROBERTS-AUSTEN, K.C.B., D.C.L., F.R.S., A.R.S.M.,  
 Late Chemist and Assayer of the Royal Mint, and Professor of Metallurgy  
 in the Royal College of Science.

Revised throughout by F. W. HARBORD, A.R.S.M., F.I.C.

GENERAL CONTENTS.—The Relation of Metallurgy to Chemistry.—Physical Properties of Metals.—Alloys. The Thermal Treatment of Metals.—Fuel and Thermal Measurements.—Materials and Products of Metallurgical Processes.—Furnaces.—Means of Supplying Air to Furnaces.—Thermo-Chemistry.—Typical Metallurgical Processes.—The Micro-Structure of Metals and Alloys.—Economic Considerations.

"No English text-book at all approaches this in the COMPLETENESS with which the most modern views on the subject are dealt with. Professor Austen's volume will be INVALUABLE, not only to the student, but also to those whose knowledge of the art is far advanced."—*Chemical News*.

---

FIFTH EDITION, Revised, Considerably Enlarged, and in part Re-written.  
 With Frontispiece and numerous Illustrations. 21s.

**THE METALLURGY OF GOLD.**

BY

T. KIRKE ROSE, D.Sc.Lond., Assoc.R.S.M.,  
*Chemist and Assayer of the Royal Mint.*

GENERAL CONTENTS.—The Properties of Gold and its Alloys.—Chemistry of the Compounds of Gold.—Mode of Occurrence and Distribution of Gold.—Shallow Placer Deposits.—Deep Placer Deposits.—Quartz Crushing in the Stamp Battery.—Amalgamation in the Stamp Battery.—Other Forms of Crushing and Amalgamating Machinery.—Concentration in Gold Mills.—Dry Crushing.—Re-grinding.—Roasting.—Chlorination: The Plattner Process, The Barrel Process, The Vat-Solution Process.—The Cyanide Process.—Chemistry of the Cyanide Process.—Refining and Parting of Gold Bullion.—Assay of Gold Ores.—Assay of Gold Bullion.—Statistics of Gold Production.—Bibliography.—INDEX.

"A COMPREHENSIVE PRACTICAL TREATISE on this important subject."—*The Times*.

"The MOST COMPLETE description of the CHLORINATION PROCESS which has yet been published."—*Mining Journal*.

"Adapted for all who are interested in the Gold Mining Industry, being free from technicalities as far as possible, but is more particularly of value to those engaged in the industry."—*Cape Times*.

---

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

**GRIFFIN'S METALLURGICAL SERIES.**

EDITED BY SIR W. ROBERTS-AUSTEN, K.C.B., F.R.S., D.C.L.  
In Large 8vo. Handsome Cloth. With Illustrations.

SECOND EDITION, Revised Throughout and Enlarged. Illustrated.

**THE METALLURGY OF LEAD.**

By H. F. COLLINS, Assoc.R.S.M., M.INST.M.M.

A Complete and Exhaustive Treatise on the Manufacture of Lead, with Sections on Smelting and Desilverisation, and Chapters on the Assay and Analysis of the Materials involved.

"A THOROUGHLY SOUND and useful digest. May with EVERY CONFIDENCE be recommended."—*Mining Journal*.

SECOND EDITION, Revised Throughout and Enlarged. Illustrated.

**THE METALLURGY OF SILVER.**

By H. F. COLLINS, Assoc.R.S.M., M.INST.M.M.

Comprising Details regarding the Sources and Treatment of Silver Ores, together with Descriptions of Plant, Machinery, and Processes of Manufacture, Refining of Bullion, Cost of Working, &c.

"The author has focussed a LARGE AMOUNT OF VALUABLE INFORMATION into a convenient form. . . . The author has evidently considerable practical experience, and describes the various processes clearly and well."—*Mining Journal*.

JUST PUBLISHED. Frontispiece in Colours, and Beautiful Series of Photo-micrographs. 12s. 6d. net.

**A L L O Y S**  
**AND THEIR INDUSTRIAL APPLICATIONS.**

By EDWARD F. LAW, A.R.S.M.

CONTENTS.—Introduction.—Properties of Alloys.—Methods of Investigation.—Constitution.—Influence of Temperature on Properties.—Corrosion of Alloys.—Copper Alloys, Brass, Bronzes.—Special Brasses and Bronzes.—German Silver and Miscellaneous Copper Alloys.—White Metal Alloys.—Anti-Friction Alloys.—Aluminium Alloys.—Silver and Gold Alloys.—Iron Alloys.—Miscellaneous Alloys (Amalgams, &c.).—INDEX.

"Concise and practical . . . a valuable amount of information that will be appreciated by student and manufacturer alike."—*Foundry Trades' Journal*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



**GRIFFIN'S METALLURGICAL SERIES.**

THIRD EDITION, Revised. With Numerous Illustrations. Large 8vo.  
Handsome Cloth. 25s. net.

*With Additional Chapter on The Electric Smelting of Steel.*

**THE METALLURGY OF STEEL.**

By F. W. HARBORD, Assoc.R.S.M., F.I.C.

With 37 Plates, 280 Illustrations in the Text, and nearly 100 Micro-  
Sections of Steel, and a Section on

*THE MECHANICAL TREATMENT OF STEEL.*

By J. W. HALL, A.M.Inst.C.E.

ABRIDGED CONTENTS.—The Plant, Machinery, Methods and Chemistry of the Bessemer and of the Open Hearth Processes (Acid and Basic).—The Mechanical Treatment of Steel comprising Mill Practice, Plant and Machinery.—The Influence of Metalloids, Heat Treatment, Special Steels, Microstructure, Testing, and Specifications.

The Engineer says, at the conclusion of a review of this book:—"We cannot conclude without earnestly recommending all who may be interested as makers or users of steel, which practically means the whole of the engineering profession, to make themselves acquainted with it as speedily as possible, and this may be the more easily done as the published price, considering the size of the book, is extremely moderate."

THIRD EDITION, Revised and Enlarged. With many new Plates.  
16s. net.

**THE METALLURGY OF IRON.**

By THOMAS TURNER, Assoc.R.S.M., F.I.C.,

*Professor of Metallurgy in the University of Birmingham.*

*General Contents.*—Early History of Iron.—Modern History of Iron.—The Age of Steel.—Chief Iron Ores.—Preparation of Iron Ores.—The Blast Furnace.—The Air used in the Blast Furnace.—Reactions of the Blast Furnace.—The Gaseous Products of the Blast Furnace.—The Fuel used in the Blast Furnace.—Slags and Fluxes of Iron Smelting.—Properties of Cast Iron.—Foundry Practice.—Wrought Iron.—Indirect Production of Wrought Iron.—The Puddling Process.—Further Treatment of Wrought Iron.—Corrosion of Iron and Steel.

"A THOROUGHLY USEFUL BOOK, which brings the subject UP TO DATE. OF GREAT VALUE to those engaged in the iron industry."—*Mining Journal*.

\* \* For Professor Turner's *Lectures on Iron-Founding*, see page 53.

JUST PUBLISHED. In Large 8vo. Handsome Cloth. Fully Illustrated.  
12s. 6d. net.

**ANTIMONY:**

Its History, Chemistry, Mineralogy, Geology, Metallurgy, Uses and  
Preparation, Analysis, Production and Valuation.

By C. Y. WANG, M.A., B.Sc.,

Mem. Am. Inst. Mining Eng.; Mem. Iron and Steel Institute; Mining Engineer to  
the Chung Lou General Mining Company; Geologist for the  
Hunan Province, China, &c., &c.

"A book which stands alone, inasmuch as there is not, to our knowledge, any other complete treatise on antimony among all the English text-books."—*Iron and Coal Trades' Review*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

TENTH EDITION. With Tables and Illustrations. Cloth, 10s. 6d.

## A TEXT-BOOK OF ASSAYING:

*For the use of Students, Mine Managers, Assayers, &c.*

By J. J. BERINGER, F.I.C. F.C.S.,

Public Analyst for, and Lecturer to the Mining Association of, Cornwall.

AND C. BERINGER, F.C.S.,

Late Chief Assayer to the Rio Tinto Copper Company, London,

GENERAL CONTENTS. — PART I — INTRODUCTORY: MANIPULATION: Sampling; Drying; Calculation of Results—Laboratory-books and Reports. METHODS: Dry Gravimetric; Wet Gravimetric—Volumetric Assays: Titrimetric, Colorimetric, Gasometric—Weighing and Measuring—Reagents—Formulæ, Equations, &c.—Specific Gravity.

PART II.—METALS: Detection and Assay of Silver, Gold, Platinum, Mercury, Copper, Lead, Thallium, Bismuth, Antimony, Iron, Nickel, Cobalt, Zinc, Cadmium, Tin, Tungsten, Titanium, Manganese, Chromium, &c.—Earths, Alkalies.

PART III.—NON-METALS: Oxygen and Oxides; The Halogens—Sulphur and Sulphates—Arsenic, Phosphorus, Nitrogen—Silicon, Carbon, Boron—Useful Tables.

"A REALLY MERITORIOUS WORK, that may be safely depended upon either for systematic instruction or for reference."—*Nature*

In Crown 8vo. Handsome Cloth. Fully Illustrated. 3s. net.

AN INTRODUCTION TO

## PRACTICAL METALLURGY.

By PROF. THOMAS TURNER, A.R.S.M., F.I.C.

"It is an excellent and handy book for its purpose, and will have a far wider range of usefulness than for class work alone."—*Practical Engineer.*

FOURTH EDITION, Revised. With Numerous Illustrations. 6s.

A TEXT-BOOK OF

## ELEMENTARY METALLURGY.

Including the Author's PRACTICAL LABORATORY COURSE.

By A. HUMBOLDT SEXTON, F.I.C., F.C.S.

"Just the kind of work for Students COMMENCING the study of Metallurgy, or for ENGINEERING Students."—*Practical Engineer.*

Large 8vo. Cloth. With Illustrations. 12s. 6d. net.

## METALLURGICAL ANALYSIS & ASSAYING:

A THREE YEARS' COURSE FOR STUDENTS OF SCHOOLS OF MINES.

By W. A. MACLEOD, B.A., B.Sc., AND CHAS. WALKER, F.C.S.

"The publication of this volume tends to prove that the teaching of metallurgical analysis and assaying in Australia rests in competent hands."—*Nature.*

THIRD EDITION. With Folding Plates and Many Illustrations. 36s.

## ELEMENTS OF METALLURGY.

A Practical Treatise on the Art of Extracting Metals from their Ores.

By J. ARTHUR PHILLIPS, M.INST.C.E., F.G.S., &c., AND  
H. BAUERMAN, V.P.G.S.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

In Crown 8vo. Handsome cloth. With 102 Illustrations. 6s. net.

**A HANDBOOK ON  
METALLIC ALLOYS:**  
Their Structure and Constitution.

By GILBERT H. GULLIVER, B.Sc., F.R.S.E.

"A valuable addition to existing literature on alloys."—*Foundry Trades' Journal*.

In Crown 8vo. Beautifully Illustrated with nearly 100  
Microphotographs of Steel, &c. 7s. 6d. net.

**Microscopic Analysis of Metals.**

By FLORIS OSMOND & J. E. STEAD, F.R.S., F.I.C.

"There has been no work previously published in English calculated to be so useful to the student in metallographic research."—*Iron and Steel Trades' Journal*.

In Large 8vo. Handsome Cloth. Price 4s.

**QUANTITATIVE METALLURGICAL ANALYSIS.**

TABLES FOR LABORATORY USE.

ON THE PRINCIPLE OF "GROUP" SEPARATIONS.

By J. JAMES MORGAN, F.C.S., M.S.C.I.

"The Author may be CONGRATULATED on the way his work has been carried out."—*The Engineer*.

THIRD EDITION, Revised, Enlarged, and Re-written.

**A TREATISE ON  
ELECTRO-METALLURGY:**

Embracing the Application of Electrolysis to the Plating, Depositing,  
Smelting, and Refining of various Metals, and to the Repro-  
duction of Printing Surfaces and Art-Work, &c.

By W. G. McMILLAN, F.I.C., AND W. R. COOPER.

"Excellent, . . . one of the BEST and MOST COMPLETE manuals hitherto published on Electro-Metallurgy."—*Electrical Review* (on the Second Edition).

SECOND EDITION, Thoroughly Revised and Enlarged. In large 8vo.  
With Numerous Illustrations and Three Folding-Plates. 21s. net.

**ELECTRIC SMELTING & REFINING:**

A Practical Manual of the Extraction and Treatment  
of Metals by Electrical Methods.

Being the "ELEKTRO-METALLURGIE" of DR. W. BORCHERS.

Translated from the Latest German Edition by WALTER G. McMILLAN,  
F.I.C., F.C.S.

"COMPREHENSIVE and AUTHORITATIVE . . . not only FULL of VALUABLE INFORMATION, but gives evidence of a THOROUGH INSIGHT into the technical VALUE and POSSIBILITIES of all the methods discussed."—*The Electrician*.

LONDON: CHARLES GRIFFIN & CO., LIMITED EXETER STREET, STRAND.



*In Medium Svo. Handsome Cloth. Fully Illustrated. 15s. net.*

## GENERAL FOUNDRY PRACTICE:

*A Practical Handbook for Iron, Steel and Brass Founders,  
Metallurgists, and Students of Metallurgy.*

By A. McWILLIAM, A.R.S.M., AND PERCY LONGMUIR.

"The student of foundry work . . . needs no other text-book. . . . The book contains a tremendous amount of information, and is well written."—*Engineering Times.*

SECOND EDITION. *Extra Crown Svo. With many Illustrations.  
3s. 6d. net.*

## LECTURES ON IRON-FOUNDING.

By THOMAS TURNER, M.Sc., A.R.S.M., F.I.C.,

Professor of Metallurgy in the University of Birmingham.

CONTENTS.—Varieties of Iron and Steel.—Application of Cast Iron.—History.—Production.—Iron Ores.—Composition.—The Blast Furnace.—Materials.—Reactions.—Grading Pig Iron.—Carbon, Silicon, Sulphur, Phosphorus, Manganese, Aluminium, Arsenic, Copper, and Titanium.—The Foundry.—General Arrangement.—Re-melting Cast Iron.—The Cupola.—Fuel Used.—Changes due to Re-melting.—Moulds and Moulding.—Foundry Ladles.—Pouring and Pouring Temperature.—Common Troubles.—Influence of Shape and Size on Strength of Castings.—Tests.

"Ironfounders will find much information in the book."—*Iron Trade Circular Ryland's.*

*In Crown Svo. Handsome Cloth. 1s. 6d. net.*

## BLAST FURNACE PRACTICE.

By J. JAMES MORGAN, F.C.S., M.S.C.I.,

Author of "Quantitative Metallurgical Tables," &c.

CONTENTS.—Requirements.—Iron Ores.—Fuel. Flux. Slags.—Quantity of Slag.—Burden, Charge, Round.—The Blast.—Ore Mixing.—Amount and Composition of the Iron.—Calculation of Flux.—Heating the Blast; Stoves.—Drying, Changing, and Cleaning.—Drying the Furnace.—Filling the Furnace, and Lighting.—Charging the Furnace.—Descent of the Charge.—Flushing.—Tapping.—Hard Tapping Hole.—Running down the Beds (Casting).—Judging the Temperature.—Controlling the Temperature.—Temperature and the Reduction of Silicon.—The Pig Iron.—Fuel Consumption.—Economy in Fuel Consumption.—Tuyeres: Leaky, Changing.—Cooler or "Jumbo."—Obstructions.—Pillaring.—Breakouts.—Hot Spots.—Scaffolds (Hanging).—Slips.—Damping Down.—Blowing Out.—INDEX.

SECOND EDITION, *Revised. In Large Crown Svo. With Numerous  
Illustrations. 7s. 6d. net.*

## THE ART OF THE GOLDSMITH AND JEWELLER.

*A Manual on the Manipulation of Gold and the  
Manufacture of Personal Ornaments.*

By THOS. B. WIGLEY,

Headmaster of the Jewellers and Silversmiths' Assoc. Tech. School, Birmingham.

ASSISTED BY J. H. STANSBIE, B.Sc. (LOND.), F.I.C.,

Lecturer at the Birmingham Municipal Technical School.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

SECOND EDITION, Revised, Enlarged, and Re-set Throughout on Larger Page.  
With Valuable Bibliography, New Maps, Illustrations, &c. 45s. net.

IN TWO VOLUMES.

A TREATISE ON

# PETROLEUM.

By SIR BOVERTON REDWOOD,

D.Sc., F.R.S.E., Assoc. Inst. C.E., F.I.C.

CONTENTS.—SECTION I.: Historical Account of the Petroleum Industry.—SECTION II.: Geological and Geographical Distribution of Petroleum and Natural Gas.—SECTION III.: The Chemical and Physical Properties of Petroleum and Natural Gas.—SECTION IV.: The Origin of Petroleum and Natural Gas.—SECTION V.: The Production of Petroleum, Natural Gas, and Ozokerite.—SECTION VI.: The Refining of Petroleum.—SECTION VII.: The Shale Oil and Allied Industries.—SECTION VIII.: The Transport, Storage, and Distribution of Petroleum.—SECTION IX.: The Testing of Crude Petroleum, Petroleum and Shale Oil Products, Ozokerite, and Asphalt.—SECTION X.: The Uses of Petroleum and its Products.—SECTION XI.: Statutory, Municipal, and other Regulations relating to the Testing, Storage, Transport, and Use of Petroleum and its Products.—APPENDICES.—BIBLIOGRAPHY.—INDEX.

"It is indisputably the most comprehensive and complete treatise on petroleum, and this statement is true, no matter on what branch of the industry a test of its merits is made. It is the only book in existence which gives the oil man a clear and reliable outline of the growth and present-day condition of the entire petroleum world. . . . There is a wonderfully complete collection of plates and illustrations."—*Petroleum World*.

SECOND EDITION, Revised. With Illustrations. Price 8s. 6d. net.

## A HANDBOOK ON PETROLEUM. FOR INSPECTORS UNDER THE PETROLEUM ACTS,

And for those engaged in the Storage, Transport, Distribution, and Industrial Use of Petroleum and its Products, and of Calcium Carbide. With suggestions on the Construction and Use of Mineral Oil Lamps.

By CAPTAIN J. H. THOMSON,

H.M. Chief Inspector of Explosives,

AND SIR BOVERTON REDWOOD,

Author of "A Treatise on Petroleum."

"A volume that will enrich the world's petroleum literature, and render a service to the British branch of the industry. . . . Reliable, indispensable, a brilliant contribution."—*Petroleum*.

In Crown 8vo. Fully Illustrated. 2s. 6d. net.

## THE LABORATORY BOOK OF MINERAL OIL TESTING.

By J. A. HICKS,

Chemist to Sir Boverton Redwood

Should be on the shelves of every analytical chemist in practice."—*Chemical Trade Journal*.

In Large Crown 8vo, Cloth. Fully Illustrated 5s. net.

## OIL FUEL:

ITS SUPPLY, COMPOSITION, AND APPLICATION.

By SIDNEY H. NORTH,

LATE EDITOR OF THE "PETROLEUM REVIEW."

CONTENTS.—The Sources of Supply.—Economic Aspect of Liquid Fuel.—Chemical Composition of Fuel Oils.—Conditions of Combustion in Oil Fuel Furnaces.—Early Methods and Experiments.—Modern Burners and Methods.—Oil Fuel for Marine Purposes.—For Naval Purposes.—On Locomotives.—For Metallurgical and other Purposes.—Appendices.—INDEX.

"Everyone interested in this important question will welcome Mr. North's excellent text-book."—*Nature*.

**THE PETROLEUM LAMP: Its Choice and Use.** A Guide to the Safe Employment of the Paraffin Lamp. By CAPT. J. H. THOMSON and Sir BOVERTON REDWOOD. Illustrated. 1s. net.

"A work which will meet every purpose for which it has been written."—*Petroleum*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND

In Two Vols., Large 8vo. With Illustrations. Sold Separately.

## CHEMISTRY FOR ENGINEERS AND MANUFACTURERS.

BY

BERTRAM BLOUNT, F.I.C., & A. G. BLOXAM, F.I.C.

**VOLUME I.**—Chemistry of Engineering, Building, and Metallurgy.—*General Contents.*—INTRODUCTION.—Chemistry of the Chief Materials of Construction.—Sources of Energy.—Chemistry of Steam-raising.—Chemistry of Lubrication and Lubricants.—Metallurgical Processes used in the Winning and Manufacture of Metals. Price 10s. 6d.

**VOLUME II.**—The Chemistry of Manufacturing Processes.—*General Contents.*—Sulphuric Acid Manufacture.—Alkali, &c.—Destructive Distillation.—Artificial Manure.—Petroleum.—Lime and Cement.—Clay and Glass.—Sugar and Starch.—Brewing and Distilling.—Oils, Resins, and Varnishes.—Soap and Candles.—Textiles and Bleaching.—Colouring Matters, Dyeing and Printing.—Paper and Pasteboard.—Pigments and Paints.—Leather, Glue, and Size.—Explosives and Matches.—Minor Manufactures. THIRD EDITION, Thoroughly Revised. Illustrated.

SECOND EDITION. In Large 8vo. Handsome Cloth. With 800 pages and 154 Illustrations. 25s. net.

## OILS, FATS, BUTTERS, AND WAXES:

THEIR PREPARATION AND PROPERTIES, AND MANUFACTURE THEREFROM OF CANDLES, SOAPS, AND OTHER PRODUCTS.

By C. R. ALDER WRIGHT, D.Sc., F.R.S.,

Late Lecturer on Chemistry, St. Mary's Hospital Medical School; Examiner in "Soap" to the City and Guilds of London Institute.

Thoroughly Revised, Enlarged, and in Part Rewritten

By C. AINSWORTH MITCHELL, B.A., F.I.C., F.C.S.

"Will be found ABSOLUTELY INDISPENSABLE."—*The Analyst*.

"Will rank as the STANDARD ENGLISH AUTHORITY on OILS and FATS for many years to come."—*Industries and Iron*.

*In Two Volumes, Half Morocco, each complete in itself.*

## PHYSICO-CHEMICAL TABLES

For the Use of Analysts, Physicists, Chemical Manufacturers and Scientific Chemists.

**Volume I.**—Chemical Engineering, Physical Chemistry. 24s. net.

**Volume II.**—Chemical Physics, Pure and Analytical Chemistry.

[*Shortly.*]

By JOHN CASTELL-EVANS, F.I.C., F.C.S.,

Lecturer on Inorganic Chemistry and Metallurgy at the Finsbury Technical College.

The Work comprehends as far as possible ALL RULES AND TABLES required by the Analyst, Brewer, Distiller, Acid- and Alkali-Manufacturer, &c., &c.; and also the principal data in THERMO-CHEMISTRY, ELECTRO-CHEMISTRY, and the various branches of CHEMICAL PHYSICS. Every possible care has been taken to ensure perfect accuracy, and to include the results of the most recent investigations.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



SIXTH EDITION, Thoroughly Revised. Fully Illustrated. 21s.

## FOODS: THEIR COMPOSITION AND ANALYSIS.

BY A. WYNTER BLYTH, M.R.C.S., F.I.C., F.C.S.,

Barrister-at-Law, Public Analyst for the County of Devon, and  
Medical Officer of Health for St. Marylebone.

AND M. WYNTER BLYTH, B.A., B.Sc., F.C.S.

GENERAL CONTENTS.—History of Adulteration.—Legislation.—Apparatus.—“Ash.”—Sugar.—Confectionery.—Honey.—Treacle.—Jams and Preserved Fruits.—Starches.—Wheaten-Flour.—Bread.—Oats.—Barley.—Rye.—Rice.—Maize.—Millet.—Potatoes.—Peas.—Lentils.—Beans.—Milk.—Cream.—Butter.—Oleo-Margarine.—Cheese.—Lard.—Tea.—Coffee.—Cocoa and Chocolate.—Alcohol.—Brandy.—Rum.—Whisky.—Gin.—Arrack.—Liqueurs.—Absinthe.—Yeast.—Beer.—Wine.—Vinegar.—Lemon and Lime Juice.—Mustard.—Pepper.—Sweet and Bitter Almonds.—Annatto.—Olive Oil.—Water Analysis.—Appendix: Adulteration Acts, &c.

“A new edition of Mr. Wynter Blyth's Standard work, ENRICHED WITH ALL THE RECENT DISCOVERIES AND IMPROVEMENTS, will be accepted as a boon.”—*Chemical News*.

FOURTH EDITION, Thoroughly Revised. In Large 8vo, Cloth, with  
Tables and Illustrations. 21s. net.

## POISONS: THEIR EFFECTS AND DETECTION.

BY A. WYNTER BLYTH, M.R.C.S., F.I.C., F.C.S.,

Barrister-at-Law, Public Analyst for the County of Devon, and  
Medical Officer of Health for St. Marylebone.

GENERAL CONTENTS.—I.—Historical Introduction. II.—Classification—Statistics—Connection between Toxic Action and Chemical Composition—Life Tests—General Method of Procedure—The Spectroscope—Examination of Blood and Blood Stains. III.—Poisonous Gases. IV.—Acids and Alkalies. V.—More or less Volatile Poisonous Substances. VI.—Alkaloids and Poisonous Vegetable Principles. VII.—Poisons derived from Living or Dead Animal Substances. VIII.—The Oxalic Acid Group. IX.—Inorganic Poisons. Appendix: Treatment, by Antidotes or otherwise, of Cases of Poisoning.

“Undoubtedly THE MOST COMPLETE WORK on Toxicology in our language.”—*The Analyst*.  
“As a PRACTICAL GUIDE, we know NO BETTER WORK.”—*The Lancet (on the Third Edition)*.

Crown 8vo, Handsome Cloth. Fully Illustrated. 10s. 6d.

## FLESH FOODS:

With Methods for their Chemical, Microscopical, and Bacteriological Examination.

*A Practical Handbook for Medical Men, Analysts, Inspectors and others.*

BY C. AINSWORTH MITCHELL, B.A., F.I.C., F.C.S.

“A compilation which will be most useful for the class for whom it is intended.”—*Athenæum*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

SECOND EDITION. With Numerous Tables, Fully Illustrated.

# DAIRY CHEMISTRY

FOR DAIRY MANAGERS, CHEMISTS, AND ANALYSTS  
A Practical Handbook for Dairy Chemists and others  
having Control of Dairies.

By H. DROOP RICHMOND, F.I.C.,  
CHEMIST TO THE AYLESBURY DAIRY COMPANY.

*Contents.*—I. Introductory.—The Constituents of Milk. II. The Analysis of Milk. III. Normal Milk: its Adulterations and Alterations, and their Detection. IV. The Chemical Control of the Dairy. V. Biological and Sanitary Matters. VI. Butter. VII. Other Milk Products. VIII. The Milk of Mammals other than the Cow.—Appendices.—Tables.—Index.

"... In our opinion the book is the BEST CONTRIBUTION ON THE SUBJECT THAT HAS YET APPEARED in the English language."—*Lancet* (on the First Edition).

Fully Illustrated. With Photographs of Various Breeds of Cattle, &c.  
6s. net.

## MILK: ITS PRODUCTION & USES.

With Chapters on *Dairy Farming, The Diseases of Cattle, and on the Hygiene and Control of Supplies.*

By EDWARD F. WILLOUGHBY,  
M.D. (Lond.), D.P.H. (Lond. and Camb.).

"We cordially recommend it to everyone who has anything at all to do with milk."—*Dairy World*.

In Crown 8vo, Fully Illustrated. 2s. 6d. net.

## THE LABORATORY BOOK OF DAIRY ANALYSIS.

By H. DROOP RICHMOND, F.I.C.,  
Analyst to the Aylesbury Dairy Co., Ltd.

"Without doubt the best contribution to the literature of its subject that has ever been written."—*Medical Times*.

In Large Crown 8vo. Cloth. Fully Illustrated. 4s. 6d. net.

## ELEMENTARY AGRICULTURAL CHEMISTRY.

By HERBERT INGLE, B.Sc., F.I.C., F.C.S.

CONTENTS.—Introduction.—The Atmosphere.—The Soil.—Natural Waters.—The Plant.—Manures.—Crops.—The Animal.—Foods and Feeding.—The Dairy.—Miscellaneous.—INDEX.

AT PRESS. In Crown 8vo. Handsome Cloth. Illustrated.

## SOIL BACTERIA.

By JAMES CLARK, M.A., D.Sc., A.R.C.S.,  
Principal of the Academy, Kilmarnock.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

THIRD EDITION. In Handsome Cloth. Fully Illustrated. 21s. net.  
**PRINCIPLES AND PRACTICE OF BREWING.**  
 FOR THE USE OF STUDENTS AND PRACTICAL MEN.

By WALTER J. SYKES.

REVISED BY ARTHUR R. LING, F.I.C., F.C.S.,

Editor of the Journal of the Institute of Brewing.\*

CONTENTS.—Physical Principles Involved.—The Chemistry of Brewing.—The Microscope.—Vegetable Biology.—Fermentation.—Water.—Barley and Malting.—Arrangement of Brewery Plant.—Quantities of Materials.—Fermentation.—Antiseptics.—Finings.—Characteristics of Beer.—Diseases of Beer.—INDEX.

"A thorough and comprehensive text-book . . . up-to-date . . . a standard text-book."—*Brewers' Journal*.

In Large 8vo. Complete in Two Volumes.

*Each Volume Complete in Itself, and Sold Separately.*

**TECHNICAL MYCOLOGY:**  
*The Utilisation of Micro-organisms in the Arts and Manufactures.*

By DR. FRANZ LAFAR,

Prof. of Fermentation-Physiology and Bacteriology in the Technical High School, Vienna.

TRANSLATED BY CHARLES T. C. SALTER.

**Vol. I.—SCHIZOMYCETIC FERMENTATION.**

**Vol. II.—EUMYCETIC FERMENTATION.**

NOTE.—Part I. of Vol. II. was issued separately at 7s. 6d. Copies of Part II., Vol. II., have, therefore, been bound up to enable those possessing Part I. to complete their copies.

"The first work of the kind which can lay claim to completeness in the treatment of a fascinating subject. The plan is admirable, the classification simple, the style is good, and the tendency of the whole volume is to convey sure information to the reader."—*Lancet*.

Crown 8vo, Handsome Cloth. With Diagrams. 7s. 6d. net.

[*Companion Volume to "FERMENTS," by the same Author.*]

**TOXINES AND ANTITOXINES.**

By CARL OPPENHEIMER, PH.D., M.D.,

Of the Physiological Institute at Erlangen.

TRANSLATED FROM THE GERMAN BY

C. AINSWORTH MITCHELL, B.A., F.I.C., F.C.S.

With Notes, and Additions by the Author, since the publication of the German Edition.

"For wealth of detail, we have no small work on Toxines which equals the one under review."—*Medical Times*

In Crown 8vo, Handsome Cloth. Price 7s. 6d. net.

**FERMENTS: AND THEIR ACTIONS.**

*A Text-book on the Chemistry and Physics of Fermentative Changes.*

By CARL OPPENHEIMER, PH.D., M.D.

TRANSLATED BY C. AINSWORTH MITCHELL, B.A., F.I.C., F.C.S.

"Such a veritable *multum in parvo* has never yet appeared."—*Brewers' Journal*.

LONDON: CHARLES GRIFFIN & CO., LIMITED. EXETER STREET, STRAND



In Crown 8vo. Handsome Cloth. Fully Illustrated. 6s. net.

## PEAT: Its Use and Manufacture.

By PHILIP R. BJÖRLING AND FREDERICK T. GISSING.

GENERAL CONTENTS.—Introduction.—The Formation of Peat.—Area and Depth of Bogs in Principal Countries.—Manufacture of Peat Fuel, &c.—Cut Peat, Dredged Peat, and Manufactured Peat.—Machinery employed in the Manufacture of Peat Fuel.—Peat Moss Litter, and the Machinery employed in its Manufacture.—Peat Charcoal and its Manufacture.—Cost of making Peat Fuel and Charcoal.—Other Productions derived from Peat, such as Tar, Manure, Candles, Dyes, Paper, &c.—BIBLIOGRAPHY.—INDEX.

"The treatment throughout is clear and interesting . . . excellent plates."—*Engineering*.

Companion Volume to the above. In Crown 8vo. Cloth. Fully Illustrated. 6s. net.

## COMMERCIAL PEAT:

Its Uses and Its Possibilities.

By F. T. GISSING.

"A useful and instructive epitome of the development of the industry."—*Mechanical Engineer*.

SECOND EDITION, Revised. In Medium 8vo, Cloth. Illustrated.  
12s. 6d. net.

## PAPER TECHNOLOGY:

AN ELEMENTARY MANUAL ON THE MANUFACTURE, PHYSICAL QUALITIES,  
AND CHEMICAL CONSTITUENTS OF PAPER AND OF  
PAPERMAKING FIBRES.

With Selected Tables for Stationers, Publishers, and Others.

By R. W. SINDALL, F.C.S.

"Exceedingly instructive and particularly useful."—*Paper Makers' Monthly Journal*.

In Crown 8vo. Handsome Cloth. With 30 Illustrations. 6s. net.

## THE CLAYWORKER'S HANDBOOK.

An Epitome of the Materials and Methods employed in Brickmaking and Pottery.

By THE AUTHOR OF "THE CHEMISTRY OF CLAYWORKING," &c.

GENERAL CONTENTS.—Materials used in Clayworking: Clays, Engobes, Glazes, Colours, Water, Fuel, Oils, and Lubricants.—The Preparation of the Clay. Mining and Quarrying, Weathering, Washing, Grinding, Tempering, and Pugging.—Machinery: Boilers, Engines, General Machinery, Sieves, Mixing Machinery, Presses, &c.—Driers and Drying.—Engobing and Glazing.—Setting or Charring, Transport.—Kilns.—Firing.—Discharging, Sorting, and Packing.—Defects and Waste.—Tests, Analysis and Control.—BIBLIOGRAPHY.—TABLES.—INDEX.

"We can thoroughly recommend this handy little book to all our readers."—*Brick and Pottery Trades' Journal*.

In Imperial 8vo. Strongly and Elegantly Bound.

With over 1,000 Pages.

## CERAMIC LITERATURE.

Compiled, Classified, and Described by M. L. SOLON,

President of the English Ceramic Society.

An Analytical Index to the Works Published in all Languages on the History and the Technology of the Ceramic Art; also to the Catalogues of Public Museums, Private Collections, and of Auction Sales in which the Description of Ceramic Objects occupy an important place; and to the most important Price Lists of the Ancient and Modern Manufactories of Pottery and Porcelain.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND

In Large 8vo. Cloth. With 147 Illustrations. 15s. net.

A MANUAL OF

## THE PRINCIPLES OF SEWAGE TREATMENT.

BY PROF. DUNBAR,

Director of the Institute of State Hygiene, Hamburg.

ENGLISH EDITION BY HARRY T. CALVERT, M.Sc., Ph.D., F.I.C.,  
Chief Chemical Assistant, West Riding of Yorkshire Rivers Board.

CONTENTS.—Growth of River Pollution.—Legal Measures taken by Central and Local Authorities.—Rise and Development of Methods of Sewage Treatment.—Earlier Views on Methods of Treatment.—Characteristics of Sewage.—Objects of Purification Works.—Methods for the Removal of Suspended Matters.—For the Removal of Putrescibility.—Disinfection.—Supervision and Inspection of Works.—Utility and Cost.—INDEX.

"We heartily commend the book as a peculiarly fair and impartial statement of the present position of the sewage problem."—*Lancet*.

*Beautifully Illustrated, with Numerous Plates, Diagrams, and  
Figures in the Text. 21s. net.*

## TRADES' WASTE:

ITS TREATMENT AND UTILISATION.

Handbook for Borough Engineers, Surveyors, Architects, and Analysts.

BY W. NAYLOR, F.C.S., A.M. INST. C.E.,

Chief Inspector of Rivers, Ribble Joint Committee.

"There is probably no person in England to-day better fitted to deal rationally with such a subject."—*British Sanitarian*.

In Handsome Cloth. With 59 Illustrations. 6s. net.

## SMOKE ABATEMENT.

*A Manual for the Use of Manufacturers, Inspectors, Medical Officers of  
Health, Engineers, and Others.*

BY WILLIAM NICHOLSON,

Chief Smoke Inspector to the Sheffield Corporation.

"We welcome such an adequate statement on an important subject."—*British Medical Journal*.

SECOND EDITION. In Medium 8vo. Thoroughly Revised and Re-Written.  
15s. net.

## CALCAREOUS CEMENTS:

THEIR NATURE, PREPARATION, AND USES.

With some Remarks upon Cement Testing.

By GILBERT R. REDGRAVE, Assoc. INST. C.E.,

Assistant Secretary for Technology, Board of Education, South Kensington,

AND CHARLES SPACKMAN, F.C.S.

"We can thoroughly recommend it as a first-class investment."—*Practical Engineer*.

In Handsome Cloth. 5s. net.

## A HANDBOOK FOR CEMENT WORKS' CHEMISTS.

By FRANK B. GATEHOUSE, F.C.S.

GENERAL CONTENTS.—Introduction.—Chemicals and Apparatus.—Books.—Analysis and Calculations of Raw Materials.—Analysis of Fuel, Kiln Gases, Lubricants and Water.—Cement Analysis.—Gypsum, Plaster, &c., Burnt Lime.—APPENDICES.—INDEX.

"Concise . . . excellent . . . a useful addition to Cement Literature."—*Concrete*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

With Four Folding Plates and Numerous Illustrations. Large 8vo.  
8s. 6d. net.

## WATER SUPPLY:

*A Practical Treatise on the Selection of Sources and the Distribution of Water.*

By REGINALD E. MIDDLETON, M. INST. C. E., M. INST. MECH. E., F. S. I.

ABRIDGED CONTENTS.—Introductory.—Requirements as to Quality.—Requirements as to Quantity.—Storage Reservoirs.—Purification.—Service Reservoirs.—The Flow of Water through Pipes.—Distributing Systems.—Pumping Machines.—Special Requirements.

"As a companion for the student, and a constant reference for the technical man, we anticipate it will take an important position on the bookshelf."—*Practical Engineer*.

In Large Crown 8vo. Fully Illustrated. In Two Volumes.

VOLUME I. FOURTH EDITION. Price 7s. 6d. net.

,, II. THIRD EDITION. READY SHORTLY.

THE CHEMISTRY OF

## GAS MANUFACTURE:

*A Hand-Book on the Production, Purification, and Testing of Illuminating Gas, and the Assay of the Bye-Products of Gas Manufacture.*

By W. J. ATKINSON BUTTERFIELD, M.A., F.I.C., F.O.S.,

Formerly Head Chemist, Gas Works, Beckton, London, E.

"The BEST WORK of its kind which we have ever had the pleasure of reviewing."—*Journal of Gas Lighting*.

SECOND EDITION, Rewritten. Illustrated. 8s. 6d. net.

## ACETYLENE:

THE PRINCIPLES OF ITS GENERATION AND USE.

By F. H. LEEDS, F.I.C., F.C.S.,

Member of the Society of Public Analysts and of the Acetylene Association;

AND W. J. ATKINSON BUTTERFIELD, M.A., F.I.C., F.C.S.,

Consulting Chemist, Author of "The Chemistry of Gas Manufacture."

"Brimful of information."—*Chem. Trade Journal*.

"We can thoroughly recommend the book to the manufacturer as a reliable work of reference, to the user as supplying valuable hints on apparatus and methods of procedure, and to the student as a safe and certain guide."—*Acetylene*.

Large 8vo. Handsome Cloth. Price 16s. net.

## FIRE AND EXPLOSION RISKS:

*A Handbook of the Detection, Investigation, and Prevention of Fires and Explosions.*

By DR. VON SCHWARTZ.

Translated from the Revised German Edition

By C. T. C. SALTER.

ABRIDGED GENERAL CONTENTS.—Fires and Explosions of a General Character.—Dangers arising from Sources of Light and Heat.—Dangerous Gases.—Risks Attending Special Industries.—Materials Employed.—Agricultural Products.—Fats, Oils, and Resins.—Mineral Oils and Tar.—Alcohol, &c.—Metals, Oxides, Acids, &c.—Lightning Ignition Appliances, Fireworks.

"The work affords a wealth of information on the chemistry of fire and kindred topics."—*Fire and Water*.

"A complete and useful survey of a subject of wide interest and vital importance."—*Oil and Colourman's Journal*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



FIFTEENTH EDITION, Thoroughly Revised. Price 6s.

## **PRACTICAL SANITATION:** **A HAND-BOOK FOR SANITARY INSPECTORS AND OTHERS** **INTERESTED IN SANITATION.**

By **GEORGE REID, M.D., D.P.H.,**

*Fellow, Mem. Council, and Examiner, Sanitary Institute of Great Britain,  
and Medical Officer to the Staffordshire County Council.*

**With an Appendix on Sanitary Law.**

By **HERBERT MANLEY, M.A., M.B., D.P.H.,**  
*Barrister-at-Law.*

**GENERAL CONTENTS.**—Introduction.—Water Supply: Drinking Water, Pollution of Water.—Ventilation and Warming.—Principles of Sewage Removal.—Details of Drainage; Refuse Removal and Disposal.—Sanitary and Insanitary Work and Appliances.—Details of Plumbers' Work.—House Construction.—Infection and Disinfection.—Food, Inspection of; Characteristics of Good Meat; Meat, Milk, Fish, &c., unfit for Human Food.—Appendix: Sanitary Law; Model Bye-Laws, &c.

"A VERY USEFUL HANDBOOK, with a very useful Appendix. We recommend it not only to SANITARY INSPECTORS, but to HOUSEHOLDERS and ALL interested in Sanitary Matters."—*Sanitary Record.*

In Handsome Cloth. With 53 Illustrations. 3s. 6d. net.

## **LESSONS ON SANITATION.**

By **JOHN WM. HARRISON, M.R.SAN.I.,**

*Mem. Incor. Assoc. Mun. and County Engineers; Surveyor, Wombwell, Yorks.*

**CONTENTS.**—Water Supply.—Ventilation.—Drainage.—Sanitary Building Construction.—Infectious Diseases.—Food Inspection.—Duties of an Inspector of Nuisances and Common Lodging-Houses.—Infectious Diseases Acts.—Factory and Workshop Acts.—Housing of the Working-Classes Act.—Shop Hours Acts.—Sale of Food and Drugs Acts.—The Margarine Acts.—Sale of Horseflesh, &c.—Rivers Pollution.—Canal Boats Act.—Diseases of Animals.—Dairies, Cowsheds and Milkshops Order.—Model Bye-Laws.—Miscellaneous.—INDEX.

"Accurate, reliable, and compiled with conciseness and care."—*Sanitary Record.*

SECOND EDITION, Revised. In Crown 8vo. Handsome Cloth. Profusely Illustrated. 8s. 6d. net.

## **SANITARY ENGINEERING:**

**A Practical Manual of Town Drainage and Sewage and Refuse Disposal.**

**For Sanitary Authorities, Engineers, Inspectors, Architects,  
Contractors, and Students.**

By **FRANCIS WOOD, A.M.INST.C.E., F.G.S.,**

*Borough Engineer and Surveyor, Fulham; late Borough Engineer, Bacup, Lancs.*

### **GENERAL CONTENTS.**

Introduction.—Hydraulics.—Velocity of Water in Pipes.—Earth Pressures and Retaining Walls.—Powers.—House Drainage.—Land Drainage.—Sewers.—Separate System.—Sewage Pumping.—Sewer Ventilation.—Drainage Areas.—Sewers, Manholes, &c.—Trade Refuse.—Sewage Disposal Works.—Bacterial Treatment.—Sludge Disposal.—Construction and Cleansing of Sewers.—Refuse Disposal.—Chimneys and Foundations.

The volume bristles with information which will be greedily read by those in need of assistance. The book is one that ought to be on the bookshelves of EVERY PRACTICAL ENGINEER."—*Sanitary Journal.*

"A VERITABLE POCKET COMPENDIUM of Sanitary Engineering. . . . A work which may, in many respects, be considered as COMPLETE . . . COMMENDABLY CAUTIOUS . . . INTERESTING . . . SUGGESTIVE."—*Public Health Engineer.*

LONDON: CHARLES GRIFFIN & CO., LIMITED. EXETER STREET, STRAND.

SECOND EDITION. *In Large 8vo. Handsome Cloth. Beautifully Illustrated. With Plates and Figures in the Text. 21s. net.*

## ROAD MAKING AND MAINTENANCE:

*A Practical Treatise for Engineers, Surveyors, and Others.*

WITH AN HISTORICAL SKETCH OF ANCIENT AND MODERN PRACTICE.

BY THOS. AITKEN, ASSOC. M. INST. C. E.,

Member of the Association of Municipal and County Engineers; Member of the Sanitary Inst.; Surveyor to the County Council of Fife, Cupar Division.

WITH NUMEROUS PLATES, DIAGRAMS, AND ILLUSTRATIONS.

CONTENTS.—Historical Sketch.—Resistance of Traction.—Laying out New Roads.—Earthworks, Drainage, and Retaining Walls.—Road Materials, or Metal.—Quarrying.—Stone Breaking and Haulage.—Road-Rolling and Scarifying.—The Construction of New, and the Maintenance of existing Roads.—Carriage Ways and Foot Ways.

"The Literary style is EXCELLENT. . . . A COMPREHENSIVE and EXCELLENT Modern Book, and UP-TO-DATE work. Should be on the reference shelf of every Municipal and County Engineer or Surveyor in the United Kingdom, and of every Colonial Engineer."—*The Surveyor*.

*In Handsome Cloth. Fully Illustrated. 10s. 6d. net.*

## DUSTLESS ROADS. TAR MACADAM.

BY J. WALKER SMITH,

Borough Engineer and Master of Works, Edinburgh.

CONTENTS.—Necessity for Improved and Standard Road Construction.—Tar.—Standardisation of Matrix.—Aggregate for Macadam.—Different Modes of Preparing and Laying.—Mechanical Mixing.—Effects of Wear, Density, Porosity, Distribution of Weight.—Scavenging: Watering and Maintenance.—Camber: Gradient, Noiselessness, Hygienic Advantages.—Rolling.—Tractive Effort.—Statistics.—Tar Spraying on Ordinary Macadam Surfaces.—APPENDICES.—INDEX.

"The book is in every respect up-to-date and very suggestive. It is written by one who has had unique opportunities for studying the subject, who has made himself master of all its details, and who is not afraid to express his opinions thereon. It is, therefore, practical in the best sense of the term."—*County and Municipal Record*.

*In Demy 8vo. Handsome Cloth. With Many Tables. 6s. net.*

## THE THEORY AND PRACTICE OF ENAMELLING ON IRON AND STEEL.

BY JULES GRÜNWARD,

Technical Chemist and Works' Manager.

CONTENTS.—Introduction.—The Raw Materials.—The Mixing, Dissolving, and Application of Enamel.—Heating and Pickling Goods in the Rough.—Correct laying on.—Baking Enamelled Ware.—Decoration of Enamelled Objects.—Photo-Ceramics in their Application to Enamels.—General and Statistical Chapter.—The History of Enamels and their Uses.—INDEX.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

In Large 8vo. Handsome Cloth. Profusely Illustrated. 30s. net.

## A TREATISE ON COLOUR MANUFACTURE.

A Guide to the Preparation, Examination, and Application of all the Pigment Colours in Practical Use.

BY GEORGE ZERR AND DR. R. RÜBENCAMP.

AUTHORISED ENGLISH TRANSLATION BY DR. C. MAYER, OF BURGDORF.

“This comprehensive guide . . . useful and interesting.”—*Oil and Colour Trades Journal*.

FOURTH EDITION, Revised and Enlarged. With Illustrations. 12s. 6d.

## PAINTERS' COLOURS, OILS, AND VARNISHES:

### A PRACTICAL MANUAL.

BY GEORGE H. HURST, F.C.S.

GENERAL CONTENTS.—Introductory—THE COMPOSITION, MANUFACTURE, ASSAY, and ANALYSIS OF PIGMENTS, White, Red, Yellow and Orange, Green, Blue, Brown, and Black—LAKES—Colour and Paint Machinery—Paint Vehicles (Oils, Turpentine, &c., &c.)—Driers—VARNISHES.

“A THOROUGHLY PRACTICAL book. . . . Satisfactorily treats of the manufacture of oils, colours, and pigments.”—*Chemical Trades' Journal*.

In Crown 8vo. Handsome Cloth. With Illustrations. 5s.

## THE PAINTER'S LABORATORY GUIDE.

A Student's Handbook of Paints, Colours, and Varnishes.

BY GEORGE H. HURST, F.C.S.

ABSTRACT OF CONTENTS.—Preparation of Pigment Colours.—Chemical Principles Involved.—Oils and Varnishes.—Properties of Oils and Varnishes.—Tests and Experiments.—Plants, Methods, and Machinery of the Paint and Varnish Manufactures.

“This excellent handbook, . . . the model of what a handbook should be.”—*Oils, Colours, and Drysalteries*.

THIRD EDITION, Revised. In Crown 8vo. extra. With Numerous Illustrations and Plates (some in Colours), including Original Designs. 12s. 6d.

## Painting and Decorating:

*A Complete Practical Manual for House  
Painters and Decorators.*

BY WALTER JOHN PEARCE,

LECTURER AT THE MANCHESTER TECHNICAL SCHOOL FOR HOUSE-PAINTING AND DECORATING.

“A THOROUGHLY USEFUL BOOK . . . GOOD, SOUND, PRACTICAL INFORMATION in a CLEAR and CONCISE FORM.”—*Plumber and Decorator*.

“A THOROUGHLY GOOD AND RELIABLE TEXT-BOOK. . . . So FULL and COMPLETE that it would be difficult to imagine how anything further could be added about the Painter's craft.”—*Builders' Journal*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



THIRD EDITION. In Large 8vo. Handsome Cloth. With 4 Plates and Several Illustrations. 16s. net.

## THE CHEMISTRY OF INDIA RUBBER.

Treatise on the Nature of India Rubber, its Chemical and Physical Examination, and the Determination and Valuation of India Rubber Substitutes.

*Including the Outlines of a Theory on Vulcanisation.*

By CARL OTTO WEBER, PH.D.

"Replete with scientific and also with technical interest. . . . The section on physical properties is a complete *résumé* of every thing known on the subject."—*India-rubber Journal*.

In Handsome Cloth. Fully Illustrated. 10s. 6d. net.

## THE MANUFACTURE OF RUBBER GOODS.

By ADOLF HEIL AND DR. W. ESCH.

TRANSLATED BY EDWARD W. LEWIS, A.C.G.I., F.C.S.,

Chemist to Messrs. J. G. INGRAM & SON, London.

GENERAL CONTENTS.—Raw Material and its Preparation.—Vulcanisation.—Rubber Mixings.—Manufacture of Soft Rubber Goods.—Manufacture of Hard Rubber Goods.—Regeneration of Waste Rubber.—Specific Gravity of Rubber Goods.—INDEX.

"Can be recommended as a very practical and useful work."—*Nature*.

In Large Crown 8vo. Fully Illustrated. 5s. net.

## GLUE, GELATINE, AND THEIR ALLIED PRODUCTS,

*A Practical Handbook for the Manufacturer, Agriculturist, and Student of Technology.*

By THOMAS LAMBERT,

Analytical and Technical Chemist.

CONTENTS.—Historical.—GLUE.—GELATINE.—Size and Isinglass.—Treatment of Effluents produced in Glue and Gelatine Making.—Liquid and other Glues, Cements, &c.—Uses of Glue and Gelatine.—Residual Products.—Analysis of Raw and Finished Products.—APPENDIX.—INDEX.

"A sufficient account of modern methods of working, chiefly from a practical standpoint. A book . . . of real value."—*Chemical News*.

In Large 8vo. Handsome Cloth. Fully Illustrated. 15s. net.

## LEATHER TRADES' CHEMISTRY.

*A Practical Manual on the Analysis of Materials and Finished Products.*

By S. R. TROTMAN, M.A., F.I.C.,

Public Analyst for the City of Nottingham, Member of the International Association of Leather Trades' Chemists.

SYNOPSIS OF CONTENTS.—Standard Solutions.—Acids, Alkalies, &c.—Water.—Depilation and Deliming.—Fleshings, &c.—Glue.—Spent Liquors.—Mineral and Vegetable Tanning Agents.—Oils.—Soaps.—Varnishes.—Skin.—Leather.—Dyestuffs.—Degreasing Agents.—Effluents.—GLOSSARY.—INDEX.

"Mr. Trotman has admirably succeeded in his aim. . . . Practically every section of the leather trade chemistry is gone into."—*Leather Trades' Review*.

In Large 8vo. Handsome Cloth. With Plates and Illustrations. 7s. 6d. net.

## THE MANUFACTURE OF INK.

*A Handbook of the Production and Properties of Printing, Writing, and Copying Inks.*

By C. A. MITCHELL, B.A., F.I.C., F.C.S., & T. C. HEPWORTH.

"Thoroughly well arranged . . . and of a genuinely practical order."—*British Printer*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

**THE TEXTILE INDUSTRIES.**

SECOND EDITION, *Thoroughly Revised Throughout. In Two Large Volumes. Handsome Cloth. 45s.*

**A MANUAL OF DYEING:**  
**FOR THE USE OF PRACTICAL DYERS, MANUFACTURERS, STUDENTS,**  
**AND ALL INTERESTED IN THE ART OF DYEING.**

BY  
**E. KNECHT, Ph.D., F.I.C.,**

Head of the Chemistry and Dyeing Department of  
 the Technical School, Manchester; Editor of "The  
 Journal of the Society of Dyers and Colourists;"

**CHR. RAWSON, F.I.C., F.C.S.,**

Late Head of the Chemistry and Dyeing Department  
 of the Technical College, Bradford; Member  
 Council of the Society of Dyers and Colourists;

AND **RICHARD LOEWENTHAL, Ph.D.**

**GENERAL CONTENTS.**—Chemical Technology of the Textile Fabrics—  
 Water—Washing and Bleaching—Acids, Alkalies, Mordants—Natural  
 Colouring Matters—Artificial Organic Colouring Matters—Mineral Colours—  
 Machinery used in Dyeing—Tinctorial Properties of Colouring Matters—  
 Analysis and Valuation of Materials used in Dyeing, &c., &c.

"This authoritative and exhaustive work . . . the MOST COMPLETE we have yet seen  
 on the subject."—*Textile Manufacturer.*

*In Large 8vo, Handsome Cloth. Pp. i-xv + 405. 16s. net.*

**THE SYNTHETIC DYESTUFFS,**

AND

**THE INTERMEDIATE PRODUCTS FROM WHICH THEY ARE DERIVED.**

By **JOHN CANNELL CAIN, D.Sc. (MANCHESTER AND TUBINGEN),**  
 Technical Chemist,

AND **JOCELYN FIELD THORPE, Ph.D. (HEIDELBERG), F.R.S.,**  
 Lecturer on Colouring Matters in the Victoria University of Manchester.

**Part I. Theoretical. Part II. Practical. Part III. Analytical.**

"We have no hesitation in describing this treatise as one of the most valuable books  
 that has appeared. . . . Will give an impetus to the study of Organic Chemistry  
 generally."—*Chemical Trade Journal.*

*Companion Volume to Knecht & Rawson's "Dyeing." In Large 8vo.  
 Handsome Cloth, Library Style. 16s. net.*

**A DICTIONARY OF**

**DYES, MORDANTS, & OTHER COMPOUNDS**  
**USED IN DYEING AND CALICO PRINTING.**

*With Formulae, Properties, and Applications of the various substances described  
 and concise directions for their Commercial Valuation,  
 and for the Detection of Adulterants.*

By **CHRISTOPHER RAWSON, F.I.C., F.C.S.,**

Consulting Chemist to the Behar Indigo Planters' Association; Co-Author of "A Manual  
 of Dyeing;"

**WALTER M. GARDNER, F.C.S.,**

Head of the Department of Chemistry and Dyeing, Bradford Municipal Technical College;  
 Editor of the "Journ. Soc. Dyers and Colourists;"

AND **W. F. LAYCOCK, Ph.D., F.C.S.,**

Analytical and Consulting Chemist.

"Turn to the book as one may on any subject, or any substance in connection with the  
 trade, and a reference is sure to be found. The authors have apparently left nothing out."  
 —*Textile Mercury.*

**LONDON: CHARLES GRIFFIN & CO., LIMITED. EXETER STREET, STRAND.**

In Crown 8vo. Cloth. With Numerous Illustrations. 6s. net.

## THE COTTON WEAVERS' HANDBOOK.

*A Practical Guide to the Construction and Costing of Cotton Fabrics, with Studies in Design.*

By HENRY B. HEYLIN,

Of the Royal Technical Institute, Salford.

CONTENTS.—Weaving.—Designing.—Weaves.—The Power Loom and its Accessories.—Analysing or Dissection of the Cloth.—Cloth Quoting or Costing.—Division of the Cotton Industry in England.—Yarns for Manufacturing Purposes.—The Selection of Warp Yarns and Yarn Testing.—Read and Head Counting and Calculations.—Important Labour Units in a Weaving Mill.—Miscellany.—Illustrations of Machinery.—Examination Questions.—INDEX.

"Mr. Heylin's text-book is a very reliable one. It is difficult to mark out any special points among so much excellent matter."—*Dyer and Calico Printer.*

Large 8vo. Profusely Illustrated with Plates and Figures in the Text.  
16s. net.

## THE SPINNING AND TWISTING OF LONG VEGETABLE FIBRES

(FLAX, HEMP, JUTE, TOW, & RAMIE).

*A Practical Manual of the most Modern Methods as applied to the Hackling, Carding Preparing, Spinning, and Twisting of the Long Vegetable Fibres of Commerce.*

By HERBERT R. CARTER, Belfast and Lille.

GENERAL CONTENTS.—Long Vegetable Fibres of Commerce.—Rise and Growth of the Spinning Industry.—Raw Fibre Markets.—Purchasing Raw Material.—Storing and Preliminary Operations.—Hackling.—Sorting.—Preparing.—Tow Carding and Mixing.—Tow Combing.—Gill Spinning.—The Roving Frame.—Dry and Demi-sec Spinning.—Wet Spinning.—Spinning Waste.—Yarn Reeling.—Manufacture of Threads, Twines, and Cords.—Rope Making.—The Mechanical Department.—Modern Mill Construction.—Steam and Water Power.—Power Transmission.

"Meets the requirements of the Mill Manager or Advanced Student in a manner perhaps more than satisfactory. . . . We must highly commend the work as representing up-to-date practice."—*Nature.*

In Large 8vo, Handsome Cloth, with Numerous Illustrations. 9s. net.

## TEXTILE FIBRES OF COMMERCE.

A HANDBOOK OF

The Occurrence, Distribution, Preparation, and Industrial Uses of the Animal, Vegetable, and Mineral Products used in Spinning and Weaving.

By WILLIAM I. HANNAN,

Lecturer on Botany at the Ashton Municipal Technical School, Lecturer on Cotton Spinning at the Chorley Science and Art School, &c.

"USEFUL INFORMATION. . . . ADMIRABLE ILLUSTRATIONS. . . ."—*Textile Recorder.*

In Large 8vo, with Illustrations and Printed Patterns. Price 21s.

## TEXTILE PRINTING: A PRACTICAL MANUAL.

Including the Processes Used in the Printing of  
COTTON, WOOLLEN, SILK, and HALF-SILK FABRICS.

By C. F. SEYMOUR ROTHWELL, F.C.S.,

*Mem. Soc. of Chem. Ind.; late Lecturer at the Munic. Tech. School, Manchester.*

"BY FAR THE BEST AND MOST PRACTICAL BOOK ON TEXTILE PRINTING which has yet been brought out, and will long remain the standard work on the subject."—*Textile Mercury.*

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



Large 8vo. Handsome Cloth. 12s. 6d.

## BLEACHING & CALICO-PRINTING.

A Short Manual for Students and  
Practical Men.

By GEORGE DUERR,

Director of the Bleaching, Dyeing, and Printing Department at the Accrington and Bacup  
Technical Schools; Chemist and Colourist at the Irwell Print Works.

ASSISTED BY WILLIAM TURNBULL

(of Turnbull & Stockdale, Limited).

With Illustrations and upwards of One Hundred Dyed and Printed Patterns  
designed specially to show various Stages of the Processes described.

GENERAL CONTENTS.—COTTON, Composition of; BLEACHING, New Processes; PRINTING, Hand-Block; Flat-Press Work; Machine Printing—MORDANTS—STYLES OF CALICO-PRINTING: The Dyed or Madder Style, Resist Padded Style, Discharge and Extract Style, Chromed or Raised Colours, Insoluble Colours, &c.—Thickeners—Natural Organic Colouring Matters—Tannin Matters—Oils, Soaps, Solvents—Organic Acids—Salts—Mineral Colours—Coal Tar Colours—Dyeing—Water, Softening of—Theory of Colours—Weights and Measures, &c.

"When a READY WAY out of a difficulty is wanted, it is IN BOOKS LIKE THIS that it is found."—*Textile Recorder*.

"MR. DUERR'S WORK will be found MOST USEFUL . . . The information given is of GREAT VALUE . . . The Recipes are THOROUGHLY PRACTICAL."—*Textile Manufacturer*.

SECOND EDITION, with New Appendix. In Handsome Cloth.

With 76 Illustrations. 5s. net.

## DYEING AND CLEANING.

By FRANK J. FARRELL, M.Sc., &c.

GENERAL CONTENTS.—Technology of the Textile Fibres.—Dry Cleaning.—Wet Cleaning.—Dyeing.—Dry Dyeing.—Special Methods, Cleaning and Dyeing Skin Rugs, Feathers, and Hats.—Finishing.—APPENDICES.—INDEX.

"A timely and valuable contribution . . . well got up in every way."—*Dyer and Calico Printer*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

THIRD EDITION, Revised, Enlarged, and Re-issued. Price 6s. net.

## A SHORT MANUAL OF INORGANIC CHEMISTRY.

By A. DUPRÉ, Ph.D., F.R.S.,  
AND WILSON HAKE, Ph.D., F.I.C., F.C.S.,  
Of the Westminster Hospital Medical School.

"AN EXAMPLE OF THE ADVANTAGES OF THE SYSTEMATIC TREATMENT of a Science over the fragmentary style so generally followed. BY A LONG WAY THE BEST of the small Manuals for Students."—*Analyst*.

In Handsome Cloth. With nearly 50 Illustrations. 3s. 6d. net.

## THE ELEMENTS OF CHEMICAL ENGINEERING.

By J. GROSSMANN, M.A., Ph.D., F.I.C.

WITH A PREFACE BY

SIR WILLIAM RAMSAY, K.C.B., F.R.S.

CONTENTS.—The Beaker and its Technical Equivalents.—Distilling Flasks, Liebig's Condensers.—Fractionating Tubes and their Technical Equivalents.—The Air-Bath and its Technical Equivalents.—The Blowpipe and Crucible and their Technical Equivalents.—The Steam Boiler and other Sources of Power.—General Remarks on the Application of Heat in Chemical Engineering.—The Funnel and its Technical Equivalents.—The Mortar and its Technical Equivalents.—Measuring Instruments and their Technical Equivalents.—Materials Used in Chemical Engineering and their Mode of Application.—Technical Research and the Designing of Plant.—Conclusion.—Chemicals and Materials.—INDEX.

"Excellent. . . . Every student of chemistry attending a technical course should obtain a copy."—*Chemical News*.

## LABORATORY HANDBOOKS BY A. HUMBOLDT SEXTON,

Professor of Metallurgy in the Glasgow and West of Scotland Technical College.

### OUTLINES OF QUANTITATIVE ANALYSIS.

FOR THE USE OF STUDENTS.

With Illustrations. FIFTH EDITION. Crown 8vo, Cloth, 3s.

"A COMPACT LABORATORY GUIDE for beginners was wanted, and the want has been WELL SUPPLIED. . . . A good and useful book."—*Lancet*.

### OUTLINES OF QUALITATIVE ANALYSIS.

FOR THE USE OF STUDENTS.

With Illustrations. FOURTH EDITION, Revised. Crown 8vo, Cloth, 3s. 6d.

"The work of a thoroughly practical chemist."—*British Medical Journal*.

"Compiled with great care, and will supply a want."—*Journal of Education*.

## ELEMENTARY METALLURGY:

Including the Author's Practical Laboratory Course.

[See p. 51.]

LONDON: CHARLES GRIFFIN & CO., LIMITED. EXETER STREET. STRAND.

THIRD EDITION, Revised and Enlarged. Large Crown 8vo, with numerous Illustrations. 3s. 6d.

## THE FLOWERING PLANT,

WITH A SUPPLEMENTARY CHAPTER ON FERNS AND MOSSES.  
As Illustrating the First Principles of Botany.

By J. R. AINSWORTH DAVIS, M.A., F.Z.S.,  
Prof. of Biology, University College, Aberystwyth; Examiner in Zoology,  
University of Aberdeen.

"It would be hard to find a Text-book which would better guide the student to an accurate knowledge of modern discoveries in Botany. . . . The SCIENTIFIC ACCURACY of statement, and the concise exposition of FIRST PRINCIPLES make it valuable for educational purposes. In the chapter on the Physiology of Flowers, an *admirable résumé*, drawn from Darwin, Hermann Müller, Kerner, and Lubbock, of what is known of the Fertilization of Flowers, is given."—*Journal of Botany*.

POPULAR WORKS ON BOTANY BY MRS. HUGHES-GIBB.

With Illustrations. Crown 8vo. Cloth. 2s. 6d.

## HOW PLANTS LIVE AND WORK:

A Simple Introduction to Real Life in the Plant-world, Based on Lessons originally given to Country Children.

By ELEANOR HUGHES-GIBB.

\*.\* The attention of all interested in the Scientific Training of the Young is requested to this DELIGHTFULLY FRESH and CHARMING LITTLE BOOK. It ought to be in the hands of every Mother and Teacher throughout the land.

"The child's attention is first secured, and then, in language SIMPLE, YET SCIENTIFICALLY ACCURATE, the first lessons in plant-life are set before it."—*Natural Science*.

"In every way well calculated to make the study of Botany ATTRACTIVE to the young."—*Scotsman*.

With Illustrations. Crown 8vo. Gilt 2s. 6d.

## THE MAKING OF A DAISY; "WHEAT OUT OF LILIES;"

And other Studies from the Plant World.

*A Popular Introduction to Botany.*

By ELEANOR HUGHES-GIBB,

Author of *How Plants Live and Work*.

"A BRIGHT little introduction to the study of Flowers."—*Journal of Botany*.

"The book will afford real assistance to those who can derive pleasure from the study of Nature in the open. . . . The literary style is commensurate."—*Knowledge*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



"Boys COULD NOT HAVE A MORE ALLURING INTRODUCTION to scientific pursuits than these charming-looking volumes."—Letter to the Publishers from the Headmaster of one of our great Public Schools.

SECOND EDITION, Revised. Handsome Cloth. 6s. net.

## OPEN-AIR STUDIES IN BOTANY:

SKETCHES OF BRITISH WILD FLOWERS  
IN THEIR HOMES.

By R. LLOYD PRAEGER, B.A., M.R.I.A.

Illustrated by Drawings from Nature by S. Rosamond Praeger,  
and Photographs by R. Welch.

GENERAL CONTENTS.—A Daisy-Starred Pasture—Under the Hawthorn:  
—By the River—Along the Shingle—A Fragrant Hedgerow—A Connemara  
Bog—Where the Samphire grows—A Flowery Meadow—Among the Corn  
(a Study in Weeds)—In the Home of the Alpines—A City Rubbish-Heap—  
Glossary.

"A FRESH AND STIMULATING book . . . should take a high place . . . The  
Illustrations are drawn with much skill."—*The Times*.

"BEAUTIFULLY ILLUSTRATED. . . . One of the MOST ACCURATE as well as  
INTERESTING books of the kind we have seen."—*Athenæum*.

"Redolent with the scent of woodland and meadow."—*The Standard*.

With 12 Full-Page Illustrations from Photographs. Cloth.

Second Edition, Revised. 8s. 6d.

## OPEN-AIR STUDIES IN GEOLOGY:

An Introduction to Geology Out-of-doors.

By GRENVILLE A. J. COLE, F.G.S., M.R.I.A.,

Professor of Geology in the Royal College of Science for Ireland,  
and Examiner in the University of London.

GENERAL CONTENTS.—The Materials of the Earth—A Mountain Hollow  
—Down the Valley—Along the Shore—Across the Plains—Dead Volcanoes  
—A Granite Highland—The Annals of the Earth—The Surrey Hills—The  
Folds of the Mountains.

"The FASCINATING 'OPEN-AIR STUDIES' of PROF. COLE give the subject a GLOW OF  
ANIMATION . . . cannot fail to arouse keen interest in geology."—*Geological Magazine*.

"A CHARMING BOOK, beautifully illustrated."—*Athenæum*.

Beautifully Illustrated. With a Frontispiece in Colours, and Numerous  
Specially Drawn Plates by Charles Whympere. 7s. 6d.

## OPEN-AIR STUDIES IN BIRD-LIFE:

SKETCHES OF BRITISH BIRDS IN THEIR HAUNTS.

By CHARLES DIXON.

The Spacious Air.—The Open Fields and Downs.—In the Hedgerows.—On  
Open Heath and Moor.—On the Mountains.—Amongst the Evergreens.—  
Cope and Woodland.—By Stream and Pool.—The Sandy Wastes and Mud-  
flats.—Sea-laved Rocks.—Birds of the Cities.—INDEX.

"Enriched with excellent illustrations. A welcome addition to all libraries."—*West-  
minster Review*.

LONDON: CHARLES GRIFFIN & CO., LIMITED. EXETER STREET, STRAND.

# AN ELEMENTARY TEXT-BOOK OF PHYSICS.

By R. WALLACE STEWART, D.Sc. (LOND.)

In Four Volumes. Crown 8vo. Cloth. Each Fully Illustrated.  
Sold Separately.

VOL. I. Uniform with Vols. II. to IV. and Fully Illustrated.

## GENERAL PHYSICS.

NOW IN THE PRESS. Will be ready very shortly.

VOL. II. JUST PUBLISHED. Profusely Illustrated. 2s. 6d. net.

## SOUND.

CONTENTS. — Simple Harmonic Vibration. — Production of Sound. — Wave Motion. — Propagation of Sound. — Characteristics of Sound. — Reflection and Refraction of Sound. — Velocity of Sound in Air and Water. — Transverse Vibration of Strings. — Longitudinal Vibration of Rods and Columns of Air. — INDEX.

"Should supply the much-felt need of an elementary treatment of this subject . . . distinctly good."—*Nature*.

VOL. III. JUST PUBLISHED. With 142 Illustrations. 3s. 6d.

## LIGHT.

CONTENTS. — Introductory. — Rectilinear Propagation of Light. — Photometry. — Reflection at Plane Surfaces. — Reflection at Spherical Surfaces. — Refraction. — Refraction through Lenses. — Dispersion. — INDEX.

"This elementary treatise resembles Part II. (*Sound*) in its attractiveness . . . the treatment is good . . . excellent diagrams . . . very clear."—*Journ. of Inst. of Teachers in Technical Institutes*.

VOL. IV. JUST PUBLISHED. With 84 Illustrations. 3s. 6d. net.

## HEAT.

CONTENTS. — Introductory. — Thermometry. — Expansion of Solids. — Expansion of Liquids. — Expansion of Gases. — Calorimetry. — Specific Heat. — Liquefaction and Solidification. — Vaporisation and Condensation. — Conduction of Heat. — Convection. — Mechanical Equivalent of Heat. — Radiation. — INDEX.

In Large 8vo. With Bibliography, Illustrations in the Text, and Seven Plates. 12s. 6d.

## THE MEAN DENSITY OF THE EARTH.

An Essay to which the Adams Prize was Adjudged in 1893 in the University of Cambridge.

By J. H. POYNTING, Sc.D., F.R.S.

"Cannot fail to be of great and general interest."—*Athenæum*.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

In Five Volumes. Large 8vo. Sold Separately.

# A TEXT-BOOK OF PHYSICS.

By J. H. POYNTING, Sc.D., F.R.S.,  
Professor of Physics, Birmingham University,

And Sir J. J. THOMSON, M.A., F.R.S.,  
Professor of Experimental Physics in the University of Cambridge.

INTRODUCTORY VOLUME. FIFTH EDITION, Revised. Fully Illustrated.  
10s. 6d.

## PROPERTIES OF MATTER.

CONTENTS.—Gravitation.—The Acceleration of Gravity.—Elasticity.—Stresses and Strains.—Torsion.—Bending of Rods.—Spiral Springs.—Collision.—Compressibility of Liquids.—Pressures and Volumes of Gases.—Thermal Effects Accompanying Strain.—Capillarity.—Surface Tension.—Laplace's Theory of Capillarity.—Diffusion of Liquids.—Diffusion of Gases.—Viscosity of Liquids.—INDEX.

"We regard this book as quite indispensable not merely to teachers but to physicists of every grade above the lowest."—*University Correspondent*.

VOLUME II. FIFTH EDITION. Fully Illustrated. Price 8s. 6d.

## SOUND.

CONTENTS.—The Nature of Sound and its chief Characteristics.—The Velocity of Sound in Air and other Media.—Reflection and Refraction of Sound.—Frequency and Pitch of Notes.—Resonance and Forced Oscillations.—Analysis of Vibrations.—The Transverse Vibrations of Stretched Strings or Wires.—Pipes and other Air Cavities.—Rods.—Plates.—Membranes.—Vibrations maintained by Heat.—Sensitive Flames and Jets.—Musical Sand.—The Superposition of Waves.—INDEX.

"The work . . . may be recommended to anyone desirous of possessing an **UP-TO-DATE STANDARD TREATISE ON ACOUSTICS**."—*Literature*.

VOLUME III. THIRD EDITION, Revised. Fully Illustrated. Price 15s.

## HEAT.

CONTENTS.—Temperature.—Expansion of Solids.—Liquids.—Gases.—Circulation and Convection.—Quantity of Heat; Specific Heat.—Conductivity.—Forms of Energy; Conservation; Mechanical Equivalent of Heat.—The Kinetic Theory.—Change of State; Liquid, Vapour.—Critical Points.—Solids and Liquids.—Atmospheric Conditions.—Radiation.—Theory of Exchanges.—Radiation and Temperature.—Thermodynamics.—Isothermal and Adiabatic Changes.—Thermodynamics of Changes of State, and Solutions.—Thermodynamics of Radiation.—INDEX.

"Well up-to-date, and extremely clear and exact throughout. . . . As clear as it would be possible to make such a text-book."—*Nature*.

Remaining Volumes in Preparation—

**LIGHT; MAGNETISM AND ELECTRICITY.**

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.



Twenty-sixth Annual Issue. Handsome cloth, 7s. 6d.

(To Subscribers, 6s.).

## THE OFFICIAL YEAR-BOOK

OF THE

SCIENTIFIC AND LEARNED SOCIETIES OF GREAT BRITAIN  
AND IRELAND.

COMPILED FROM OFFICIAL SOURCES.

*Comprising (together with other Official Information) LISTS of the PAPERS read during the Session 1908-1909 before all the LEADING SOCIETIES throughout the Kingdom engaged in the following Departments of Research:—*

- |  |   |
|--|---|
| § 1. Science Generally: <i>i.e.</i> , Societies occupying themselves with several Branches of Science, or with Science and Literature jointly. | § 6. Economic Science and Statistics.                   |
| § 2. Mathematics and Physics.  | § 7. Mechanical Science, Engineering, and Architecture. |
| § 3. Chemistry and Photography.  | § 8. Naval and Military Science.                        |
| § 4. Geology, Geography, and Mineralogy.   | § 9. Agriculture and Horticulture.                      |
| § 5. Biology, including Microscopy and Anthropology.   | § 10. Law.  |
|  | § 11. Literature.                                       |
|  | § 12. Psychology.                                       |
|  | § 13. Archæology.                                       |

§ 14. MEDICINE.

"FILLS A VERY REAL WANT."—*Engineering*.

"INDISPENSABLE to any one who may wish to keep himself abreast of the scientific work of the day."—*Edinburgh Medical Journal*.

"THE YEAR-BOOK OF SOCIETIES is a Record which ought to be of the greatest use for the progress of Science."—*Lord Playfair, F.R.S., K.C.B., M.P., Past-President of the British Association*.

"It goes almost without saying that a Handbook of this subject will be in time one of the most generally useful works for the library or the desk."—*The Times*.

"British Societies are now well represented in the 'Year-Book of the Scientific and Learned Societies of Great Britain and Ireland.'"—(Art. "Societies" in New Edition of "Encyclopædia Britannica," vol. xxii.)

Copies of the FIRST ISSUE, giving an Account of the History, Organization, and Conditions of Membership of the various Societies, and forming the groundwork of the Series, may still be had, price 7/6. *Also Copies of the Issues following.*

THE YEAR-BOOK OF SOCIETIES forms a complete INDEX TO THE SCIENTIFIC WORK of the sessional year in the various Departments. It is used as a HANDBOOK in all our great SCIENTIFIC CENTRES, MUSEUMS, and LIBRARIES throughout the Kingdom, and has become an INDISPENSABLE BOOK OF REFERENCE to every one engaged in Scientific Work.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

# ELEMENTARY ENGINEERING WORKS.

In Crown 8vo. Handsome Cloth. With 105 Illustrations. 5s. net.

## MECHANICAL ENGINEERING FOR BEGINNERS.

By R. S. M'LAREN.

CONTENTS.—Materials.—Bolts and Nuts, Studs, Set Screws.—Boilers.—Steam Raising Accessories.—Steam Pipes and Valves.—The Steam Engine.—Power Transmission.—Condensing Plant.—The Steam Turbine.—Electricity.—Hydraulic Machinery.—Gas and Oil Engines.—Strength of Beams, and Useful Information.—INDEX.

"The best of its kind we have seen, and should be in the hands of every apprentice."—*Steamship*.

## PROFESSOR JAMIESON'S INTRODUCTORY MANUALS.

*Crown 8vo. With Illustrations and Examination Papers.*

### STEAM AND THE STEAM ENGINE (Elementary Manual of).

For First-Year Students, forming an Introduction to the Author's larger Work. TWELFTH EDITION, Revised and Enlarged. 3s. 6d.

"Should be in the hands of EVERY engineering apprentice."—*Practical Engineer*.

### MAGNETISM AND ELECTRICITY (Practical Elementary Manual of).

For First-Year Students. With Stud. Inst. C.E. and B. of E. Exam. Questions. EIGHTH EDITION, Revised and Enlarged. 3s. 6d.

"A THOROUGHLY TRUSTWORTHY Text-book. PRACTICAL and clear."—*Nature*.

### APPLIED MECHANICS (Elementary Manual of). For First-Year Students.

With B. of E., C. and G., and Stud. Inst. C.E. Questions. EIGHTH EDITION, Revised and Greatly Enlarged. 3s. 6d.

"The work has VERY HIGH QUALITIES, which may be condensed into the one word CLEAR."—*Science and Art*.

### TEXT-BOOK OF ENGINEERING DRAWING AND DESIGN. By

SIDNEY H. WELLS, WH.Sc. FIFTH EDITION. VOL. I.—Practical Geometry, Plane and Solid, 4s. 6d. VOL. II.—Machine and Engine Drawing and Design, 4s. 6d. The volumes sold separately.

### AN ELEMENTARY TEXT-BOOK OF MECHANICAL DRAWING.

By JOHN E. JAGGER, M.Sc., WH.Sc. Profusely Illustrated.

### HINTS ON STEAM ENGINE DESIGN AND CONSTRUCTION. By

CHARLES HURST. SECOND EDITION. With 32 Illustrations. 1s. 6d. net.

### THERMO-DYNAMIC PRINCIPLES OF ENGINE DESIGN. By LIONEL

HOBBS, R.N., Instructor in Applied Mechanics and Engine Design at the Royal Naval College, Greenwich. 4s. 6d. net.

### PRACTICAL CALCULATIONS FOR ENGINEERS. By C. E. LARARD,

A.M.Inst.C.E., and H.A. GOLDING, A.M.I. Mech.E. SECOND EDITION. 6s. net.

### TELEGRAPH SYSTEMS, and Other Notes. By ARTHUR CROTCH,

of the Engineer-in-Chief's Dept., G.P.O. With 222 Illustrations. 5s. net.

### THEODOLITE SURVEYING AND LEVELLING. By Prof. JAMES

PARK, F.G.S. In Crown 8vo. Cloth. Illustrated. 6s. net.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.

## SCIENTIFIC ROMANCES.

HIS MAJESTY THE KING has most graciously condescended to accept a copy of each of these books.

By JOHN MASTIN, F.S.A.Scot., F.L.S., F.C.S., F.R.A.S.,  
F.R.M.S., F.B.A.

In Crown 8vo. Handsome Cloth. Gilt Lettering. Price 6s.

### THROUGH THE SUN IN AN AIRSHIP.

A THRILLING SCIENTIFIC ROMANCE.

"An immense display of resource and knowledge on the part of the author . . . the adventures and discoveries are well worth following."—*Times Literary Supplement*.

"Mr. Mastin manages to make his tale absorbing at all points, the interest never slackens, his imagination never fails. The suggestions opened out are numerous and appalling. Some of the discussions are on very deep subjects, and though they do not lead us far, and are hardly as illuminating as the utterances of poets, they are put down soberly and in a convincing manner, which shows that the author takes his work seriously. His scientific knowledge aids him well in his task, and has enabled him produce a fine novel as attractive to boys as to grown up people."—*Daily Telegraph*.

COMPANION VOLUME TO THE ABOVE.

In Crown 8vo. Uniform with the above. Price 3s. 6d.

### THE STOLEN PLANET.

SOME PRESS OPINIONS OF THIS.

"Certain it is that the reading of this capital story will prove exciting, for compared with the adventures therein written, the books of Jules Verne and H. G. Wells read like the placid pages of Miss Austen's novels."—*Daily Telegraph*.

"Mr. Mastin's ingenious and engaging fantasy . . . he is to be commended for resource, ingenuity, and persistent vigour of narrative."—*Glasgow Herald*.

"It is a graphic and exciting tale."—*Times*.

THE ADVENTURES OF A SOUTH POLAR EXPEDITION

In Crown 8vo. Handsome Cloth. Price 6s.

### THE IMMORTAL LIGHT.


PRESS OPINIONS.

'More daring than Poe's 'Narrative of Arthur Gordon Pym of Nantucket' is Mr. Mastin's romance of Antarctic adventure; for Poe, having introduced a giant 'of the perfect whiteness of the snow,' regrets the loss of his crowning chapters. Certainly, if the matter which they contained 'relative to the Pole itself, or at least to regions in its very near proximity,' was as sensational as 'The Immortal Light,' the loss is deplorable. . . . The story is wildly improbable, but confronts incredulity with a considerable display of scientific detail. A strong religious feeling animates the last part of the book.'—*Athenæum*.

These three volumes are uniform in size and binding.

LONDON: CHARLES GRIFFIN & CO., LIMITED, EXETER STREET, STRAND.







UNIVERSITY OF TORONTO  
LIBRARY

---

Do not  
remove  
the card  
from this  
Pocket.

---

Acme Library Card Pocket

Under Pat. "Ref. Index File."

Made by LIBRARY BUREAU, Boston

DATE.

ing on iron and steel.



